

**LOCATION 4**  
**US 50 & IL 33/1900E - LAWRENCE COUNTY**

**USE DETAIL "C" (EB EXIT RAMP)**  
**USE DETAIL "A" (WB EXIT RAMP)**

**SIGNS**

| SIGN TYPES BY LOCATION                            | UNITS | EB EXIT RAMP | WB EXIT RAMP |
|---|-------|--------------|--------------|
| FREEWAY ENTRANCE (D13-3) 48" x 30"                | EACH  | 0            | 0            |
| DIRECTIONAL ARROW (M6-2a) 21" x 15"               | EACH  | 0            | 0            |
| STOP SIGN (R1-1) 48" x 48"                        | EACH  | 2            | 3            |
| NO RIGHT TURN (R3-1) 36" x 36"                    | EACH  | 1            | 1            |
| NO LEFT TURN (R3-2) 36" x 36"                     | EACH  | 2            | 2            |
| KEEP RIGHT (R4-7) 40" x 60"                       | EACH  | 0            | 0            |
| DO NOT ENTER (R5-1) 36" x 36"                     | EACH  | 0            | 1            |
| DO NOT ENTER (R5-1) 48" x 48"                     | EACH  | 2            | 2            |
| WRONG WAY (R5-1a) 42" x 30"                       | EACH  | 4            | 4            |
| ONE WAY (R6-1 - LEFT) 54" x 18"                   | EACH  | 2            | 3            |
| ONE WAY (R6-1 - RIGHT) 54" x 18"                  | EACH  | 2            | 3            |
| RETROREFLECTIVE SIGN SUPPORT PANEL (RED) 2" x 60" | EACH  | 6            | 7            |
| CHEVRON (W1-8 - YELLOW) 30" x 36"                 | EACH  | 8            | 7            |

**BILL OF MATERIALS**

| PAY ITEM DESCRIPTION                                     | UNITS | EB EXIT RAMP | WB EXIT RAMP |
|--|-------|--------------|--------------|
| SIGN PANEL - TYPE 1                                      | SQ FT | 140.5        | 149.6        |
| SIGN PANEL - TYPE 2                                      | SQ FT | 64.0         | 80.0         |
| REMOVE SIGN PANEL - TYPE 1                               | SQ FT | 49.0         | 59.5         |
| REMOVE SIGN PANEL - TYPE 2                               | SQ FT | 0.0          | 0.0          |
| RELOCATE SIGN PANEL - TYPE 1                             | SQ FT | 0.0          | 8.2          |
| RELOCATE SIGN PANEL - TYPE 2                             | SQ FT | 0.0          | 0.0          |
| WOOD SIGN SUPPORT  | FOOT  | 284.0        | 284.0        |
| REMOVE GROUND MOUNTED SIGN SUPPORT                       | EACH  | 6.0          | 6.0          |
| THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS     | SQ FT | 39.9         | 55.5         |
| THERMOPLASTIC PAVEMENT MARKING - LINE 4"                 | FOOT  | 0.0          | 0.0          |
| THERMOPLASTIC PAVEMENT MARKING - LINE 8"                 | FOOT  | 0.0          | 150.0        |
| THERMOPLASTIC PAVEMENT MARKING - LINE 12"                | FOOT  | 0.0          | 50.0         |
| THERMOPLASTIC PAVEMENT MARKING - LINE 24"                | FOOT  | 20.0         | 40.0         |
| MODIFIED URETHANE PAVEMENT MARKING - LETTERS AND SYMBOLS | SQ FT | 0.0          | 0.0          |
| MODIFIED URETHANE PAVEMENT MARKING - LINE 4"             | FOOT  | 0.0          | 0.0          |
| MODIFIED URETHANE PAVEMENT MARKING - LINE 8"             | FOOT  | 0.0          | 0.0          |
| MODIFIED URETHANE PAVEMENT MARKING - LINE 12"            | FOOT  | 0.0          | 0.0          |
| MODIFIED URETHANE PAVEMENT MARKING - LINE 24"            | FOOT  | 0.0          | 0.0          |
| PAVEMENT MARKING REMOVAL                                 | SQ FT | 0.0          | 0.0          |
| WOOD SIGN SUPPORT, SPECIAL                               | FOOT  | 0.0          | 0.0          |