

SUMMARY OF QUANTITIES						
				CONSTRUCTION TYPE CODE		
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	0005 ROADWAY	0011 STRUCTURE	0042 TRAINERS
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	1.5	1.5		
40600300	AGGREGATE (PRIME COAT)	TON	3	3		
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	22	22		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	166	166		
40600990	TEMPORARY RAMP	SQ YD	23	23		
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	204	204		
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	97	97		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	20	20		
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	101	101		
44000100	PAVEMENT REMOVAL	SQ YD	228	228		
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	96	96		
44004250	PAVED SHOULDER REMOVAL	SQ YD	73	73		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	95	95		
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1	
50105220	PIPE CULVERT REMOVAL	FOOT	80	80		
50157300	PROTECTIVE SHIELD	SQ YD	78		78	
50200100	STRUCTURE EXCAVATION	CU YD	430		430	
50300100	FLOOR DRAINS	EACH	12		12	
50300225	CONCRETE STRUCTURES	CU YD	250.4		250.4	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	361.8		361.8	
50300260	BRIDGE DECK GROOVING	SQ YD	944		944	
50300300	PROTECTIVE COAT	SQ YD	1172		1172	

• SPECIAL PROVISION

FILE NAME : G:\11\files\110015\05 Plans\Current\SH_Summary-11015.dgn	USER NAME = EBJ	DESIGNED - SEB	REVISED - SEB - 1/16/13	ADAMS COUNTY HIGHWAY DEPARTMENT	FAS 1598 (CH 27 /CANNONBALL ROAD) SUMMARY OF QUANTITIES		RTE.		SECTION	COUNTY	SHEETS	NO.
	DRAWN - EBB	REVISED -	1598				11-00218-00-BR	ADAMS	53	4		
	PLOT SCALE = 20,000' / 1"	CHECKED - SRW	REVISED -				CONTRACT NO. 1598-00					
	PLOT DATE = 1/30/2013	DATE - 6-21-12	REVISED -				ILLINOIS FED. AID PROJECT					
				SCALE:	SHEET NO. 2 OF 4 SHEETS	STA.	TO STA.					