

SUMMARY OF QUANTITIES			
ITEM #	DESCRIPTION	QUANTITY	UNIT
20200100	EARTH EXCAVATION	855	CU YD
20400800	FURNISHED EXCAVATION	100	CU YD
35101400	AGGREGATE BASE COURSE, TYPE B	437	TON
42001200	PAVEMENT FABRIC	243	SQ YD
42001300	PROTECTIVE COAT	6220	SQ YD
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	53236	SQ FT
42400410	PORTLAND CEMENT CONCRETE SIDEWALK 8 INCH	2190	SQ FT
42400800	DETECTABLE WARNINGS	40	SQ FT
50102700	MASONRY REMOVAL	46.0	CU YD
50200100	STRUCTURE EXCAVATION	284.0	CU YD
50300225	CONCRETE STRUCTURES	45.5	CU YD
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	37450	POUND
50700105	TREATED TIMBER	14570	F.B.M.
50700305	HARDWARE	2780	POUND
50800205	REINFORCEMENT BARS, EPOXY COATED	3160	POUND
50900805	PEDESTRIAN RAILING	80	FOOT
50901780	PIPE HANDRAIL	380	FOOT
51500100	NAME PLATES	1	EACH
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE 1	2	EACH
62100530	ANCHOR BOLTS, 1 1/4"	12	EACH
64010302	PRECAST CONCRETE BOX CULVERTS 3' X 2'	43	FOOT
642D0217	PIPE CULVERTS, CLASS D, TYPE 1 12"	12	FOOT
63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	44	FOOT
66400305	CHAIN LINK FENCE, 6'	164	FOOT

Δ SPECIALTY ITEMS

SUMMARY OF QUANTITIES			
ITEM #	DESCRIPTION	QUANTITY	UNIT
67100100	MOBILIZATION	1	L SUM
72000100	SIGN PANEL - TYPE 1	10.8	SQ FT
72900100	METAL POST - TYPE A	26.5	FOOT
78001100	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	5	SQ FT
78001110	PAINT PAVEMENT MARKING - LINE 4"	560	FOOT
X0636100	PARKING BLOCKS	7	EACH
X0325153	MASONRY CLEANING AND TUCKPOINTING	44.5	SQ YD
X2501000	SEEDING, CLASS 2 (SPECIAL)	0.5	ACRE
X2810214	STONE RIPRAP, CLASS A7 (SPECIAL)	82	TON
X6640300	CHAIN LINK FENCE REMOVAL	141	FOOT
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	1	L SUM
Z0001903	STRUCTURAL STEEL REMOVAL	21980	POUND
Z0001905	STRUCTURAL STEEL REPAIR	100	POUND
Z0003618	REMOVAL OF EXISTING TIMBER FLOOR	1	EACH
Z0012755	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	10	SQ FT
Z0031300	JACKING AND CRIBBING	1	L SUM
Z0004002	BOLLARDS	10	EACH
Z0053600	RIVET REMOVAL AND REPLACEMENT	220	EACH
Z0073410	TEMPORARY SUPPORT SYSTEM, LOCATION 1	1	EACH
Z0073420	TEMPORARY SUPPORT SYSTEM, LOCATION 2	1	EACH
LR420021	PORTLAND CEMENT CONCRETE PAVEMENT 6" (SPECIAL)	558	SQ YD
X000309	BOLLARDS, QUICK RELEASE	5	EACH
X2030205	ROCK EXCAVATION (SPECIAL)	256	CU YD