											100% STATE									100% STATE									100% STATE						100% STATE
CODED PAY ITEM NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	0001 ROADWAY		0003 ROADWAY		0004 ROADWAY	0005 ROADWAY		0008 BRIDGE				0028 PATH	0021 LIGHTING		0021 TRAFFIC SIGNALS							0031 LANDSCAPING		0021	0040	0043 UTILITIES		0044
				100% STATE	100% LOCAL	100% STATE	100% LOCAL	100% STATE	100% STATE	100% LOCAL	SN 056-0077	SN 056-0081	SN 056-0079	SN 056-0080		STATE	100% LOCAL	EDGE WOOD DRIVE	HUNT INGTON DRIVE	RAMPS A/B	RAMPS C/D	QUARRY ACCESS	INTERCO NNECT	STATE	100% LOCAL	SAFETY	RETAIN ING WALLS	STATE	100% LOCAL	CREEK RELOCATE
50201122	COFFERDAM (TYPE 2) (LOCATION - 2)	EACH	1											1																	
50300225	CONCRETE STRUCTURES	CU YD	1208.6								226.9	246.2	98.4	96.6													540.5				
50300255	CONCRETE SUPERSTRUCTURE	CU YD	3323								669	706.2	317.7	349.1													1281				
50300260	BRIDGE DECK GROOVING	SQ YD	4699								1587	1705	713	694																	
50300285	FORM LINER TEXTURED SURFACE	SQ FT	38455								6979	4511	1775	3364													21826				
50300300	PROTECTIVE COAT	SQ YD	8559								2033	2142	944	1000													2440				
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1								0.32	0.36	0.15	0.17																	
50500505	STUD SHEAR CONNECTORS	EACH	8084								2130	2400	1020	1095													1439				
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	727260								172230	182220	85610	82150													205040				
50800515	BAR SPLICERS	EACH	452								154	162	68	68																	
50900105	ALUMINUM RAILING, TYPE L	FOOT	715																								715				
51100100	SLOPE WALL 4 INCH	SQ YD	317									317																			
51201800	FURNISHING STEEL PILES HP14X73	FOOT	11115								3900	4080	1599	1536																	
51202305	DRIVING PILES	FOOT	11115								3900	4080	1599	1536																	
51203800	TEST PILE STEEL HP14X73	EACH	8								2	2	2	2																	
51204650	PILE SHOES	EACH	155								52	50	27	26																	
51500100	NAME PLATES	EACH	4								1	1	1	1																	
52000110	PREFORMED JOINT STRIP SEAL	FOOT	462								157	167	70	68																	
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	30								10	10	5	5																	
52100520	ANCHOR BOLTS, 1"	EACH	60								20	20	10	10																	
52100530	ANCHOR BOLTS, 1 1/4"	EACH	60								20	20	10	10																	
542A0253	PIPE CULVERTS, CLASS A, TYPE 1 48"	FOOT	23			23																									
• 54210182	PIPE ELBOW 12"	EACH	6	6																											
• 54210184	PIPE ELBOW 15"	EACH	2	2																											
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	42	41					1																						
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	3	3																											
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	5	5																											

21

• INDICATES SPECIAL PROVISION
△ ITEM TO BE PAID FOR BY ALGONQUIN/LAKE IN THE HILLS FIRE PROTECTION DISTRICT
□ ITEM TO BE PAID FOR BY THE VILLAGE OF ALGONQUIN

FILE NAME = ...\D160F72-sht-summary-04.dgn	USER NAME = ctb	DESIGNED - DTE	REVISED -
		DRAWN - CTB	REVISED -
	PLOT SCALE = 2.0000 '/ in.	CHECKED - GAB	REVISED -
	PLOT DATE = 5/8/2012	DATE - 5/3/2012	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET NO. 4 OF 22 SHEETS | STA. | TO STA.

O.R. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0003	18A-2	MCHENRY	825	9
		CONTRACT NO. 60F72		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		