PERMANENT SIGNING SCHEDULE

STATION / LOCATION		FACING	SIGN NUMBER (MUTCD)	SIZE	SIGN PANEL TYPE 1 (SQ	SIGN PANEL TYPE 2 (SQ	MESSAGE	NUMBER OF POSTS (EACH)	WOODEN SIGN SUPPORT (FOOT)	POST LENGTH TELESCOPING STEEL SIGN SUPPORT (FOOT)	POST LENGTH METAL POST - TYPE A (FOOT)
72+40	LT MED	SE	R5-1	36" X 36"	9.0		DO NOT ENTER	1		16.8	
72+40	LT OUT	SE	R5-1	36" X 36"	9.0		DO NOT ENTER	1		17.3	
74+15	LT MED	SE	R5-1A	36" X 24"	6.0		WRONG WAY	1		15.8	
74+15	LT OUT	SE	R5-1A	36" X 24"	6.0		WRONG WAY	1		16.3	
77+55	LT MED	NW	R3-1100L	24" X 24"	4.0		LEFT TURN LANE	1		17.5	
77+55	LT MED	NW	M6-2L	21" X 15"	2.2		LEFT ARROW				
77+74	LT OUT	NW	SIGN 001	99" X 21"		14.4	BRECKENRIDGE	2		41.5	
77+74	LT OUT	NW	R3-1100R	24" X 24"	4.0		RIGHT TURN LANE				
77+74	LT OUT	NW	M6-2R	21" X 15"	2.2		RIGHT ARROW				
79+74	LT MED	NW	W2-1	36" X 36"	9.0		CROSS ROAD	1		20.0	
79+74	LT MED	NW	SIGN 013	66" X 15"	6.9		ELM ST. / BRECKENRIDGE RD.				
79+74	LT OUT	NW	W2-1	36" X 36"	9.0		CROSS ROAD	1		20.5	
79+74	LT OUT	NW	SIGN 013	66" X 15"	6.9		ELM ST. / BRECKENRIDGE RD.				
123+50	LT OUT	NW	RED FLAG	12" X 12"	1.0		NONE	0		0.0	
123+50	LT MED	NW	RED FLAG	12" X 12"	1.0		NONE	0		0.0	
130+00	LT OUT	NW	RED FLAG	12" X 12"	1.0		NONE	0		0.0	
130+00	LT MED	NW	RED FLAG	12" X 12"	1.0		NONE	0		0.0	
TR 81 (CHRISTIAN COUNTY)											
88+00	RT	WEST	W1-4R	36" X 36"	9.0		REVERSE CURVE	1		19.8	
93+50	RT	WEST	W3-1	36" X 36"	9.0		STOP AHEAD	1		19.8	
99+30	RT	EAST	R6-1L	36" X 12"	3.0		ONE WAY	1		26.0	
99+30	RT	WEST	R6-1R	36" X 12"	3.0		ONE WAY				
99+30	RT	WEST	R1-1	36" X 36"	9.0		STOP				
99+30	RT	WEST	R6-3	24" X 18"	3.0		DIVIDED HIGHWAY CROSSING				
100+71	LT	WEST	R6-1L	36" X 12"	3.0		ONE WAY	1		26.0	
100+71	LT	EAST	R6-1R	36" X 12"	3.0		ONE WAY				
100+71	LT	EAST	R1-1	36" X 36"	9.0		STOP				
100+71	LT	EAST	R6-3	24" X 18"	3.0		DIVIDED HIGHWAY CROSSING				
106+50	LT	EAST	W3-1	36" X 36"	9.0		STOP AHEAD	1		19.8	
TR 73 (CHRISTIAN COUNTY)											
180+00	RT	NW	W1-10L	36" X 36"	9.0		HORIZONTAL ALIGNMENT	1		20.3	
180+00	RT	NW	SIGN 019	51" X 9"	3.2		2050 NORTH RD.				
188+18	LT	SW	W1-7	36" X 18"	4.5		TWO DIRECTION LARGE ARROW	2		28.7	
193+50	RT	WEST	W3-1	36" X 36"	9.0		STOP AHEAD	1		19.8	
199+21	RT	EAST	R6-1L	36" X 12"	3.0		ONE WAY	1		26.0	
199+21	RT	WEST	R6-1R	36" X 12"	3.0		ONE WAY				
199+21	RT	WEST	R1-1	36" X 36"	9.0		STOP				
199+21	RT	WEST	R6-3	24" X 18"	3.0		DIVIDED HIGHWAY CROSSING				
200+79	LT	WEST	R6-1L	36" X 12"	3.0		ONE WAY	1		26.0	
200+79	LT	EAST	R6-1R	36" X 12"	3.0		ONE WAY				
200+79	LT	EAST	R1-1	36" X 36"	9.0		STOP				
200+79	LT	EAST	R6-3	24" X 18"	3.0		DIVIDED HIGHWAY CROSSING				
206+50	LT	EAST	W3-1	36" X 36"	9.0		STOP AHEAD	1		19.8	
TR 73 CONNECTOR (CHRISTIAN COUNTY)											
291+50	RT	WEST	W1-2L	36" X 36"	9.0		CURVE	1		19.8	
294+70	RT	WEST	W3-1	36" X 36"	9.0		STOP AHEAD	1		19.8	
299+65	RT	SW	R1-1	36" X 36"	9.0		STOP	1		18.3	
CH 21 (CHRISTIAN COUNTY)											
393+50	RT	WEST	W3-1	36" X 36"	9.0		STOP AHEAD	1		19.8	
399+18	RT	EAST	R6-1L	36" X 12"	3.0		ONE WAY	1		26.0	
399+18	RT	WEST	R6-1R	36" X 12"	3.0		ONE WAY				
399+18	RT	WEST	R1-1	36" X 36"	9.0		STOP				
399+18	RT	WEST	R6-3	24" X 18"	3.0		DIVIDED HIGHWAY CROSSING				
400+81	LT	WEST	R6-1L	36" X 12"	3.0		ONE WAY	1		26.0	
400+81	LT	EAST	R6-1R	36" X 12"	3.0		ONE WAY				
400+81	LT	EAST	R1-1	36" X 36"	9.0		STOP				
400+81	LT	EAST	R6-3	24" X 18"	3.0		DIVIDED HIGHWAY CROSSING				
406+50	LT	EAST	W3-1	36" X 36"	9.0		STOP AHEAD	1		19.8	
TR 69 (CHRISTIAN COUNTY)											
	RIGHT	WEST	W14-1	36" X 36"	9.0		DEAD END	1		18.3	
	RIGHT	WEST	W8-1108	36" X 36"	9.0		ROAD ENDS 500 FT.	1		18.3	
		WEST	R11-1100	36" X 30"	7.5		ROAD ENDS	2		30.7	
		WEST	E.O.R. RED	18" X 18"	2.3		END OF ROAD				
		WEST	E.O.R. RED	18" X 18"	2.3		END OF ROAD				
		EAST	R11-1100	36" X 30"	7.5		ROAD ENDS	2		30.7	
		EAST	E.O.R. RED	18" X 18"	2.3		END OF ROAD				
		EAST	E.O.R. RED	18" X 18"	2.3		END OF ROAD				
	LEFT	EAST	W8-1108	36" X 36"	9.0		ROAD ENDS 500 FT.	1		18.3	
	LEFT	EAST	W14-1	36" X 36"	9.0		DEAD END	1		18.3	

STATION / LOCATION		FACING	SIGN NUMBER (MUTCD)	SIZE	SIGN PANEL TYPE 1 (SQ	SIGN PANEL TYPE 2 (SQ	MESSAGE	NUMBER OF POSTS (EACH)	WOODEN SIGN SUPPORT (FOOT)	POST LENGTH TELESCOPING STEEL SIGN SUPPORT (FOOT)	POST LENGTH METAL POST - TYPE A (FOOT)
CH 23 (CHRISTIAN COUNTY)											
479+65	LT	NORTH	R1-1	36" X 36"	9.0		STOP	1		18.3	
485+75	LT	NW	W3-1	36" X 36"	9.0		STOP AHEAD	1		19.8	
493+50	RT	SOUTH	W3-1	36" X 36"	9.0		STOP AHEAD	1		19.8	
499+00	LT	NE	R5-2A	24" X 24"	4.0		NO TRUCKS	1		19.8	
499+23	RT	NE	R6-1L	36" X 12"	3.0		ONE WAY	1		26.0	
499+23	RT	SW	R6-1R	36" X 12"	3.0		ONE WAY				
499+23	RT	SW	R1-1	36" X 36"	9.0		STOP				
499+23	RT	SW	R6-3	24" X 18"	3.0		DIVIDED HIGHWAY CROSSING				
500+80	LT	SW	R6-1L	36" X 12"	3.0		ONE WAY	1		26.0	
500+80	LT	NE	R6-1R	36" X 12"	3.0		ONE WAY				
500+80	LT	NE	R1-1	36" X 36"	9.0		STOP				
500+80	LT	NE	R6-3	24" X 18"	3.0		DIVIDED HIGHWAY CROSSING				
502+00	LT	NE	R5-1102	24" X 24"	4.0		CLASS III TRUCK ROUTE	1		21.6	
502+00	LT	NE	M6-1	21" X 15"	2.2		RIGHT ARROW				
506+50	RT	SOUTH	R5-1102	24" X 24"	4.0		CLASS III TRUCK ROUTE	1		17.2	
506+50	LT	NORTH	W3-1	36" X 36"	9.0		STOP AHEAD	1		19.8	
508+50	LT	NORTH	R5-1102	24" X 24"	4.0		CLASS III TRUCK ROUTE	1		17.2	
TR 88 (CHRISTIAN COUNTY)											
581+00	RT	SE	W1-2B	36" X 36"	9.0		CURVE	1		19.8	
582+50	LT	NW	R5-1102	24" X 24"	4.0		CLASS III TRUCK ROUTE	1		17.2	
583+00	RT	SE	R5-1102	24" X 24"	4.0		CLASS III TRUCK ROUTE	1		17.2	
593+50	RT	SW	W3-1	36" X 36"	9.0		STOP AHEAD	1		22.5	
597+50	LT	NE	R5-1102	24" X 24"	4.0		CLASS III TRUCK ROUTE	1		19.8	
598+00	RT	SW	R5-1102	24" X 24"	4.0		CLASS III TRUCK ROUTE	1		21.6	
598+00	RT	SW	M6-1	21" X 15"	2.2		RIGHT ARROW				
599+10	RT	NE	R6-1L	36" X 12"	3.0		ONE WAY	1		26.0	
599+10	RT	SW	R6-1R	36" X 12"	3.0		ONE WAY				
599+10	RT	SW	R1-1	36" X 36"	9.0		STOP				
599+10	RT	SW	R6-3	24" X 18"	3.0		DIVIDED HIGHWAY CROSSING				
600+82	LT	SW	R6-1L	36" X 12"	3.0		ONE WAY	1		26.0	
600+82	LT	NE	R6-1R	36" X 12"	3.0		ONE WAY				
600+82	LT	NE	R1-1	36" X 36"	9.0		STOP				
600+82	LT	NE	R6-3	24" X 18"	3.0		DIVIDED HIGHWAY CROSSING				
607+50	LT	NORTH	W3-1	36" X 36"	9.0		STOP AHEAD	1		19.8	
608+50	LT	NORTH	W1-2R	36" X 36"	9.0		CURVE	1		19.8	
EXIST. IL RTE 29											
94+93.55	LEFT	SW	W1-7	36" X 18"	4.5		TWO DIRECTION LARGE ARROW	2		29.7	
106+67.40	LEFT	SE	R2-1	30" X 36"	7.5		SPEED LIMIT 45	1		18.2	
166+67+91	RIGHT	NW	R2-1	30" X 36"	7.5		SPEED LIMIT 45	1		18.2	
TR63/74 SOUTH (CHRISTIAN COUNTY)											
91+00	RT	SOUTH	W1-2L	36" X 36"	9.0		CURVE	1		19.8	
94+17	RT	SOUTH	W3-1	36" X 36"	9.0		STOP AHEAD	1		19.8	
99+35	RT	SE	R1-1	36" X 36"	9.0		STOP	1		20.3	
99+35	RT	SE	W4-4AP	36" X 18"	4.5		TRAFFIC FROM RIGHT DOES NOT				
100+00	LT	NE	W1-7	48" X 24"	8.0		TWO DIRECTION LARGE ARROW	2		29.7	
100+50	LT	NW	R1-1	36" X 36"	9.0		STOP	1		20.3	
100+50	LT	NW	W4-4AP	36" X 18"	4.5		TRAFFIC FROM LEFT DOES NOT				
105+83	LT	WEST	W3-1	36" X 36"	9.0		STOP AHEAD	1		19.8	
112+00.00	LT	WEST	W1-2R	36" X 36"	9.0		CURVE	1		19.8	
TR63/74 NORTH (CHRISTIAN COUNTY)											
91+00	RT	EAST	W1-2R	36" X 36"	9.0		CURVE	1		19.8	
94+10	RT	EAST	W3-1	36" X 36"	9.0		STOP AHEAD	1		19.8	
99+70	RT	SE	R1-1	36" X 36"	9.0		STOP	1		20.3	
99+70	RT	SE	W4-4AP	36" X 18"	4.5		TRAFFIC FROM LEFT DOES NOT				
100+00	RT	SW	W1-7	48" X 24"	8.0		TWO DIRECTION LARGE ARROW	2		29.7	
100+75	LT	NW	R1-1	36" X 36"	9.0		STOP	1		20.3	
100+75	LT	NW	W4-4AP	36" X 18"	4.5		TRAFFIC FROM RIGHT DOES NOT				
105+90	LT	NORTH	W3-1	36" X 36"	9.0		STOP AHEAD	1		19.8	
109+00	LT	NORTH	W1-2L	36" X 36"	9.0		CURVE	1		19.8	
TR63/74 CONNECTOR (CHRISTIAN COUNTY)											

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
PERMANENT SIGNING

SCALE: N/A — DRAWN BY: K.E.U.
DATE: 03/06/2012 — CHECKED BY: J.M.M.

SH717
L:\DOT\030660\draw\sheets\0672829-sht-Schedule.dgn
3/30/2012