

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
315	55-2	McDONOUGH	1025	41
STA.		TO STA.		
FED. ROAD DIST. NO. 4 ILLINOIS		FED. AID PROJECT		

LOCATION							PIPE CULVERTS, CLASS A, TYPE 1					PIPE CULVERTS, CLASS A, TYPE 2					PIPE CULVERTS, CLASS A, TYPE 3		PRECAST REINFORCED CONCRETE FLARED END SECTIONS						
							18"	24"	30"	48"	54"	18"	24"	30"	36"	48"	18"	60"	18"	24"	30"	36"	48"	54"	60"
							FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	EA	EA	EA	EA	EA	EA	EA	
<b>RAMP I</b>																									
STA. 20+00.00	20.00 FT	RT	TO	STA. 20+00.00	36.00 FT	LT							56								2				
STA. 27+00.00	18.00 FT	RT	TO	STA. 27+00.00	34.00 FT	LT			52													2			
<b>RAMP J</b>																									
STA. 157+00.00	34.00 FT	LT	TO	STA. 157+00.00	18.00 FT	RT			104													2			
STA. 165+00.00	13.00 FT	RT	TO	STA. 165+00.00	28.00 FT	LT															4				
STA. 181+80.00	48.00 FT	RT	TO	STA. 182+21.70	22.80 FT	RT	46		82																
<b>US ROUTE 136 (RELOCATED)</b>																									
STA. 9+50.00	38.00 FT	LT	TO	STA. 9+50.00	36.00 FT	RT			74													2			
<b>SERVICE DRIVE</b>																									
STA. 21+50.00	19.20 FT	RT	TO	STA. 21+50.00	20.50 FT	LT					40										2				
STA. 24+28.00	50.00 FT	RT	TO	STA. 24+62.00	50.00 FT	LT											106						2		
<b>TWP. ROAD 350E</b>																									
STA. 8+70.00	72.50 FT	LT	TO	STA. 8+75.00	42.90 FT	LT									28						1				
STA. 8+75.00	42.90 FT	LT	TO	STA. 8+88.50	38.00 FT	RT					80										1				
<b>TWP. ROAD 118</b>																									
STA. 17+90.00	28.80 FT	LT	TO	STA. 17+90.00	29.20 FT	RT							58									2			
STA. 18+94.00	34.00 FT	LT	TO	STA. 18+94.00	31.00 FT	RT							65									2			
STA. 21+10.00	35.60 FT	LT	TO	STA. 21+10.00	28.40 FT	RT						64									2				
<b>COUNTY HIGHWAY 8 (RELOCATED)/TWP. ROAD 150</b>																									
STA. 26+24.00	50.00 FT	LT	TO	STA. 26+68.00	29.00 FT	RT					132												4		
STA. 35+50.00	20.00 FT	RT	TO	STA. 35+50.00	23.00 FT	LT			86												4				
<b>COUNTY HIGHWAY 8 (EAST)</b>																									
STA. 38+86.00	44.00 FT	LT	TO	STA. 38+90.00	40.00 FT	RT							84								2				
<b>TWP. ROAD 194</b>																									
STA. 49+03.00	35.00 FT	LT	TO	STA. 49+07.00	32.40 FT	RT							68								2				
<b>TWP. ROAD 200 (RELOCATED)</b>																									
STA. 54+03.00	24.00 FT	LT	TO	STA. 54+28.07	30.70 FT	RT																2			
STA. 54+35.00	23.00 FT	LT	TO	STA. 54+35.00	26.00 FT	RT																2			
STA. 58+83.00	73.40 FT	LT	TO	STA. 59+08.00	38.00 FT	RT							110								2				
STA. 60+99.00	38.00 FT	LT	TO	STA. 61+16.00	46.00 FT	RT								83								2			
<b>TWP. ROAD 900N (RELOCATED)</b>																									
STA. 89+48.00	23.00 FT	LT	TO	STA. 89+48.00	37.00 FT	RT																2			
STA. 89+70.00	36.00 FT	LT	TO	STA. 89+53.50	38.00 FT	RT																2			
<b>TWP. ROAD 900N (EAST)</b>																									
STA. 100+50.00	23.00 FT	LT	TO	STA. 100+50.00	21.50 FT	RT	45														2				
<b>TOTAL</b>							91	168	403	74	132	120	234	148	123	83	28	106	6	14	16	4	4	4	2

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SCHEDULE OF QUANTITIES**  
**IL. ROUTE 336**

DATE 3/30/06  
DRAWN BY  
CHECKED BY