FAP ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
314	110-1VBR-1	MADISON	77	8
STA.		TO STA.		
CONTRACT NO.: 76549				

* RESURFACING SCHEDULE

LOCATION	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	BIUTMINOUS CONCRETE PAVEMENT (FULL-DEPTH), TYPE 1 12 3/4"	BIUTMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	PAVEMENT REMOVAL	AGGREGATE SHOULDERS, TYPE A, 6"	BITUMINOUS SHOULDERS SUPERPAVE 8"	AGGREGATE SURFACE COURSE, TYPE B	BIUTMINOUS CONCRETE PAVEMENT (FULL-DEPTH), TYPE 1 10"	AGGREGATE BASE COURSE, TYPE B 8"	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, IL 9.5l (LOW ESAL)	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX C, N70	BITUMINOUS BINDER COURSE, SUPERPAVE, IL-19.0, N70
STATION TO STATION	TON	TON	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	TON	SQ YD	SQ YD	TON	SQ YD	SQ YD
SECTION 110-1VBR-1 SN 060-2406													
STA 491+39.30 TO STA 496+00.00	0.54	2.67	226.7	1251.5	249.0	291.8	285.3					246.0	106.0
STA 496+00.00 TO STA 511+00.00			4,000.0		4,070.0	1,000.0	1,000.0						
STA 511+00.00 TO STA 516+63.34	0.46	2.33	773.3	1427.4	605.0	327.2	325.7	28.2				280.0	120.0
WASTEWATER TREATMENT PLANT SERVICE ROAD (USE MAINLINE STATIONING)													
STA 494+13.08 TO STA 496+00.00					539.0								
STA 496+00.00 TO STA 500+86.29					965.0								
STA 500+86.29 TO STA 516+63.34					0.0								
BIKE TRAIL													
STA 576+22.49 TO STA 577+49.49										181.2	19.0		
STA 577+49.49 TO STA 578+15.99										109.6	11.6		
STA 578+15.99 TO STA 579+32.49										166.2	17.4		
RUN AROUND													
STA 0+76.00 TO STA 3+93.30					875.0			239.1	916.8				
STA 3+93.30 TO STA 19+03.90					2,140.0			434.7	4,364.1				
STA 19+03.90 TO STA 23+46.60					1,284.0				1,279.1				
RECONSTRUCTED SERVICE DRIVE (USE RUNAROUND STATIONING)													
STA 0+00.00 TO STA 3+83.13									871				
STA 11+63.37 TO STA 12+18.52									159				
TOTAL	1	5	5,000	2679	10,727	1,619	1,611	702	7,590	457	48	526	226

* THE BITUMINOUS PRIME COAT FOR THE BIKE TRAIL IS INCLUDED IN THE PRICE OF BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE IL 9.5L (LOW ESAL)

PIPE CULVERT SCHEDULE

STATION	OFFSET	LT/RT	CONCRETE HEADWALL	REINFORCED CONCRETE PIPE ELBOW 30"	PIPE CULVERTS CL A, TYPE 2, 24"	TYPE 2 CORRUGATED STEEL OR ALLUMINUM CULVERT 15"	TEMPORARY		PIPE CULVERT REMOVAL
							PIPE CULVERTS CL A, TYPE 2, 24"	PIPE CULVERTS CL A, TYPE 2, 30"	
	(FOOT)		(CUBIC YARDS)	(EACH)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)
493+61.83	27.1	LT				214			
494+09.86	24.36	LT							42
501+33.73	58.9	LT				40			
503+90.36	102.3	LT			50				
503+91.74	ON MAINLINE								78
503+91.74	38	LT	0.6		78				
504+31.50	38	LT	0.6		78				
504+40.55	ON MAINLINE								78
505+10.95	123.9	LT					114		
512+68.43	58.2	LT		1					
512+68.43	54.6	LT						10	
513+11.89	62.3	LT						76	
515+42.80	29.7	LT						18	
TOTAL:			1.2	1	206	254	114	104	198

GUARDRAIL SCHEDULE

LOCATION	GUARDRAIL REMOVAL FOOT	SPBGR TYA FOOT	TBT TY1 (SPEC) TANG EACH	GUARDRAIL MRKRS, TYA EACH	TERM. MKR DIR. APPL. EACH
STA. 500+08 TO STA. 503+58-LT	350				
STA. 500+08 TO STA. 503+58-RT	350				
STA. 502+95 TO STA. 504+70-LT	175				
STA. 502+95 TO STA. 504+70-RT	175				
STA. 500+12.5-RT			1		1
STA. 500+62.5 TO STA. 506+12.5-RT		550		8	
STA. 506+12.5-RT			1		1
STA. 500+87.5 -LT			1		1
STA. 501+37.5 TO STA. 506+87.5-LT		550		8	
STA. 506+87.5-LT			1		1
STA. 513+89.3-LT			1		1
STA. 514+39.3 TO STA. 518+76.8-LT		437.5		6	
STA. 519+26.8-LT			1		1
STA. 514+63.09-RT			1		1
STA. 515+13.09 TO STA. 519+50.59-RT		437.5		6	
STA. 520+00.59-RT			1		1
TOTAL	1050	1975	8	28	8

EROSION CONTROL SCHEDULE

PAGE	INLET & PIPE PROTECTION (EACH)	TEMP DITCH CHECK (EACH)	PERIMETER EROSION BAR. (FEET)	TEMPORARY SEEDING (ACRE)	TEMP. MULCH METHOD 1 (ACRE)
16	2	8	591	0.25	0.25
17	6	4	3046	1.50	1.50
18	2	1	968	0.50	0.50
19	3	3	467	0.25	0.25
20	7	4	3054	3.75	3.75
21	2	0	841	0.50	0.50
22	0	0	0	0.00	0.00
23	0	0	1308	0.75	0.75
24	2	0	787	0.50	0.50
	24	20	11062	8	8

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES

FAP ROUTE 314 (IL 4)
SECTION 110-1VBR-1
MADISON COUNTY

DRAWN BY:

PLOT DATE: *DATE-TIME*

PLAN | SURVEYED | PLOTTED | ALIGNMENT CHECKED | R/L OF WAY CHECKED | CADD FILE NAME | NOTE BOOK NO. | BY | DATE

SSDATE8
DATE-TIME
SSDB-SPEC
SSDB-
*REV-
*REV-