

F.A.P. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
869	(103)I	SALINE	64	7
STA.		TO STA.		
FED. ROAD DIST. NO. -	ILLINOIS	FED. AID PROJECT		
CONTRACT NO.: 98896				

SURFACING SCHEDULE

LOCATION STATION TO STATION	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N90	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N90	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	GRANULAR EMBANKMENT, SPECIAL	CALCIUM CHLORIDE APPLIED
	TON	TON	GALLON	TON	TON	TON
IL 34						
SALINE COUNTY						
RURAL						
STA 1023+25 TO STA 1024+00	18.3	6.8	20.0	0.3		
STA 1024+00 TO STA 1024+62	15.1	60.6	16.8	0.3		
STA 1024+62 TO STA 1029+66	122.9	375.7	483.8	2.3	3,045.0	7.1
STA 1029+66 TO STA 1030+25	14.4	57.6	16.0	0.3		
STA 1030+25 TO STA 1033+25	73.2	135.9	79.9	1.3		
STA 1033+25 TO STA 1034+02	18.8	75.2	20.9	0.3		
STA 1034+02 TO STA 1046+36	300.9	919.9	1,184.6	5.6	10,683.0	52.5
STA 1046+36 TO STA 1048+25	46.1	184.5	51.3	0.9		
STA 1048+25 TO STA 1049+50	30.5	56.7	33.3	0.6		
STA 1049+50 TO STA 1050+76	30.7	123.0	34.2	0.6		
STA 1050+76 TO STA 1053+73	72.4	221.4	285.1	1.3	614.0	1.4
STA 1053+73 TO STA 1054+95	29.7	119.0	33.1	0.6		
STA 1054+95 TO STA 1056+95	48.8	195.2	54.3	0.9		
STA 1056+95 TO STA 1061+34	107.0	327.3	421.4	2.0	1,218.0	2.0
STA 1061+34 TO STA 1062+00	16.1	64.4	17.9	0.3		
STA 1062+00 TO STA 1063+50	37.1	40.8	40.4	0.7		
			67.0	0.3		
FROM ENTRANCE SCHEDULE						
FROM DRAINAGE SCHEDULE					272.0	
PROJECT TOTALS:	982.0	2,964.0	2,860.0	18.6	15,832.0	63.0

DATE: 1986 FEBRUARY 4, 1986
DRAWN: SPEC-4893502, 09/05/82 chm32