

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE						SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005						CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	334	334						70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	301	301					
25200110	SODDING, SALT TOLERANT	SQ YD	334	334						* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	616	616					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	24	24						* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	10809	10809					
40600300	AGGREGATE (PRIME COAT)	TON	104	104						* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1252	1252					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	117	117						* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	422	422					
40600895	CONSTRUCTING TEST STRIP	EACH	2	2						* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	70	70					
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	1949	1949						* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	507	507					
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	206	206						* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	225	225					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2312	2312						78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	180	180					
42001300	PROTECTIVE COAT	SQ YD	446	446						* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	1442	1442					
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SQ FT	2176	2176						X4060826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1105	1105					
44022029	PARTIAL DEPTH REMOVAL 3"	SQ YD	1202	1202						X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	5129	5129					
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	619	619						Δ X5539700	STORM SEWERS TO BE CLEANED	FOOT	300	300					
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	145	145						Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	2000	2000					
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	313	313						Δ Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	18	18					
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	3	3						Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4					
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	3	3						Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1					
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	15	15						70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	30	30						70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1					
60404940	FRAMES AND GRATES, TYPE 23	EACH	12	12															
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6															
67100100	MOBILIZATION	L SUM	1	1															
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1															
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1															
70300100	SHORT TERM PAVEMENT MARKING	FOOT	1800	1800															
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	616	616															
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	10809	10809															
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1252	1252															
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	422	422															
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	70	70															
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	507	507															
										Δ NON-PARTICIPATING (100% STATE) * SPECIALTY ITEMS									
										Rev. 6-3-11									
STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION										IL 171 - 1st AVE. FRONTAGE ROAD (JOLIET RD. TO 47TH ST.) SUMMARY OF QUANTITIES									
FILE NAME * USER NAME * DESIGNED - REVISED - DRAWN - REVISED - PLOT SCALE = 50,000.0' / IN. PLOT DATE = 4/7/2011										SCALE: SHEET NO. OF SHEETS STA. TO STA. F.A.P. RTE. SECTION COUNTY TOTAL SHEETS SHEET NO. 372 2010-155-RS COOK 27 3 FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT CONTRACT NO. 60N59									