

ROUTE: IL 59 (Batavia Rd to N. Aurora Rd)

CROSS STREETS		DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
FROM	TO						
Batavia	Meadow	SB	1	12	12	144	16
		SB	2	12	12	144	16
		SB	1	12	8	96	11
		SB	1	12	8	96	11
Meadow	IL 56	SB	2	12	20	240	27
			1	12	10	120	13
			1	12	10	120	13
			2	12	8	96	11
IL-56	Ferry	SB	1	12	10	120	13
			1	12	10	120	13
Diehl	Bruce	SB	1	12	20	240	27
			1	12	20	240	27
Bruce	N. Aurora	SB	1	12	8	96	11
			1	12	8	96	11
			1	12	8	96	11
			1	12	6	72	8
			1	12	6	72	8
N. Aurora	Brookdale	NB	1	12	10	120	13
			2	12	10	120	13
Brookdale	Diehl	NB	1	12	10	120	13
			2	12	10	120	13
I-88	Ferry	NB	1	12	20	240	27
			1	12	20	240	27
			2	12	10	120	13
			2	12	12	144	16
Ferry	IL 56	NB	2	12	20	240	27
			2	12	20	240	27
			1	12	8	96	11
IL 56	Meadow	NB	1	12	10	120	13
			1	12	10	120	13
			1	12	10	120	13
			2	12	50	600	67
			2	12	30	360	40
			2	12	40	480	53
Meadow	Batavia	NB	1	12	12	144	16
			2	12	10	120	13
			1	12	10	120	13
			2	12	10	120	13

TOTALS:	526	702
	FT	SY

ROUTE: IL 59 (US 34 to N. Aurora Rd)

CROSSSTREETS		DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
FROM	TO						
Liberty	New York	SB	1	12	30	360	40
			2	12	100	1200	133
			2	12	20	240	27
New York	Jefferson	NB	1	12	10	120	13
			3	12	50	600	67
			2	12	10	120	13

TOTALS:	220	294
	FT	SY

ROUTE: IL 64 (w/o Swift Rd @ asphalt concrete transition joint)

CROSSSTREETS		DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
FROM	TO						
IL 64 w/o Swift Rd @ Jt		WB	1	12	6	72	8
		WB	2	12	6	72	8
		WB	3	12	6	72	8
		WB	4	12	6	72	8
						0	0
		EB	1	12	6	72	8
	IL 64 w/o Swift Rd @ Jt	EB	LTL	12	6	72	8

TOTALS:	36	48
	FT	SY

FILE NAME =	USER NAME = VelichkovVV	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PATCHING SCHEDULE IL 59 & IL 64				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pw-work\pwsdot\velichkovvv\d0260183\Design.dgn		DRAWN -	REVISED -		VAR.	2011-010-RS	DUPAGE	37	17				
PLOT SCALE = 100.0000' / IN.		CHECKED -	REVISED -		CONTRACT NO. 60N98								
PLOT DATE = 4/13/2011		DATE -	REVISED -		SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.	FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT	