



- NOTES:
1. CLASS D PATCHES, 9" AS SHOWN ON THE PLANS AND AS DIRECTED BY ENGINEER.
 2. MORE QUANTITY IS INCLUDED FOR CLASS D PATCHES, 9" THAN IS SHOWN ON THE PLANS, THE REMAINING QUANTITY SHALL BE USED AT THE DIRECTION OF THE ENGINEER.
 3. REMOVAL AND DISPOSAL OF THE MATERIAL UNDER THE PROPOSED CURB AND GUTTER IN ORDER TO INSTALL THE PROPOSED SUB-BASE GRANULAR MATERIAL, TY B 4" SHALL BE CONSIDERED INCLUDED IN THE COST OF COMB CURB AND GUTTER REMOVAL.
 4. IF UNSUITABLE MATERIAL IS ENCOUNTERED UNDER THE EXISTING DRIVEWAYS, A 4" DEPTH OF THE MATERIAL SHALL BE REMOVED AND DISPOSED OF AND PAID FOR AS REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL. SUB-BASE GRANULAR MATERIAL SHALL BE INSTALLED IN ITS PLACE AND SHALL BE PAID FOR AS SUB-BASE GRANULAR MATERIAL, TYPE B 4".
 5. THE ADJUSTMENT OF THE DRAINAGE STRUCTURES IN THE CURB AND GUTTER LINE SHALL BE PAID FOR AS DRAINAGE STRUCTURES TO BE ADJUSTED. THE ADJUSTMENT AND REPAIR OF THE DRAINAGE STRUCTURES IN THE CURB AND GUTTER LINE SHALL BE PAID FOR AS DRAINAGE STRUCTURES TO BE RECONSTRUCTED.

LEGEND

[Symbol]	DRAINAGE STRUCTURE TO BE ADJUSTED
[Symbol]	DRAINAGE STRUCTURE TO BE RECONSTRUCTED
[Symbol]	FRAMES AND LIDS TO BE ADJUSTED, SPECIAL
[Symbol]	NEW FRAME & GRATE, TYPE IIV
[Symbol]	NEW FRAME & LID, TYPE I, CLOSED LID
[Symbol]	FACE OF CURB
[Symbol]	FACE OF SIDEWALK
[Symbol]	VALVE BOX TO BE ADJUSTED
[Symbol]	PAVEMENT PATCHING (CLASS D PATCHES, 9" UNLESS OTHERWISE NOTED)
[Symbol]	TREE PROTECTION
[Symbol]	TREE REMOVAL
[Symbol]	SHRUB REMOVAL
[Symbol]	SODDING, SALT TOLERANT TOPSOIL FURNISH AND PLACE, 6"

FILE NAME = g:\odp\2056\oad\shets\VP-283.dwt	USER NAME = ajpandexter	DESIGNED - KB	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	WEST AVENUE IMPROVEMENT PLAN			F.A.U. RTE. 2659	SECTION 1-00:77-00-RS	COUNTY DUPAGE	TOTAL SHEETS 21	SHEET NO. 7
		DRAWN - AJP	REVISED -		SCALE: 1"=50'	SHEET NO. 3 OF 3 SHEETS	STA. 155+00 TO STA. 181+55	CONTRACT NO. 63585				
		CHECKED - ESN	REVISED -									
		DATE - 3/28/2011	REVISED -									