

SCHEDULE OF QUANTITIES
TABULATION OF CLASS A PATCH, 14"
I-57 MAINLINE (SOUTHBOUND)

STATION	LOCATION	LANE	LENGTH	WIDTH	TYPE I	TYPE II	TYPE III	TYPE IV	SAWCUTS	TIE BARS, 3/4"	PATCHING REINFORCEMENT
			(FT)	(FT)	44200616 (SQ. YD.)	44200620 (SQ. YD.)	44200624 (SQ. YD.)	44200628 (SQ. YD.)	44213200 (FT)	44213204 (EACH)	44213000 (SQ. YD.)
685+47.46	I-57 MAINLINE	NBDL	20.0	6.0		13.3			64.0	10.0	13.3
733+89.98	I-57 MAINLINE	NBDL	8.0	12.0		10.7			64.0		10.7
735+27.78	I-57 MAINLINE	NBDL	8.0	6.0		5.3			40.0		5.3
736+45.89	I-57 MAINLINE	NBDL	20.0	6.0		13.3			64.0	10.0	13.3
764+96.94	I-57 MAINLINE	SBDL	6.0	6.0	4.0				36.0		4.0
765+13.34	I-57 MAINLINE	NBDL	6.0	6.0	4.0				36.0		4.0
766+80.66	I-57 MAINLINE	NBDL	12.0	12.0			16.0		72.0		16.0
804+76.59	I-57 MAINLINE	NBDL	20.0	6.0		13.3			64.0	10.0	13.3
807+81.71	I-57 MAINLINE	NBDL	15.0	6.0		10.0			54.0		10.0
818+41.42	I-57 MAINLINE	NBDL	20.0	12.0				26.7	88.0	10.0	26.7
832+19.37	I-57 MAINLINE	NBDL	6.0	12.0		8.0			60.0		8.0
838+42.73	I-57 MAINLINE	NBDL	6.0	6.0	4.0				36.0		4.0
871+69.50	I-57 MAINLINE	NBDL	20.0	12.0				26.7	88.0	10.0	26.7
637+57.63	I-57 MAINLINE	SBDL	20.0	6.0		13.3			64.0	10.0	13.3
642+13.67	I-57 MAINLINE	SBDL	20.0	6.0		13.3			64.0	10.0	13.3
649+61.70	I-57 MAINLINE	SBDL	6.0	6.0	4.0				36.0		4.0
650+14.19	I-57 MAINLINE	SBDL	10.0	6.0		6.7			44.0		6.7
652+89.78	I-57 MAINLINE	SBDL	6.0	6.0	4.0				36.0		4.0
660+37.81	I-57 MAINLINE	SBDL	6.0	6.0	4.0				36.0		4.0
662+97.00	I-57 MAINLINE	SBDL	14.0	12.0			18.7		76.0		18.7
670+12.22	I-57 MAINLINE	SBDL	6.0	6.0	4.0				36.0		4.0
671+46.73	I-57 MAINLINE	SBDL	6.0	12.0		8.0			60.0		8.0
681+53.94	I-57 MAINLINE	SBDL	8.0	6.0		5.3			40.0		5.3
687+31.37	I-57 MAINLINE	SBDL	6.0	6.0	4.0				36.0		4.0
687+47.77	I-57 MAINLINE	SBDL	6.0	6.0	4.0				36.0		4.0
689+77.43	I-57 MAINLINE	SBDL	6.0	6.0	4.0				36.0		4.0
690+20.08	I-57 MAINLINE	SBDL	6.0	6.0	4.0				36.0		4.0
698+04.20	I-57 MAINLINE	SBDL	8.0	6.0		5.3			40.0		5.3
754+11.16	I-57 MAINLINE	SBDL	16.0	12.0			21.3		80.0		21.3
766+57.88	I-57 MAINLINE	SBDL	6.0	12.0		8.0			60.0		8.0
773+40.29	I-57 MAINLINE	SBDL	6.0	12.0		8.0			60.0		8.0
786+52.63	I-57 MAINLINE	SBDL	30.0	6.0			20.0		84.0	15.0	20.0
790+98.82	I-57 MAINLINE	SBDL	30.0	6.0			20.0		84.0	15.0	20.0
792+30.05	I-57 MAINLINE	SBDL	6.0	6.0	4.0				36.0		4.0
792+72.70	I-57 MAINLINE	SBDL	20.0	6.0		13.3			64.0	10.0	13.3
793+64.56	I-57 MAINLINE	SBDL	6.0	6.0	4.0				36.0		4.0
795+77.81	I-57 MAINLINE	SBDL	10.0	6.0		6.7			44.0		6.7
805+45.66	I-57 MAINLINE	SBDL	8.0	12.0		10.7			64.0		10.7
827+96.32	I-57 MAINLINE	SBDL	20.0	12.0				26.7	88.0	10.0	26.7
851+09.31	I-57 MAINLINE	SBDL	20.0	6.0		13.3			64.0	10.0	13.3
854+76.76	I-57 MAINLINE	SBDL	6.0	6.0	4.0				36.0		4.0
854+99.73	I-57 MAINLINE	SBDL	10.0	6.0		6.7			44.0		6.7
860+18.10	I-57 MAINLINE	SBDL	30.0	6.0			20.0		84.0	15.0	20.0
863+39.62	I-57 MAINLINE	SBDL	6.0	6.0	4.0				36.0		4.0
863+75.71	I-57 MAINLINE	SBDL	25.0	6.0			16.7		74.0	13.0	16.7
903+84.89	I-57 MAINLINE	SBDL	15.0	12.0			20.0		78.0		20.0
905+75.18	I-57 MAINLINE	SBDL	10.0	6.0		6.7			44.0		6.7
906+93.29	I-57 MAINLINE	SBDL	6.0	12.0		8.0			60.0		8.0
909+45.91	I-57 MAINLINE	SBDL	20.0	12.0				26.7	88.0	10.0	26.7
SUBTOTALS					60.0	207.2	152.7	106.8	2750.0	168.0	526.7
USE					60.0	208.0	153.0	107.0	2750.0	168.0	527.0

•VERMILION & CHAMPAIGN
•• FAI 57 & FAI 74

FILE NAME =	USER NAME = bucklesjj	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwwork\pwwidott\bucklesjj\d0262126\057940-sht-schedule.dgn		DRAWN -	REVISED -			**	D5 PATCHING 2012-1	*	10	9
PLOT SCALE = 40.0000' / 1" IN.		CHECKED -	REVISED -			CONTRACT NO. 70940				
PLOT DATE = 3/17/2011		DATE -	REVISED -			[ILLINOIS] FED. AID PROJECT				
				SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	