

SCHEDULE OF QUANTITIES
TABULATION OF CLASS B PATCH, 13" & 17"
I-74 MAINLINE (EASTBOUND & WESTBOUND)

STATION	LOCATION	LANE	LENGTH	WIDTH	DEPTH	TYPE II	TYPE III	TYPE IV	TYPE IV	DOWEL BARS	SAWCUTS	TIE BARS, 3/4"	PAVEMENT FABRIC
						17"-44201055	17"-44201057	13"-44201013	17"-44201053	44201299	44213200	44213204	44213100
			(FT)	(FT)	(INCHES)	(SQ. YD.)	(SQ. YD.)	(SQ. YD.)	(SQ. YD.)	(EACH)	(FT)	(EACH)	(SQ. YD.)
1688+94	I-74 MAINLINE	WBDL	25.0	12.0	13.0			33.3		30.0	86.0	13.0	33.3
1881+15	I-74 MAINLINE	WBDL	6.0	12.0	17.0	8.0				20.0	48.0		
1882+80	I-74 MAINLINE	WBPL	6.0	12.0	17.0	8.0				20.0	48.0		
1885+09	I-74 MAINLINE	WBDL	8.0	12.0	17.0	10.7				20.0	52.0		
1885+09	I-74 MAINLINE	WBPL	6.0	12.0	17.0	8.0				20.0	48.0		
1886+10	I-74 MAINLINE	WBDL	6.0	12.0	17.0	8.0				20.0	48.0		
1887+11	I-74 MAINLINE	WBDL	6.0	12.0	17.0	8.0				20.0	48.0		
1889+12	I-74 MAINLINE	WBDL	6.0	12.0	17.0	8.0				20.0	48.0		
1889+35	I-74 MAINLINE	WBDL	6.0	12.0	17.0	8.0				20.0	48.0		
1892+61	I-74 MAINLINE	WBDL	6.0	12.0	17.0	8.0				20.0	48.0		
1893+57	I-74 MAINLINE	WBDL	10.0	12.0	17.0	13.3				20.0	56.0		
1894+33	I-74 MAINLINE	WBDL	6.0	12.0	17.0	8.0				20.0	48.0		
1894+76	I-74 MAINLINE	WBDL	20.0	12.0	17.0				26.7	20.0	76.0	10.0	26.7
1895+29	I-74 MAINLINE	WBDL	12.0	12.0	17.0		16.0			20.0	60.0		16.0
1897+13	I-74 MAINLINE	WBDL	6.0	12.0	17.0	8.0				20.0	48.0		
1899+18	I-74 MAINLINE	WBDL	15.0	12.0	17.0		20.0			20.0	66.0		20.0
1921+07	I-74 MAINLINE	WBDL	6.0	12.0	17.0	8.0				20.0	48.0		
1921+65	I-74 MAINLINE	WBDL	8.0	12.0	17.0	10.7				20.0	52.0		
1923+10	I-74 MAINLINE	WBDL	6.0	12.0	17.0	8.0				20.0	48.0		
1924+04	I-74 MAINLINE	WBDL	6.0	12.0	17.0	8.0				20.0	48.0		
1927+05	I-74 MAINLINE	WBDL	10.0	12.0	17.0	13.3				20.0	56.0		
1927+87	I-74 MAINLINE	WBDL	12.0	12.0	17.0		16.0			20.0	60.0		16.0
1929+06	I-74 MAINLINE	WBDL	6.0	12.0	17.0	8.0				20.0	48.0		
1931+72	I-74 MAINLINE	WBDL	6.0	12.0	17.0	8.0				20.0	48.0		
1932+47	I-74 MAINLINE	WBDL	6.0	12.0	17.0	8.0				20.0	48.0		
1933+02	I-74 MAINLINE	WBDL	20.0	12.0	17.0				26.7	20.0	76.0	10.0	26.7
1934+18	I-74 MAINLINE	WBDL	42.0	12.0	17.0				56.0	40.0	120.0	21.0	56.0
1934+69	I-74 MAINLINE	WBDL	25.0	12.0	17.0				33.3	30.0	86.0	13.0	33.3
1934+99	I-74 MAINLINE	WBDL	6.0	12.0	17.0	8.0				20.0	48.0		
1935+07	I-74 MAINLINE	WBDL	15.0	12.0	17.0		20.0			20.0	66.0		20.0
1935+67	I-74 MAINLINE	WBPL	6.0	12.0	17.0	8.0				20.0	48.0		
1937+24	I-74 MAINLINE	WBDL	20.0	12.0	17.0				26.7	20.0	76.0	10.0	26.7
1937+54	I-74 MAINLINE	WBDL	6.0	12.0	17.0	8.0				20.0	48.0		
1938+65	I-74 MAINLINE	WBDL	6.0	12.0	17.0	8.0				20.0	48.0		
1939+51	I-74 MAINLINE	WBDL	6.0	12.0	17.0	8.0				20.0	48.0		
1941+23	I-74 MAINLINE	WBDL	6.0	12.0	17.0	8.0				20.0	48.0		
1941+51	I-74 MAINLINE	WBDL	20.0	12.0	17.0				26.7	20.0	76.0	10.0	26.7
1942+96	I-74 MAINLINE	WBDL	6.0	12.0	17.0	8.0				20.0	48.0		
					SUBTOTALS	232.0	72.0	33.3	196.1	800.0	2168.0	87.0	301.4
					TOTALS	232.0	72.0	34.0	196.0	800.0	2168.0	87.0	302.0

- VERMILION & CHAMPAIGN
- FAI57 & FAI74

FILE NAME =	USER NAME = austinr1	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES	F.A.J. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwwork\pwwork\Austinr1\09262126\0570	440-shr-schedule.dgn	DRAWN -	REVISED -			**	05 PATCHING 2012-1	*	10	10	
	PLOT SCALE = 40.0000' / in.	CHECKED -	REVISED -			CONTRACT NO. 70940					
	PLOT DATE = 3/30/2011	DATE -	REVISED -			IN 1 INCHES					
SCALE:		SHEET NO. OF SHEETS		STA. TO STA.							