

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	100% STATE URBAN TOTAL QUANTITY	ST. CLAIR COUNTY											
				ROADWAY I-70	CULVERT I-70	CONSTRUCTION TYPE CODE									
				0001	0040										
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	196	196											
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	48	48											
20100500	TREE REMOVAL, ACRES	ACRE	0.7	0.7											
20101000	TEMPORARY FENCE	FOOT	740	740											
20200100	EARTH EXCAVATION	CU YD	22,070	22,070											
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	14,955	14,955											
20400800	FURNISHED EXCAVATION	CU YD	84,425	84,425											
20800150	TRENCH BACKFILL	CU YD	1,303	1,303											
* 25000210	SEEDING, CLASS 2A	ACRE	0.75	0.75											
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	68	68											
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	68	68											
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	68	68											
* 25100115	MULCH, METHOD 2	ACRE	70.75	70.75											
25100630	EROSION CONTROL BLANKET	SQ YD	91,076	91,076											
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	20,039	20,039											
28000305	TEMPORARY DITCH CHECKS	FOOT	140	140											
28000400	PERIMETER EROSION BARRIER	FOOT	12,570	12,570											
28000510	INLET FILTERS	EACH	4	4											
28100107	STONE RIPRAP, CLASS A4	SQ YD	311	311											
28200200	FILTER FABRIC	SQ YD	251	251											
28500400	ARTICULATED BLOCK REVETMENT MAT	SQ YD	647	647											
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	13	13											
40701811	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 6 1/2"	SQ YD	489	489											
44000100	PAVEMENT REMOVAL	SQ YD	9,340	9,340											
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	13	13											
44004250	PAVED SHOULDER REMOVAL	SQ YD	6	6											
44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SQ YD	91	91											
44201299	DOWEL BARS 1 1/2"	EACH	122	122											
44213200	SAW CUTS	FOOT	297	297											
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	89	89											
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	6	6											

* DENOTES SPECIALTY ITEMS

△ REVISED 6-6-11

\\FS-0044\AMVAULT\TRANS_07\2202\20888-001\CIVIL\CAD\99 ALL CONTRACTS\CONNSHEETS CONTRACT 06\DECONN-06-SHT-SUMMARY1.DGN
--\BDCNN-06-BORDER1.DGN, --\BDCNN-06-S001.DGN, --\BDCNN-99-MOTIF1.DGN, --\BDCNN-06-LEGEND1.DGN
2-04-2011, 15:52:02 BONDHJJD

FILE NAME : #FILE#	USER NAME : #USER#	DESIGNED - JB	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION I-70 CONNECTION	SUMMARY OF QUANTITIES 1	F.A.P. RTE. 998	SECTION 82-1A	COUNTY ST. CLAIR	TOTAL SHEETS 190	SHEET NO. 4	
TENG	TENG & ASSOCIATES, INC. ENGINEERS/ARCHITECTS/PLANNERS CHICAGO, ILLINOIS	DRAWN - JB	REVISED -			SCALE: N.T.S.	SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT
		CHECKED - ACL	REVISED -								
		DATE - 02/04/11	REVISED -								
CONTRACT NO. 76C41											