06-17-2022 LETTING ITEM 032

INDEX

1 COVER SHEET

2 GENERAL NOTES

3-4 SUMMARY OF QUANTITIES

5 LIGHT TOWER ID DETAIL

6-9 LIGHTING REMOVAL

.0-13 PROPOSED LIGHTING PLANS

14 LUMINAIRE TABLE

15 ELECTRICAL DETAIL


838001-01 BREAKAWAY DEVICES

 \bigcirc

16-17 SOIL BORINGS

LIST OF ILLINOIS DOT HIGHWAY STANDARDS

000001-08	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
001001-02	AREAS OF REINFORCEMENT BARS
001006	DECIMAL OF AN INCH AND OF A FOOT
701001 02	OFF ROAD OPERATIONS 2L, 2W, MORE THAN 15' AWAY
701006-05	OFF-ROAD OPERATIONS 2L, 2W, 15' TO 24" FROM FAVEMENT EDG
701011-04	OFF-ROAD MOVING OPERATIONS 2L, 2W, DAY ONLY
701201-05	LANE CLOSURE, 2L, 2W, DAY ONLY, FOR SPEEDS ≥ 45 MPH
701456-05	PARTIAL EXIT RAMP CLOSURE FREEWAY/EXPRESSWAY
701801-06	SIDEWALK, CORNER OR CROSSWALK CLOSURE
701901-08	TRAFFIC CONTROL DEVICES
821101-02	LUMINAIRE WIRING IN POLE
835001-01	LIGHT TOWER
837001-05	LIGHT TOWER FOUNDATION



FULL SIZE PLANS HAVE BEEN PREPARED USING STANDARD ENGINEERING SCALES. REDUCED SIZED PLANS WILL NOT CONFORM TO STANDARD SCALES. IN MAKING MEASUREMENTS ON REDUCED PLANS, THE ABOVE SCALES MAY BE USED.

J.U.L.I.E.
JOINT UTILITY LOCATION INFORMATION FOR EXCAVATION
1–800–892–0123

PROJECT ENGINEER – BRAD DUNCAN UNIT CHIEF – DARCY CARPENTER DISTRICT 3 NO. (815) 434–6131 CONTRACT NO. 66M05


STATE OF ILLINOIS

DEPARTMENT OF TRANSPORTATION

PROPOSED HIGHWAY PLANS

FAI ROUTE 57 (I 57)
SECTION (38-8)RA-L2
PROJECT NHPP-QZU0(009)
TYPE of IMPROVEMENT - LIGHTING IROQUOIS COUNTY

C-93-106-21





D-93-072-21



RURAL INTERSTATE

2019 ADT = 15900

PU=60.9% SU=3.9% MU=35.2%



PRINTED BY THE AUTHORITY OF THE STATE OF ILLINOIS

GENERAL NOTES

THE MAINTENANCE OF THE EXISTING LIGHTING WILL BE THE RESPONSIBILITY OF THE CONTRACTOR ACCORDING TO ARTICLE 801.11(a) UNTIL THE NEW LIGHT TOWERS AND LIGHT POLES ARE APPROVED BY THE RESIDENT ENGINEER/TECHNICIAN.

FOR STABILIZATION, ALL TYPE III BARRICADES WILL REQUIRE A MINIMUM OF FOUR SAND BAGS PER BARRICADE.

SEEDING WILL NOT BE PERMITTED AT ANY TIME WHEN THE GROUND IS FROZEN, WET, OR IN AN UNTILLABLE CONDITION. LOCATIONS TO BE SEEDED WILL BE DETERMINED BY THE ENGINEER.

THERE ARE NO TREES SCHEDULED TO BE REMOVED ON THIS PROJECT. IF TREES ARE TO BE REMOVED FOR WHATEVER REASON THEY WILL NOT BE ALLOWED TO BE REMOVED BETWEEN APRIL 1ST AND SEPTEMBER 30TH OF ANY GIVEN YEAR.

THE FINISHED EARTHWORK SHALL HAVE A VEGETATION SUSTAINING SOIL COVERING THE TOP FOUR INCHES (100 MILLIMETERS) IN AREAS TO BE SEEDED OR SODDED. THE VEGETATION SUSTAINING SOIL REQUIRED WILL NOT BE PAID FOR SEPARATELY BUT WILL BE INCLUDED IN THE COST OF THE LIGHTING PAY ITEMS.

ALL EXCAVATED MATERIAL, WHICH INCLUDES DIGGING OR GRADING OF ANY SOIL OR FILL MATERIAL, WITH THE EXCEPTION OF AGGREGATE FILLS, MUST BE INCORPORATED WITHIN THE IDOT RIGHT OF WAY DUE TO ENVIRONMENTAL DOCUMENTATION REQUIREMENTS.

ALL ELEVATIONS REFERRING TO U.S.G.S. MEAN SEA LEVEL DATUM.

ABANDONED UNDERGROUND UTILITIES THAT CONFLICT WITH CONSTRUCTION SHALL BE DISPOSED OF OUTSIDE THE LIMITS OF THE RIGHT OF WAY ACCORDING TO ARTICLE 202.03 OF THE STANDARD SPECIFICATIONS AND AS DIRECTED BY THE ENGINEER. THIS WORK WILL NOT BE PAID FOR SEPARATELY, BUT WILL BE INCLUDED IN THE COST OF THE LIGHTING PAY ITEMS.

ANY REFERENCE TO A STANDARD IN THESE PLANS SHALL BE INTERPRETED TO MEAN THE EDITION AS INDICATED BY THE SUBNUMBER SHOWN IN THE LIST OF STANDARDS OR THE COPY INCLUDED IN THESE PLANS.

THE CONTRACTOR'S ATTENTION IS DIRECTED TO THE PRESENCE OF DEPARTMENT-OWNED UNDERGROUND ELECTRICAL CABLE WITHIN THE LIMITS OF THE PROPOSED IMPROVEMENT. THE CONTRACTOR SHALL REQUEST THE ILLINOIS DEPARTMENT OF TRANSPORTATION IN OTTAWA (815-434-8417) TO LOCATE THE UNDERGROUND FACILITIES, PROVIDING A MINIMUM OF 72 HOURS NOTICE. THE DEPARTMENT IS NOT A MEMBER OF THE JOINT UTILITY LOCATING INFORMATION FOR EXCAVATORS (JULIE)

ALL DAMAGE TO DEPARTMENT OWNED UNDERGROUND FACILITIES, CAUSED BY THE CONTRACTOR SHALL BE REPAIRED TO THE SATISFACTION OF THE DEPARTMENT AT THE CONTRACTOR'S EXPENSE. THIS SHALL INCLUDE ALL TEMPORARY REPAIRS REQUIRED TO KEEP THE FACILITY OPERATIONAL WHILE MATERIAL IS BEING OBTAINED TO MAKE PERMANENT REPAIRS. SPLICING OF ELECTRIC CABLE WILL NOT BE ALLOWED. ELECTRIC CABLE SHALL BE REPLACED FROM POLE TO POLE OR CONTROLLER.

THERE IS A WATER SERVICE LINE FOR THE REST AREA THAT MUST BE LOCATED BEFORE WORK BEGINS. IT IS DEPARTMENT OWNED AND NOT A PART OF JULIE. THE CONTRACTOR SHALL LOCATE THE WATER SERVICE LINE FOR NB AND SB REST AREAS AT THEIR OWN EXPENSE.

ALL PROPOSED LIGHT TOWERS SHALL BE GALVANIZED STEEL.

KNOWN MEMBERS OF JULIE KNOWN TO BE WITHIN THE LIMITS OF THE IMPROVEMENT ARE:

AMEREN, CMS, EIEC, FRONTIER, NICOR, WINDRSTREAM METRO COMMUNICATIONS AND VILLAGE OF BUCKLEY

NON-MEMBERS OF JULIE KNOWN TO BE WITHIN THE LIMITS OF THE IMPROVEMENT ARE:

ILLINOIS DEPARTMENT OF TRANSPORTATION

THE CONTRACTOR SHALL CONTACT JULIE AT LEAST 48 HOURS PRIOR TO EXCAVATION TO DETERMINE WHICH UTILITIES ARE IN THE AREA.

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
DISTRICT THREE
AS BUILT INFORMATION

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION DISTRICT THREE

DISTRICT STUDIES & PLANS ENGINEER

SUPERVISING CONSTRUCTION FIELD ENGINEER

RESIDENT ENGINEER / TECHNICIAN

DATE:

PREPARED BY:

START & END DATES
OF CONSTRUCTION:

SCALE:

INSPECTORS:

EXAMINED BY:

DISTRICT CONSTRUCTION ENGINEER

DISTRICT MATERIALS ENGINEER

DISTRICT OPERATIONS ENGINEER

 USER NAME
 = pletschtr
 DESIGNED
 REVISED

 DRAWN
 REVISED

 PLOT SCALE
 = 100,0000 ' / in.
 CHECKED
 REVISED

 PLOT DATE
 = 3/21/2022
 DATE
 REVISED

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ODEL: Default

				CONSTR. CODE
				90% FEDERAL
				10% STATE
				ROADWAY
CODE			TOTAL	0021
NO.	ITEM	UNIT	QUANTITY	RURAL
67100100	MOBILIZATION	L SUM	1	1
70100825	TRAFFIC CONTROL AND PROTECTION, STANDARD 701456	L SUM	1	1
70107025	CHANGEABLE MESSAGE SIGN	CAL DA	60	60
81028720	UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 1" DIA.	FOOT	2595	2595
81100454	CONDUIT ATTACHED TO STRUCTURE, 1" DIA., STAINLESS STEEL	FOOT	10	10
81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	9375	9375
82110009	LUMINAIRE, LED, ROADWAY, OUTPUT DESIGNATION I	EACH	10	10
82110016	LUMINAIRE, LED, HIGHMAST, OUTPUT DESIGNATION I	EACH	24	24
82500430	LIGHTING CONTROLLER, WALL MOUNTED, 240VOLT, 100AMP	EACH	2	2
83503400	LIGHT TOWER, 110 FT. MOUNTING HEIGHT, LUMINAIRE MT 6	EACH	4	4
83700300	LIGHT TOWER FOUNDATION, 48" DIAMETER	FOOT	76	76
0.45004.45	DEMOVAL OF LIGHTING CONTROLLED	F. 6.1.		-
84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	2	2
89502300	DEMOVE ELECTRIC CARLE EDOM CONDUIT	FOOT	0275	0275
09302300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	9375	9375
X0324599	ROD AND CLEAN EXISTING CONDUIT	FOOT	9375	9375
7,032,7333	THE CLEAR EXTERNO COMBOTT	1 301	3373	3313

 USER NAME
 = pletschtr
 DESIGNED
 REVISED

 DRAWN
 REVISED

 PLOT SCALE
 = 100,0000 / in.
 CHECKED
 REVISED

 PLOT DATE
 = 3/17/2022
 DATE
 REVISED

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

CONSTR. CODE

CONSTR. CODE 90% FEDERAL 10% STATE


				ROADWAY
CODE			TOTAL	0021
NO.	ITEM	UNIT	QUANTITY	RURAL
X1400267	REMOVAL OF LIGHTING LUMINAIRE, NO SALVAGE	EACH	10	10
X8210402	LUMINAIRE MOUNTING BRACKET - SPECIAL	EACH	10	10
X8420502	REMOVAL OF LIGHT TOWER, NO SALVAGE	EACH	4	4
X8420510	REMOVAL OF TOWER FOUNDATION	EACH	4	4

DEI: Derault : NAME: pw:\\ildot-pw.bentley.com:PWIDOT\Documents\IDOT Offices\District 3\P

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCALE: __

LIGHT TOWER IDENTIFICATION:



THE CONTRACTOR SHALL FURNISH AND INSTALL A LIGHT TOWER IDENTIFICATION ON EACH LIGHT TOWER PER SECTION 1069.06 OF THE S.S., AS SHOWN ABOVE, INCIDENTAL TO THE RESPECTIVE LIGHT TOWER PAY ITEM. THE NUMERALS SHALL BE 3" HIGH SERIES "D", BLACK, SCREENED ON SILVER-WHITE TYPE B PRESSURE SENSITIVE REFLECTIVE SHEETING CONFORMING TO THE REQUIREMENTS OF THE APPLICABLE PORTION OF SECTION 1091 OF THE STANDARD SPECIFICATIONS FOR TRAFFIC CONTROL ITEMS. THE NUMERALS SHALL CONFORM TO THE FHWA "STANDARD ALPHABETS FOR HIGHWAY SIGNS".

THE LIGHT TOWER IDENTIFICATION SHALL BE APPLIED TO SIGN BASE MATERIAL AS SPECIFIED IN SECTION 1085,05 OF THE SUPPLEMENTAL SPECIFICATIONS, APPROXIMATELY 7' ABOVE THE ADJACENT PAVEMENT GRADE VISIBLE TO APPROACHING TRAFFIC IN ACCORDANCE WITH HIGHWAY STANDARD 2319.


I-57 AND SB MAINLINE TOWER
I-57 AND SB MAINLINE TOWER
I-57 AND NB MAINLINE TOWER
FURTHEST TOWER SOUTH IS 50-3
FURTHEST TOWER SOUTH IS 50-3

I-57 AND NB MAINLINE TOWER FURTHEST TOWER NORTH IS 50-2

BILL OF MATERIALS PAY ITEM DESCRIPTION UNIT QUANTITY 81028720 UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 1" DIA. FOOT 2,595 CONDUIT ATTACHED TO STRUCTURE, 1" DIA., STAINLESS STEEL FOOT 81100454 10 81702130 ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6 FOOT 9,375 EACH 82110009 LUMINAIRE, LED, ROADWAY, OUTPUT DESIGNATION I 10 82110017 LUMINAIRE, LED, HIGHMAST, OUTPUT DESIGNATION J EACH 16 82500430 LIGHTING CONTROLLER, WALL MOUNTED, 240VOLT, 100AMP EACH 2 83503300 LIGHT TOWER, 110 FT. MOUNTING HEIGHT, LUMINAIRE MT. - 4 EACH 4 83700300 LIGHT TOWER FOUNDATION, 48" DIAMETER **FOOT** 76.0 84500110 REMOVAL OF LIGHTING CONTROLLER EACH 2 REMOVE ELECTRIC CABLE FROM CONDUIT 89502300 **FOOT** 9,375 REMOVAL OF LIGHTING LUMINAIRE, NO SALVAGE X1400267 EACH 10 X8210402 LUMINAIRE MOUNTING BRACKET - SPECIAL **EACH** 10 X8420502 REMOVAL OF LIGHT TOWER, NO SALVAGE **EACH** 4 X8420510 REMOVAL OF TOWER FOUNDATION **EACH**

USER NAME = pletschtr	DESIGNED	REVISED	
	DRAWN	REVISED	
PLOT SCALE = 100.0000 / in.	CHECKED	REVISED	
PLOT DATE = 3/18/2022	DATE	REVISED	

				F.A.I. RTE	SECTION		COUNTY	TOTAL SHEETS	SHEET NO.
LIGHT TOWER ID DETAIL				57	(38-8)RA-L2		IROQUOIS	17	5
							CONTRACT	NO. 66	5M05
OF	SHEETS	STA.	TO STA.		ILLINOIS E	FD Δ	D PROJECT		



O—O EXISTING LIGHTING UNIT TO REMAIN, REMOVE LUMINAIRE

EXISTING ELECTRIC CABLE IN CONDUIT TO BE REMOVED (SEE NOTE 1)

NOTES:

1. ELECTRIC CABLES IN EXISTING UNIT DUCT OR CONDUIT SHALL BE REMOVED AND PAID FOR AS "REMOVE ELECTRIC CABLE FROM CONDUIT". THE CONTRACTOR SHALL VERIFY LOCATION OF EXISTING CONDUIT ROUTE.

0	50	100	150						
SCALE IN FEET									

IROQUOIS 17 6
CONTRACT NO. 66M05

SECTION (38-8)RA-L2

USER NAME = pietscntr	I–57 NB MAINLINE REST AREA								
	DRAWN -	REVISED -	STATE OF ILLINOIS						
PLOT SCALE = 100.0000 / in.	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION		L	GHTING	KEMUV	AL PLAN	
PLOT DATE = 3/17/2022	DATE -	REVISED -		SCALE:	SHEET	OF	SHEETS	STA.	TO STA.





EXISTING HIGH MAST LIGHT TOWER TO BE REMOVED, BREAKDOWN FOUNDATION BELOW GRADE

O—O EXISTING LIGHTING UNIT TO REMAIN, REMOVE LUMINAIRE

EXISTING LIGHTING CONTROL PANEL TO BE REMOVED (SEE NOTE 2)

EXISTING ELECTRIC CABLE IN CONDUIT TO BE REMOVED (SEE NOTE 1)

NOTES:

- ELECTRIC CABLES IN EXISTING UNIT DUCT OR CONDUIT SHALL BE REMOVED AND PAID FOR AS "REMOVE ELECTRIC CABLE FROM CONDUIT". THE CONTRACTOR SHALL VERIFY LOCATION OF EXISTING CONDUIT ROUTE.
- 2. THE CONTRACTOR SHALL VERIFY LOCATION OF EXISTING LIGHTING CONTROL PANEL.
- 3. EXISTING LIGHT TOWERS TO BE REMOVED SHALL REMAIN UNTIL PROPOSED LIGHTING SYSTEM IS OPERATIONAL.

0	50	100	150
SCAL	E IN FEET		

USER NAME = pletschtr	DESIGNED -	REVISED -		I–57 NB MAINLINE REST AREA		F.A.I. RTF	SECTION	COUNTY	TOTAL SH	EET			
	DRAWN -	REVISED -	STATE OF ILLINOIS		1-37				57	(38-8)RA-L2	IROQUOIS	17	7
PLOT SCALE = 100.0000 / in	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION	LIGHTING REMOVAL PLAN				,,,,,,	CONTRAC	T NO. 66M0)5		
PLOT DATE = 3/17/2022	DATE -	REVISED -		SCALE:	SHEET	OF	SHEETS ST.	A. TO STA.		ILLINOIS FED. A	ID PROJECT		





EXISTING HIGH MAST LIGHT TOWER TO BE REMOVED, BREAKDOWN FOUNDATION BELOW GRADE

O—O EXISTING LIGHTING UNIT TO REMAIN, REMOVE LUMINAIRE

EXISTING LIGHTING CONTROL PANEL TO BE REMOVED (SEE NOTE 2)

EXISTING ELECTRIC CABLE IN CONDUIT TO BE REMOVED (SEE NOTE 1)

OTES:

- ELECTRIC CABLES IN EXISTING UNIT DUCT OR CONDUIT SHALL BE REMOVED AND PAID FOR AS "REMOVE ELECTRIC CABLE FROM CONDUIT". THE CONTRACTOR SHALL VERIFY LOCATION OF EXISTING CONDUIT ROUTE.
- 2. THE CONTRACTOR SHALL VERIFY LOCATION OF EXISTING LIGHTING CONTROL PANEL.
- 3. EXISTING LIGHT TOWERS TO BE REMOVED SHALL REMAIN UNTIL PROPOSED LIGHTING SYSTEM IS OPERATIONAL.

0	50	100	150						
SCALE IN FEET									

USER NAME = pletschtr	DESIGNED -	REVISED -		I-57 SB MAINLINE REST AREA			F.A.I. BTE	SECTION	COUNTY	TOTAL	SHEET			
	DRAWN -	REVISED -	STATE OF ILLINOIS		1-57					57	(38-8)RA-L2	IROQUOIS	17	8
PLOT SCALE = 100.0000 / in.	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION		L	MI ING	REMOVA	L PLAN				CONTRAC	T NO. 66	M05
PLOT DATE = 3/17/2022	DATE	REVISED		SCALE:	SHEET 4	4 OF	SHEETS	STA	TO STA		TILLIMOTE FED. A	ID DDOJECT		





O—O EXISTING LIGHTING UNIT TO REMAIN, REMOVE LUMINAIRE

EXISTING ELECTRIC CABLE IN CONDUIT TO BE REMOVED (SEE NOTE 1)


OTES:

ELECTRIC CABLES IN EXISTING UNIT DUCT OR CONDUIT SHALL BE REMOVED AND PAID FOR AS "REMOVE ELECTRIC CABLE FROM CONDUIT". THE CONTRACTOR SHALL VERIFY LOCATION OF EXISTING CONDUIT ROUTE.

0	50	100	150
SCAL	E IN FEET		

USER NAME = pletschtr	DESIGNED -	REVISED -			I-57	SR M	AINLINE REST AREA	1	F.A.I. BTF	SECTION	COUNTY	TOTAL SHEE
	DRAWN -	REVISED -	STATE OF ILLINOIS				REMOVAL PLAN	•	57	(38-8)RA-L2	IROQUOIS	17 9
PLOT SCALE = 100.0000 / in	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION			IGITIING	nLIVIOVAL FLAIV				CONTRACT	Г NO. 66M05
PLOT DATE = 3/17/2022	DATE -	REVISED -		SCALE:	SHEET	OF	SHEETS STA.	TO STA.		ILLINOIS FED.	AID PROJECT	

MODEL: Default



- O—O EXISTING LIGHTING UNIT TO REMAIN WITH NEW 240V LED ROADWAY LUMINAIRE (SEE NOTE 1)
 - PROPOSED 2-1C NO.6, 1/C NO.6 GROUND, (XLP-TYPE USE), IN 1" DIA. COILABLE NONMETALLIC CONDUIT
- ----- EXISTING CONDUIT TO REMAIN (SEE NOTE 3)

IOTEC:

- A LUMINAIRE BRACKET SHALL BE INSTALLED AND PAID FOR AS "LUMINAIRE MOUNTING BRACKET SPECIAL".
- 2. THE CONTRACTOR SHALL INSTALL ROADWAY LUMINAIRES AT 0 DEGRESS HORIZONTAL TO GRADE.
- 3. THE CONTRACTOR SHALL VERIFY LOCATION OF EXISTING CONDUIT ROUTE.
- 4. THE CONTRACTOR SHALL INTERCEPT EXISTING CONDUIT WITH NEW 1" DIA. COILABLE NOMMETALLIC CONDUIT. INSTALL NEW CABLE FROM PROPOSED HIGH MAST LIGHT TOWER TO EXISTING LIGHT POLE. THE COST OF THIS WORK SHALL BE INCLUDED IN THE COST OF THE ASSOCIATED ELECTRIC CABLE.

0	50	100	150
SCALE	IN FEET		

USER NAME = pletschtr	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 100.0000 / in.	CHECKED -	REVISED -
PLOT DATE = 3/17/2022	DATE -	REVISED -

STATI	OF	ILLINOIS
DEPARTMENT	OF	TRANSPORTATION

I-57 NB MAINLINE REST AREA					F.A.I. RTE	SECTION		COUNTY	TOTAL SHEETS	SHEET NO.
PROPOSED LIGHTING PLAN			57	(38-8)RA-L2		IROQUOIS	17	10		
PROPUSED LIGHTING PLAN							CONTRACT	NO. 66	5M05	
ET	OF	SHEETS	STA.	TO STA.		ILLINOIS	FED. AI	D PROJECT		





PROPOSED GALVANIZED STEEL HIGH MAST LIGHT TOWER, 110 FT. M.H. ON 48" DIA. CONCRETE FOUNDATION, WITH 6 LED LUMINAIRES, 240V, LUMINAIRE AIMING AS SHOWN ON PLAN

EXISTING LIGHTING UNIT TO REMAIN WITH NEW 240V LED ROADWAY LUMINAIRE (SEE NOTE 1)

PROPOSED 2-1C NO.6, 1/C NO.6 GROUND, (XLP-TYPE USE), IN 1" DIA. COILABLE NONMETALLIC CONDUIT

PROPOSED LIGHTING CONTROLLER, WALL MOUNTED, 120/240 VOLT, 100 AMP, SINGLE PHASE, 3-WIRE (SEE SHEET 11)

EXISTING CONDUIT TO REMAIN (SEE NOTE 3)

NOTES:

- 1. A LUMINAIRE BRACKET SHALL BE INSTALLED AND PAID FOR AS "LUMINAIRE MOUNTING
- 2. THE CONTRACTOR SHALL INSTALL ROADWAY AND HIGH MAST LUMINAIRES AT 0 DEGRESS HORIZONTAL TO GRADE.
- 3. THE CONTRACTOR SHALL VERIFY LOCATION OF EXISTING CONDUIT ROUTE.
- 4. PROPOSED HIGH MAST LIGHT TOWER SHALL BE SET 5' BEHIND SIDEWALK AND 10' NORTH OF EXISTING HIGH MAST LIGHT TOWER TO BE REMOVED.

- 5. THE CONTRACTOR SHALL INTERCEPT EXISTING CONDUIT WITH NEW 1" DIA. COILABLE NONMETALLIC CONDUIT. INSTALL NEW CABLE FROM PROPOSED HIGH MAST LIGHT TOWER TO PROPOSED LIGHTING CONTROLLER. THE COST OF THIS WORK SHALL BE INCLUDED IN THE COST OF THE ASSOCIATED ELECTRIC CABLE.
- 6. THE CONTRACTOR SHALL INTERCEPT EXISTING CONDUIT WITH NEW 1" DIA. COILABLE NONMETALLIC CONDUIT. INSTALL NEW CABLE FROM PROPOSED HIGH MAST LIGHT TOWER TO EXISTING LIGHT POLE. THE COST OF THIS WORK SHALL BE INCLUDED IN THE COST OF THE ASSOCIATED ELECTRIC CABLE.



USER NAME = pletschtr	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 100.0000 / in.	CHECKED -	REVISED -
PLOT DATE = 3/17/2022	DATE -	REVISED -

STATE OF I	LLINOIS
DEPARTMENT OF TR	RANSPORTATION

-57 NB MAINLINE REST AREA					SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PROPOSED LIGHTING PLAN			57	(38-8)RA-L2	IROQUOIS	17	11	
					CONTRACT	NO. 66	5M05	
OF	SHEETS	STA.	TO STA.		ILLINOIS FED. A	ID PROJECT		





PROPOSED GALVANIZED STEEL HIGH MAST LIGHT TOWER, 110 FT. M.H. ON 48" DIA. CONCRETE FOUNDATION, WITH 6 LED LUMINAIRES, 240V, LUMINAIRE AIMING AS SHOWN ON PLAN

- EXISTING LIGHTING UNIT TO REMAIN WITH NEW 240V LED ROADWAY LUMINAIRE (SEE NOTE 1)
 - PROPOSED 2-1C NO.6, 1/C NO.6 GROUND, (XLP-TYPE USE), IN 1" DIA. COILABLE NONMETALLIC CONDUIT
- PROPOSED LIGHTING CONTROLLER, WALL MOUNTED, 120/240 VOLT, 100 AMP, SINGLE PHASE, 3-WIRE (SEE SHEET 11)
- ----- EXISTING CONDUIT TO REMAIN (SEE NOTE 3)

NOTES:

- 1. A LUMINAIRE BRACKET SHALL BE INSTALLED AND PAID FOR AS "LUMINAIRE MOUNTING
- 2. THE CONTRACTOR SHALL INSTALL ROADWAY AND HIGH MAST LUMINAIRES AT 0 DEGRESS HORIZONTAL TO GRADE.
- 3. THE CONTRACTOR SHALL VERIFY LOCATION OF EXISTING CONDUIT ROUTE.
- 4. PROPOSED HIGH MAST LIGHT TOWER SHALL BE SET 5' BEHIND SIDEWALK AND 10' SOUTH OF EXISTING HIGH MAST LIGHT TOWER TO BE REMOVED.

- 5. THE CONTRACTOR SHALL INTERCEPT EXISTING CONDUIT WITH NEW 1" DIA. COILABLE NONMETALLIC CONDUIT. INSTALL NEW CABLE FROM PROPOSED HIGH MAST LIGHT TOWER TO PROPOSED LIGHTING CONTROLLER. THE COST OF THIS WORK SHALL BE INCLUDED IN THE COST OF THE ASSOCIATED ELECTRIC CABLE.
- 6. THE CONTRACTOR SHALL INTERCEPT EXISTING CONDUIT WITH NEW 1" DIA. COILABLE NONMETALLIC CONDUIT. INSTALL NEW CABLE FROM PROPOSED HIGH MAST LIGHT TOWER TO EXISTING LIGHT POLE. THE COST OF THIS WORK SHALL BE INCLUDED IN THE COST OF THE ASSOCIATED ELECTRIC CABLE.



USER NAME = pletschtr	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 100.0000 / in.	CHECKED -	REVISED -
PLOT DATE = 3/17/2022	DATE -	REVISED -

STATE	0F	ILLINOIS	
DEPARTMENT (OF 1	[RANSPOR]	TATION

–57 SB MAINLINE REST AREA					SECTION	COUNTY	TOTAL SHEETS	
PROPOSED LIGHTING PLAN				57	(38-8)RA-L2	IROQUOIS	17	12
						CONTRACT	NO. 66	5M05
OF	SHEETS	STA.	TO STA.		ILLINOIS FED. A	ID PROJECT		





O—O EXISTING LIGHTING UNIT TO REMAIN WITH NEW 240V LED ROADWAY LUMINAIRE (SEE NOTE 1)

PROPOSED 2-1C NO.6, 1/C NO.6 GROUND, (XLP-TYPE USE), IN 1" DIA. COILABLE NONMETALLIC CONDUIT

----- EXISTING CONDUIT TO REMAIN (SEE NOTE 3)

OTEC:

- A LUMINAIRE BRACKET SHALL BE INSTALLED AND PAID FOR AS "LUMINAIRE MOUNTING BRACKET - SPECIAL".
- 2. THE CONTRACTOR SHALL INSTALL ROADWAY LUMINAIRES AT 0 DEGRESS HORIZONTAL TO GRADE.
- 3. THE CONTRACTOR SHALL VERIFY LOCATION OF EXISTING CONDUIT ROUTE.
- 4. THE CONTRACTOR SHALL INTERCEPT EXISTING CONDUIT WITH NEW 1" DIA. COILABLE NONMETALLIC CONDUIT. INSTALL NEW CABLE FROM PROPOSED HIGH MAST LIGHT TOWER TO EXISTING LIGHT POLE. THE COST OF THIS WORK SHALL BE INCLUDED IN THE COST OF THE ASSOCIATED ELECTRIC CABLE.

0	50	100	150
SCAL	E IN FEET		

USER NAME = pletschtr	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 100.0000 / in.	CHECKED -	REVISED -
PLOT DATE = 3/17/2022	DATE -	REVISED -

STATE OF ILLINOIS	
DEPARTMENT OF TRANSPORTATION	

-57 SB MAI	NLINE	REST AREA		F.A.I. RTE	SECTION COUNTY		TOTAL SHEETS	SHEET NO.	
PROPOSED LIGHTING PLAN					57 (38-8)RA-L2		IROQUOIS	17	13
							CONTRACT	NO. 66	M05
OF	SHEETS	STA.	TO STA.		ILLINOIS FED. AID PROJECT				

LUMINAIRE PERFORMANCE TABLE LUMINAIRE, LED, ROADWAY, OUTPUT DESIGNATION I

Project

Date	Contract Number	Section Number		County	
01-25-2022	66M05			IROOU01S	
Marked Route N	umber	Municipali	†y		
I-57 NB/SB MAII	NLINE REST AREA	LODA TO	WNSHIP		

Roadway

Lane Width	*of Lanes	Median Width	I.E.S Surface Classification	0-Zero Value	
12 ft	3	N/A	R3	0.07	

Structure

		Number of Luminaires	
Mounting Height	Arm Length	Set Back	(Highmast & Sign Lighting Only)
50 ft	1 ft	30 ft	N/A

Luminaire

Description		I.E.S. Transverse Distribution		I.E.S. Lateral Distribution	
LUMINAIRE, LED, ROADWAY, OUTPUT	TYPE III		SHOF	RT/MEDIUM	
Total Light Loss Factor (LLF)	BUG Rating		Shields		Dimming Protocol
0.7	U = 0		N/A		0-10V

Layout

Spacing (to Nearest	5 Ft)	Configuration	(Opposite,	Staggered,	1	Sided,	or	Median)
300 ft	·	SINGLE SIDED						

Performance

Average Illuminance, E _{AVE} (fc)			Uniformity Ratio, E AVE/E MIN		
≥ 0.7			≤ 4 . 0:1		
Average Luminance, L AVE(cd/m²) Unifor		mity Ratio, L _{AVE} /L _{MIN}	Uniformity Ratio, L MAX/LMIN	Veiling Luminance Ratio, L _V /L _{MIN}	
	N/A	N/A		N/A	≤ 0.4

Light Tresspass

Distance to ROW (behind pole)	Max. Horizontal Illuminance at ROW, E _H	Max. Vertical Illuminance at ROW, E _V
80 ft	0.2 fc @ LLF = 1.0	0.2 fc @ LLF = 1.0 and 3 ft above grade

Notes

- Set Back is from Edge of Pavement (white line) except for sign luminaires when it is vertical and horizontal distance from the sign to the luminaire.
- 2. Lighting calculations shall be performed with all luminaires oriented toward and perpendicular to roadway.
- 3. Total Light Loss Factor (LLF) = the product of "Lumen Maintenance" (LLD) = 0.9, "Dirt Depreciation" (LDD) = 0.8, and "Equipment Factors" (EF) = 0.95.
- 4. Performance requirements shall be the minimum acceptable standards of photometric performance for the luminaire, based on the given conditions above.
- 5. Lighting calculations shall be performed in one direction only.
- 6. Compliance with performance criteria shall be held to one significant digit.
- 7. Initial lumens of the proposed luminaire may vary from the values specified in the table given in Article 1067.06 of the BDE Special Provision Luminaire, LED.

LUMINAIRE PERFORMANCE TABLE LUMINAIRE, LED, HIGHMAST, OUTPUT DESIGNATION I

Project

Date	Contract Number	Section Num	nber	County	
01-25-2022	66M05			IROQUOIS	
Marked Route N	umber		Municipality		_
I-57 NB/SB MAIN	NLINE REST AREA		LODA TOWNSHIP		

Roadway

L	ane Width	*of Lanes	Median Width	I.E.S Surface Classification	0-Zero Value
	12 ft	11	N/A	R3	0.07

Structure

00.0.0			Number of Luminaires
lounting Height	Arm Length	Set Back	(Highmast & Sign Lighting Only)
110 ft	4 ft	20 ft	6 @ 45 degrees, same direction

Luminaire

Description	I.E.S. Transverse Distribution	I.E.S. Lateral Distribution
LUMINAIRE, LED, HIGHMAST, OUTPUT DESIGNATION I	TYPE II	SHORT/MEDIUM
Total Light Loss Factor (LLF) BUG Rating	Shields	Dimming Protocol
0.7 U = 0	N/A	0-10V

Layout

Spacing (to Nearest 5 Ft	Configuration (Opposite, Staggered, 1 Sided, or Median)
480 ft	SINGLE SIDED

Performance

Average Illuminance, E _{AVE} (fc)		Uniformity Ratio, E AVE/EMIN	١	
≥ 1.5		≤ 4.0:1		
Average Luminance, L _{AVE} (cd/m²)	Unifor	mity Ratio, L _{AVE} /L _{MIN}	Uniformity Ratio, L MAX/LMIN	Veiling Luminance Ratio, L _V /L _{MIN}
N/A	N/A		N/A	≤ 0.3

Light Tresspass

SCALE:


Distance to ROW (in front of p	oole)	Max. Horizontal Illuminance at ROW, E _H	Max. Vertical Illuminance at ROW, E _V
415 ft		0.2 fc @ LLF = 1.0	0.2 fc @ LLF = 1.0 and 3 ft above grade

Notes


- Set Back is from Edge of Pavement (white line) except for sign luminaires when it is vertical and horizontal distance from the sign to the luminaire.
- 2. Lighting calculations shall be performed with all luminaires oriented toward and perpendicular to roadway.
- 3. Total Light Loss Factor (LLF) = the product of "Lumen Maintenance" (LLD) = 0.9, "Dirt Depreciation" (LDD) = 0.8, and "Equipment Factors" (EF) = 0.95.
- 4. Performance requirements shall be the minimum acceptable standards of photometric performance for the luminaire, based on the given conditions above.
- 5. Lighting calculations shall be performed in one direction only.
- 6. Compliance with performance criteria shall be held to one significant digit.
- 7. Initial lumens of the proposed luminaire may vary from the values specified in the table given in Article 1067.06 of the BDE Special Provision Luminaire, LED.


0 50 100 150 SCALE IN FEET

- THE CONTRACTOR SHALL INTERCEPT EXISTING CONDUIT ATTACHED TO STRUCTURE WITH NEW CONDUIT ATTACHED TO STRUCTURE AND ROUTE NEW CONDUIT TO NEW LIGHTING CONTROLLER IN MECHANICAL ROOM. ROUTE NEW FEEDER CONDUCTORS THROUGH CONDUIT FROM EXISTING MAIN BREAKER TO NEW LIGHTING CONTROLLER. ROUTE NEW BRANCH CIRCUIT CONDUCTORS THROUGH CONDUIT FROM NEW LIGHTING CONTROLLER TO NEW HIGH MAST LIGHT TOWERS. REMOVAL OF EXISTING CONDUIT ATTACHED TO STRUCTURE SHALL BE INCLUDED IN COST OF THE LIGHTING CONTROL PANEL REMOVAL.
- 2. THE EXISTING FEEDER CONDUCTORS AND CONDUIT SHALL BE REPLACED TO MATCH EXISTING SIZE (CONDUIT TO BE STAINLESS STEEL). THIS WORK SHALL BE INCLUDED IN THE COST OF THE NEW LIGHTING CONTROLLER.
- THE CONTRACTOR SHALL REPLACE EXISTING PHOTOCELL WITH NEW PHOTOCELL, AND CONNECT NEW PHOTOCELL TO NEW LIGHTING CONTROLLER THROUGH EXISTING CONDUIT. THIS WORK SHALL BE INCLUDED IN THE COST OF THE NEW LIGHTING CONTROLLER.




- ALL NECESSARY REVISIONS TO THE WIRING SHOWN ON THIS SHEET SHALL BE $\,$ MADE AT NO ADDITIONAL COST TO THE DEPARTMENT AND TO THE SATISFACTION OF THE ENGINEER
 - PROPOSED ROADWAY LUMINAIRE, LED
- \bigcirc PROPOSED LIGHT TOWER (6 LED LUMINAIRES)
- GROUND ROD





2 POLE 70 AMP BREAKER 2 POLE 70 AMP BREAKER

PROPOSED I-57 NB LIGHTING CONTROLLER, 240V





2 POLE 70 AMP BREAKER


2 POLE 70 AMP BREAKER

PROPOSED I-57 SB LIGHTING CONTROLLER, 240V

JSER NAME = pletschtr DESIGNED REVISED DRAWN REVISED HECKED REVISED PLOT DATE = 3/17/2022 REVISED DATE

STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION**

SECTION I-57 NB/SB MAINLINE REST AREA (38-8)RA-L2 IROOUOIS 17 15 **ELECTRICAL DETAILS** CONTRACT NO. 66M05 SHEETS STA. TO STA.




CONTROL SCHEMATIC

- 1 Photocell with integral surge arrester.
- (2) HAND-OFF-AUTO selector switch.
- 3 100 amp*, electrically held contactor.
- (4) 15 amp, 1-pole circuit breaker.
- 5 Two 70 amp, 2-pole circuit breakers (shown) and one 30 amp, 2-pole circuit breaker (not shown).
- 6 Surge arrester.

- 1) 100 amp*, 2-pole circuit breaker.
- (12) Terminal block sized for conductors as shown on plans.

* Size larger as needed.

All dimensions are in inches (millimeters) unless otherwise shown.





SOIL BORING LOG

Page <u>1</u> of <u>1</u>

Date 10/12/21

SECTION (38-8)RA-L2		ROUTE	FAI 57 (I-57)	_ DESCR	IPTION	ا	I-57	- Buckley Southbound Rest Area	.OGG	ED BY	Larry	Myers
STRUCT. NO Station		SECTION	(38-8)RA-L2		LOCAT	TION	SE 1/4	, SEC. 4, TWP. 24, RNG. 10, 3 rd PM,				
STRUCT. NO. Station Discrimination Station Discrimination Station Discrimination Discriminat							Latitu	de 40.551195, Longitude -88.060423	(OME A	utoma	itic
Offset 283.0 ft Rt. (ft) (/6") (tsf) (%) Institution of the completion and surface Elev. 283.0 ft Rt. (ft) (/6") (tsf) (%) After Hrs. Bry ft (ft) (/6") (tsf) (%) Augered Black Silty Clay Loam Till Fill and Brown Silty Clay Loam Till Fill and Black Silty Clay Loam Topsoil Hard Gray Silty Clay Loam Till 5 8 4.6 17 Very Stiff Gray and Brown Silty Clay Loam 4 2.0 23 7 4.4 18 Clay/Silty Clay Loam 7 4.4 2.0 23 7 4.4 18 Hard Brownish Gray Silty Clay Till 5 4 5 7 4.4 18 5 5 5 10 8 704.49 9 8 5 6 4.2 18 7 10 8 8 4 17 10 18 10 10 18 10 18 10 18 10 18 10 18 10 18 10		STRUCT. NO. Station	1 (N Tower)	D E P T	B L O W	U C S	M O I S	Surface Water Elev. ft Stream Bed Elev. ft Groundwater Elev.:	D E P T	B L O W	U C S	M O I S
Augered Black Sitty Clay Loam Till Fill and Black Sitty Clay Loam Topsoil		Station Offset	1383+90 283.0 ft Rt.	_		Qu	1	First Encounter ft Upon Completion ft	н	3	Qu	1
And Brown Silty Clay Loam Till Fill and Black Silty Clay Loam Topsoil		Ground Surf	face Elev730.99	ft (ft)	(/6")	(tsf)	(%)	After Hrs. ft	(ft)		(tsf)	(%)
T28.49 3 5 5 7 4.4 18 726.49		and Brown Sil	ty Clay Loam Till Fill	-	1			Hard Gray Silty Clay Loam Till	<u></u>	_ ~	4.6	17
Very Stiff Gray and Brown Silty Clay/Silty Clay Loam 3		and Black Silt	y Clay Loam Topsoil							10	S	
Very Stiff Gray and Brown Silty Clay/Silty Clay Loam 3				728.49	1				:	ł		
Table Tabl			y and Brown Silty									
Hard Brownish Gray Silty Clay Till		Clay/Slity Clay	y Loam	_			23		_		200000	18
4												
10 S Find of Boring Find S Fin		Hard Brownisi	n Gray Silty Clay Till	5					-25	5		
End of Boring 7 12 10.3 18 15 S				_		10.77 (10.75)	17					18
12 10.3 18 15 S				-	10	3			19	,	3	
12 10.3 18 15 S				-] ,				_	1		
18 8.2 20				-	12	10.3	18		_	ł		
-10 7 8 8 2 20				_	15	S			_]		
7 8 8.2 20 14 8 8.2 20 14 9 8.7 21 11 S 15 5 7.4 22 12 S 15 S 16	4/21			-10					-30	1		
14 S	41.5					0.2	20]		
7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7	97.00			-			20		-	ł		
7 7 9 8.7 21	2			_]		
9 8.7 21 -11 8 -15 -16 -36 -36 -36 -36 -36 -36 -36 -36 -36 -3	S.GP.			_					_			
10 10 10 10 10 10 10 10 10 10 10 10 10 1	OWE					1132100131	21					
15 5 36 36 37 4 22 12 S 12 S 2 S 2 S 2 S 2 S 2 S 2 S 2	L HOI			_	.00.00.	_						
9 7.4 22 12 S - 5 - 11 7.8 16 - 15 S	ASTL			15					-35			
12 S 	SEN S			<u>-</u>	9		22		_	j		
5 5 16 7.8 16 710.99 -20 40	REAL				12	S						
5 11 7.8 16 15 S	EST A			_								
710.99 -20 40	-67 R			_	_	7.8	16		_			
710.99 -20	HING					12, 23-27			_			
	OILBC			710.99 -20					-40			

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer) The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)

BBS, form 137 (Rev. 8-99)



SOIL BORING LOG

Page <u>1</u> of <u>1</u>

Date 10/12/21

	ROUTE	FAI 57 (I-57)	_ DE	SCR	IPTION	ı	I-57	- Buckley Southbound Rest Area	LOGG	ED BY	Larry	Myers
	SECTION	(38-8)RA-L2		_ 1	LOCAT	ION _	NE 1/4	, SEC. 9, TWP. 24, RNG. 10, 3 rd PM,				
	COUNTY	Iroquois DF	RILLING	ME	THOD			de 40.549834, Longitude -88.060973 low Stem Auger HAMMER TYP	E	CME A	utoma	tic
	Station BORING NO Station Offset	2 (S Tower) 1389+30 298.0 ft Rt. ace Elev. 731.92	<u> </u>	D E P T H	B L O W S	U C S Qu (tsf)	M O I s T (%)	Surface Water Elev. ft Stream Bed Elev. ft Groundwater Elev.: First Encounter Dry ft Upon Completion Dry ft After ft	D E P T H	B L O W \$	U C S Qu (tsf)	M O I S T
		Silty Clay Loam Fill ncrete Debris and ay		_				Hard Gray Silty Clay Loam Till (continued)		4 6 7	4.9 S	18
•	Very Sliff Brow Clay Loess	vn and Gray Silly	729.42	_	3 3 3	2.0 P	27			3 4 6	4.3 S	24
	Very Stiff Gray Clay Till	and Brown Silty	Î	-5	1 2 3	2.0 P	18		-25 5.42	3 4 5	4.1 S	18
•	Hard Brownish	Gray Silty Clay Till	724.92	- - -	3 7 11	10.9 S	18	End of Boring				
DOT.GDT 11M.21				-10	4 9 12	7.8 S	21		30			
IT TOWERS GPJ IL.					4 6 9	5.4 S	29					
EA HIGH MAST LIGH				-15	6 9 12	6.1 S	17		-35			
SOIL BORING 1-67 REST AREA HIGH MAST LIGHT TOWERS.GPJ. IL, DOT.GDT 1144.21	Hard Gray Silty	y Clay Loam Till	714.42	- - -	5 7 8	5.4 S	18					
8				-20					-40			

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer) The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)

BB\$, form 137 (Rev. 8-99)

USER NAME = pletschtr	DESIGNED	REVISED
	DRAWN	REVISED
PLOT SCALE = 100.0000 / in.	CHECKED	REVISED
PLOT DATE = 3/17/2022	DATE	REVISED -

						F.A.I. RTE	SECTION		COUNTY	TOTAL SHEETS	SHEET NO.
		SOIL	BORIN	GS		57	(38-8)RA-L2		IROQUOIS	17	16
									CONTRACT	NO. 66	5M05
SCALE:	SHEET	OF	SHEETS	STA	TO STA.		ILLINOIS	FED. AII	D PROJECT		



SOIL BORING LOG

Page <u>1</u> of <u>1</u>

Date 10/13/21

	ROUTE	FAI 57 (I-57)	_ DE	SCR	PTION	١	I - 57	- Buckley Northbound R	Rest Area L	.OGG	ED BY	Larry	Myers
	SECTION	(38-8)RA-L2		_ ι	OCAT	TION _	SE 1/4	, SEC. 9, TWP. 24, RNG de 40.560555, Longitu	5. 10, 3 rd PM, de -88.061273				
	COUNTY	Iroquois DF	RILLING	ME	THOD			low Stem Auger			ME A	utoma	tic
	Station		_	D E P	B L O	U C S	M 0 1	Surface Water Elev Stream Bed Elev	ft	D E P	B L O	U C S	М О П
	Station	3 (S Tower) 1428+06 284.0 ft Lt.	_	H	S	Qu	S T	Groundwater Elev.: First Encounter Upon Completion	Dry ft	H	S	Qu	S T
	Ground Surfa	ce Elev. 720.28	ft	(ft)	(/6")	(tsf)	(%)	After Hrs	π	(ft)		(tsf)	(%)
	Augered Black Fill, Topsoil, Br	Silty Clay Loam rown Silty Clay		_				Hard Gray Silty Clay L (continued)	oam Till		4 5 7	5.1 B	19
			717.78	_						_			
	Very Stiff to Ha Silty Clay Till	ard Brown and Gray			3 4 5	3.0 P	27				5 7 8	4.7 B	19
				-5						-25		В	
				_	4 7	3.5 S	20		693.7		5 6 7	4.2 B	18
				_		3		End of Boring	693.7			ь	
				-	5					_			
				_	6 9	4.1 S	21			_			
4.21	Hard Grayish E	Brown Silty Clay Till	710.78	-10						-30			
DT 11/				-	5	7.8	17			_			
DOT.G					9	S	80-111			_			
GPJ IL				_	5					_			
OWERS				_	7	7.2	18			_			
IGHT TO				_	9	S				_			
MASTL				-15	5					-35			
BORING 1-57 RESTAREA HIGH MAST LIGHT TOWERS.GPJ IL DOT.GDT 114/21				_	8 12	8.0 S	19						
EST AR										_			
3 I-57 R				_	5 6	6.9	18			_			
BORING			700.78	_	11	S				_			
Š	Hard Gray Silty	Clay Loam Till		-20						-40			

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer) The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)

BBS, form 137 (Rev. 8-99)



SOIL BORING LOG

Page <u>1</u> of <u>1</u>

Date 10/13/21

	ROUTE	FAI 57 (I-57)	DES	CR	IPTION	١	I-57	- Buckley Northbound R	Rest Area	_ LO	GGE	ED BY	Larry	Myers
	SECTION	(38-8)RA-L2		_ 1	LOCAT	TION _	SW 1/	4, SEC. 10, TWP. 24, RM de 40.561982, Longitud	NG. 10, 3 [™] PM. de -88 06124	5				
	COUNTY	Iroquois DR	ILLING	ME	THOD			low Stem Auger			C	ME A	utoma	tic
	BORING NO Station Offset	4 (N Tower) 1423+00 298.0 ft Lt. ice Elev. 719.58		D E P T H	B L O W S	U C S Qu (tsf)	M O I S T	Surface Water Elev. Stream Bed Elev. Groundwater Elev.: First Encounter Upon Completion After Hrs.	Dry Dry	ft ft	D E P T H (ft)	B L O W S	U C S Qu (tsf)	M O I S T (%)
	Augered Black	Silty Clay Loam Fill Debris, Brown Silty						Hard Gray Silty Clay L (continued)		-		4 4 7	4.7 B	18
2	Very Stiff to Ha Silty Clay Till	ard Brown and Gray	717.08		3 3 5	3.0 P	20			-	_	4 6 7	4.1 B	16
				-5	5	4.7	18			-	-25	5	4.3	18
	Hard Grayish E	Brown Silty Clay Till	712.58	_	7 8 13	10.3 S	18	End of Boring		693.08 - -		7	В	
GDT 11M/21				-10	7 9	9.2	18			-	-30			
AREA HIGH MAST LIGHT TOWERS GPU IL_DOT.GDT 11M/21				-	7 9	S 8.1	19			-				
MAST LIGHT TO			1-	-15	5	S				-	-35			
AREA HIGH			702.58		5 9	7.4 S	19			-				
	Hard Gray Silty	/ Clay Loam Till			4 5	5.4	19			-	_			
SOIL BORING 1-67 REST				-20	9	S				-	-40			

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer) The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)

BBS, form 137 (Rev. 8-99)

USER NAME = pletschtr	DESIGNED	REVISED
	DRAWN	REVISED
PLOT SCALE = 100.0000 / in.	CHECKED	REVISED
PLOT DATE = 3/17/2022	DATE	REVISED -

STATE	0F	ILLINOIS
DEPARTMENT (DF	TRANSPORTATION

SOIL BORINGS				F.A.I. RTE			COUNTY	TOTAL SHEETS	SHEE NO.			
				57	(38-8)RA-L2		IROQUOIS	17	17			
										CONTRACT	NO. 66	M05
ALE:	SHEET	OF	SHEETS	STA	TO STA	ILLINOIS FED. AID PROJECT						