Structural Geotechnical Report

Retaining Wall #5
SN: 099-1003
I-55 at IL 59 Diverging Diamond Interchange
Station 272+24.35 to 279+35
IDOT PTB 189-011
Will County, Illinois

Prepared for



Illinois Department of Transportation (IDOT)
Contract Number: D-91-368-18

Project Design Engineer Team Alfred Benesch & Company

Geotechnical Consultant: GSG Consultants, Inc.



623 Cooper Court • Schaumburg, IL 60173 Tel: 630.994.2600 • Fax: 312.733.5612 www.gsg-consultants.com



April 28, 2021

Mr. Kurt Naus, P.E., S.E. Alfred Benesch & Company 1230 East Diehl Rd. Suite 109 Naperville, IL 60563

Structural Geotechnical Report IL 59 northbound over IL-55 Retaining Wall #5, SN: 099-1003 Contract Number: 189-011

Dear Mr. Naus:

Attached is a copy of the Structural Geotechnical Report for the above referenced project. This report provides a brief description of the site investigation, site conditions and foundation recommendations. The site investigation included advancing ten (10) soil borings to depths between 16.1 and 23.6 feet.

Should you have any questions or require additional information, please call us at 630-994-2600.

Sincerely,

Suhaib Ibrahim Project Engineer Ala E Sassila, Ph.D., P.E.

Blusarne

Principal

TABLE OF CONTENTS

1.0	INTRO	DUCTION	1
	1.1	Existing Site Conditions	2
	1.2	Proposed Retaining Wall Information	3
2.0	SITE SU	JBSURFACE EXPLORATION PROGRAM	4
	2.1	Subsurface Exploration Program	4
	2.2	Laboratory Testing Program	5
	2.3	Subsurface Soil Conditions	5
	2.4	Groundwater Conditions	6
3.0	GEOTE	CHNICAL ANALYSES	8
	3.1	Derivation of Soil Parameters for Design	8
	3.2	Settlement	9
4.0	GEOTE	CHNICAL RECOMMENDATIONS	10
	4.1	Retaining Wall Type Recommendations	10
	4.2	Retaining Wall Design Recommendations	12
	4.2.3	Subgrade Undercut Areas	17
	4.3	Drainage Recommendations	20
5.0	CONST	RUCTION CONSIDERATIONS	21
	5.1	Site Preparation	21
	5.2	Existing Utilities	21
	5.3	Site Excavation	22
	5.4	Borrow Material and Compaction Requirements	22
	5.5	Groundwater Management	22
6.0	IIMITA	ATIONS	2/



Exhibits

Exhibit 1 Project Location Map

Exhibit 2 Existing Site Conditions at Proposed Retaining Wall Location

Exhibit 3 Structural Fill Placement below MSE Wall Footing

Tables

Table 1 Retaining Wall Summary

Table 2 Summary of Subsurface Exploration Borings

Table 3 Seismic Parameters

Table 4 LRFD Load Factors for Retaining Wall Analyses

Table 5 Lateral Soil Parameters

Table 6 Recommended Bearing Resistance

Table 7 Potential Remedial Treatment Summary for West MSE Wall

Table 8 Wall Description

Table 9 Slope Stability Analyses Results

Appendices

Appendix A General Plans, Elevations, and Details

Appendix B Soil Boring Location Plan and Subsurface Profile

Appendix C Soil Boring Logs

Appendix D Laboratory Test Results
Appendix E Soil Parameters Table

Appendix F Slope Stability Analyses Exhibits

Structural Geotechnical Report Retaining Wall #5 SN: 099-1003

I-55 at IL 59 Diverging Diamond Interchange Station 272+24.35 to 279+35

Will County, Illinois IDOT PTB 189-011

1.0 INTRODUCTION

GSG Consultants, Inc. (GSG) completed a geotechnical investigation for the Phase II design of Retaining Wall #5 (SN: 099-1003) between Station 272+24.35 and 279+35, along the west side of I-55 southbound, north of the existing bridge carrying IL-59 over I-55 in Tory Township, Will County, Illinois. The purpose of this Phase II site investigation was to explore the subsurface conditions along the entire proposed structure location, to determine engineering properties of the subsurface soil, and to develop final design and construction recommendations for Retaining Wall #5 (SN: 099-1003).




Exhibit 1 – Project Location Map (Source: USGS Topographic Maps, usgs.gov)



The general scope of the overall project is the conversion of a partial access interchange to a full access interchange at I-55 and IL 59. This will include the construction a Diverging Diamond Interchange (DDI) and associated auxiliary lanes at the intersection of I-55 and IL 59. Two new ramps are proposed for the new interchange; Ramp D to provide access from I-59 to I-55 southbound, and Ramp C to provide access from I-55 to IL-59. An auxiliary lane between IL 59 and US 52 along I-55 is also proposed in each direction along the mainline. In proximity to the DDI, the existing I-55 East Frontage Road will be realigned further east. This report pertains to Wall #5 (SN: 099-1003), which will be located along I-55 SB, north of the existing bridge carrying IL-59 over I-55.

1.1 Existing Site Conditions

The proposed Retaining Wall #5 will be located along I-55 Southbound, north of the existing bridge (SN: 099-4642) carrying IL-59 over I-55. It is anticipated that the proposed wall will tie into the existing wingwall of the bridge. The area where the proposed improvements are to be built will be on existing IDOT right-of-way (ROW) and consists of an unoccupied ditch. **Exhibit 2** generally shows the existing conditions where the proposed retaining wall will be constructed.



Exhibit 2 – Existing Site Conditions at Proposed Wall Location, Looking south along I-55 SB



PTB 189-011

1.2 Proposed Retaining Wall Information

Based on the design information and drawings provided by Benesch (**Appendix A**, dated February 8, 2021), the proposed retaining wall will be carrying the proposed IL-59 Ramp A South Bound. According to the cross sections provided, the proposed retaining wall will be a "fill" section; a MSE wall is proposed for this location. **Table 1** presents a summary of the proposed wall.

Table 1 – Retaining Wall Summary

Wall Name	Wall Stations	Proposed Wall Type	Approximate Length (ft)	Maximum Anticipated Retained Wall Height* (ft)
SN: 099-1003	Sta. 272+24.35 to Sta. 279+35	MSE	710.75	24.5

^{*}Retained wall height is calculated from the top of coping to the top of levelling pad

The front face of the proposed retaining wall is located approximately 26 feet (at Station 279+20) to 61 feet (at Station 273+40) away from the proposed edge of pavement for Ramp A. It is anticipated that a new embankment will be built for Ramp A in the same stage as the construction of Wall # 5; the design and recommendations for Ramp A embankment will be presented in a separate roadway geotechnical report.



2.0 SITE SUBSURFACE EXPLORATION PROGRAM

This section describes the subsurface exploration program and laboratory testing program completed as part of this project. The proposed locations and depths of the soil borings were selected in accordance with IDOT requirements and review with Benesch for available design information at the time of the field activities. The borings were completed in the field based on field conditions and accessibility.

2.1 Subsurface Exploration Program

Soil borings were completed between October 28, 2019 through April 2, 2020. The exploration program included advancing ten (10) standard penetration test (SPT) borings at locations along the length of the proposed wall. The as-drilled locations of the soil borings are shown on the Soil Boring Location Map and Subsurface Profile (**Appendix B**). **Table 2** presents a list of the borings used for the proposed retaining wall analysis.

Table 2 – Summary of Subsurface Exploration Borings

Boring ID	Station *	Offset (ft)/ Direction	Depth (ft)	Surface Elevation (ft)
RWB-30	272+58.5	84.8 LT	23.0	593.3
RWB-15	273+19.8	85.3 LT	21.0	593.9
RWB-16	273+70.7	90.3 LT	23.0	595.4
RWB-17	274+43.9	89.3 LT	21.5	595.3
RWB-04	275+32.7	112.3 LT	16.1	595.8
RWB-05	276+6.5	107.5 LT	24.1	595.6
RWB-06	276+79.5	102.6LT	23.0	595.4
RWB-07	277+54.1	99.7 LT	23.6	595.3
RWB-08	278+69.3	100.6 LT	21.6	594.6
RWB-09	279+42.5	101.8 LT	20.5	594.4

^{*} Based on existing I-55 Stationing

The soil borings were drilled using ATV mounted Diedrich D-50 drill rig using 3½-inch I.D. hollow stem augers and an automatic hammer. Soil sampling was performed according to AASHTO T 206, "Penetration Test and Split Barrel Sampling of Soils." Soil samples were obtained at 2.5-foot intervals to the boring termination depths. Water level measurements were made in each boring



PTB 189-011

when evidence of free groundwater was detected on the drill rods or in the samples. The boreholes were also checked for free water immediately after auger removal, and before filling the open boreholes with soil cuttings.

GSG's field representative inspected, visually classified and logged the soil samples during the subsurface exploration activities and performed unconfined compressive strength tests on cohesive soil samples using a calibrated Rimac compression tester and a calibrated hand penetrometer in accordance with IDOT procedures and requirements. Representative soil samples collected from each sample interval, were placed in jars and were returned to the laboratory for further testing and evaluation.

2.2 Laboratory Testing Program

All samples were inspected in the laboratory to verify the field classifications. A laboratory testing program was undertaken to characterize and determine engineering properties of the subsurface soils encountered in the area of the proposed retaining wall. The following laboratory tests were performed on representative soil samples:

- Moisture content ASTM D2216 / AASHTO T-265
- Atterberg Limits ASTM D4318 / AASHTO T-89 / AASHTO T-90
- Dry Unit Weight ASTM D7263
- Organic Content ASTM D7348 / AASHTO T-267

The laboratory tests were performed in accordance with test procedures outlined in the IDOT Geotechnical Manual (2015), and per ASTM and AASHTO requirements. Based on the laboratory test results, the soils encountered were classified according to the AASHTO and the Illinois Division of Highways (IDH) classification systems. The results of the laboratory testing program are included in the **Appendix D Laboratory Test Results** and are also shown along with the field test results in **Appendix C Soil Boring Logs**.

2.3 Subsurface Soil Conditions

This section provides a brief description of the soils encountered in the borings performed in the vicinity of the proposed retaining wall. Variations in the general subsurface soil profile were noted during the drilling activities. Detailed descriptions of the subsurface soils are provided in



the Soil Boring Logs (**Appendix C**). The soil boring logs provide specific conditions encountered at each boring location, including soil descriptions, stratifications, penetration resistance, elevations, location of the samples, water levels (when encountered), and laboratory test data. Variations in the general subsurface soil profile were noted during the drilling activities. The stratifications shown on the boring logs represent the conditions only at the actual boring locations and represent the approximate boundary between subsurface materials; however, the actual transition may be gradual.

The surface elevations of these borings ranged between 593.9 and 595.8 feet. The borings noted 4 to 6 inches of topsoil followed by silty clay fill to depths between 3.0 and 8.5 feet. Below the fill, soft to hard silty clay was encountered at depths between 3.5 and 21.0 feet with unconfined compressive strength values ranging from 0.4 and 7.1 tsf, with most values between 2.5 and 5.5 tsf. The soil color changed from brown and gray to gray at depths between 10.0 and 13.5 feet. The unconfined compressive strength values of the upper brown and gray clay ranged from 0.8 and 6.7 tsf, with most values between 2.5 and 5.5 tsf. The unconfined compressive strength of the gray silty clay ranged from 0.4 to 6.25 tsf, with most values between 2.0 and 5.0 tsf. Medium dense to extremely dense silty loam or gravel were encountered at depths between 16.0 and 21.0 feet with SPT blow count (N) values ranging from 12 to 100 blows per foot. Borings RWB-04, RWB-05, and RWB-06 encountered highly weathered limestone at depths between 21.0 and 24.0 feet, where the borings were terminated upon encountering auger refusal. The remaining borings were also terminated upon auger refusal on apparent bedrock.

2.4 Groundwater Conditions

Water levels were checked in each boring to determine the general groundwater conditions present at the site and were measured while drilling and after each boring was completed. Ground water was encountered in borings RWB-06, RWB-07, and RWB-15 to RWB-17 at depths between 11.0 to 20.0 feet while drilling. No groundwater was observed after drilling at these locations or within the remaining borings at these times. No delayed groundwater readings were obtained as the borings were backfilled immediately upon completion.

Based on the color change from brown and gray to gray, it is anticipated that the long-term groundwater level could range between elevations 582.0 to 585.0 feet. Water level readings were made in the boreholes at times and under conditions shown on the boring logs and stated



PTB 189-011

in the text of this report. However, it should be noted that fluctuations in groundwater level may occur due to variations in rainfall, other climatic conditions, or other factors not evident at the time measurements were made and reported herein.



PTB 189-011

3.0 GEOTECHNICAL ANALYSES

This section provides GSG's geotechnical analysis and recommendations for the design of the proposed retaining wall based on the results of the field exploration, laboratory testing, and geotechnical analysis. Subsurface conditions in unexplored locations may vary from those encountered at the boring locations. If structure locations, loadings, or elevations are changed, we request that GSG be contacted so that we may re-evaluate our recommendations.

3.1 Derivation of Soil Parameters for Design

GSG determined the geotechnical parameters to be used for the project design based on the results of field and laboratory test data on individual boring logs as well as our experience. Unit weights, friction angles and shear strength parameters were estimated using corrected standard penetration test (SPT) using published correlations for N values results for the fill and cohesionless soils and in-situ and laboratory test results for cohesive soils. The SPT N values were corrected for hammer efficiency. The hammer efficiency correction factor considers the use of a safety hammer/rope/cat-head system, generally estimated to be 60% efficient. Thus, correlations should be based upon what is currently termed as N_{60} data. The efficiencies of the automatic hammers used for this exploration were estimated to be approximately 98% for the ATV mounted Diedrich D-50 and based on recent efficiency testing of the drill rigs. The correction for hammer efficiency is a direct ratio of relative efficiencies as follows:

 $N_{60} = N_{Field} * (98/60)$: Diedrich D-50 ATV

* Where the N_{Field} value is the blow counts recorded during the subsurface investigation.

Based on the field investigation data collected, generalized soil parameters for the soils in the project area for use in design are presented in **Appendix E**.



3.2 Settlement

Based on the GPE and provided construction sequence, Wall # 5 will be constructed at the same stage as the Ramp A embankment. Total settlement is anticipated to be approximately 1 to 3 inches depending on the height of the wall and embankment. It is anticipated that the Ramp A paving operations will be delayed to allow settlement to occur for a period of preloading under the self-weight of the embankment and wall. Wall #5 settlement will be discussed in *Section 4.2.5* of this report. Settlement of the Ramp A embankment will be discussed in a separate roadway report.



PTB 189-011

4.0 GEOTECHNICAL RECOMMENDATIONS

This section provides GSG's geotechnical recommendations for the design of the proposed retaining wall based on the results of the field exploration, laboratory testing, and geotechnical analyses, and information provided by the designer. If there are any significant changes to the project characteristics or if significantly different subsurface conditions are encountered during construction, GSG should be consulted so that the recommendations of this report can be reviewed

4.1 Retaining Wall Type Recommendations

There are several types of retaining walls that could be utilized for retaining earth embankments in fill areas or excavation slopes in cut areas. Based on the proposed grading, it appears that the proposed wall is located within a fill area, adjacent to the roadway possible wall types may include cast-in-place concrete cantilever, Mechanically Stabilized Earth (MSE), prefabricated modular gravity, steel sheet piles, and soldier-pile and lagging.

The wall type should be selected based on soil conditions, construction schedule, and cost. The following provides a brief description of each type of wall that could be considered at this location.

A. CIP Concrete Cantilever Walls

CIP concrete cantilever retaining walls are typically used in fill areas. They are constructed with a footing that extends laterally both in front of and behind the wall. They can be designed to resist horizontal loading with or without tie-backs by changing the geometry of the foundation. This type of wall typically requires that the area behind the wall be excavated to facilitate construction or are constructed where new fill embankments are necessary.

The advantages of a CIP wall include that it is a conventional system with well-established design procedures and performance characteristics; it is durable; and it has the ability to easily be formed, textured, or colored to meet aesthetic requirements. Disadvantages include a relatively long construction period due to undercutting, excavation, form work, steel placement, and curing of the concrete. This wall system is also sensitive to total and differential settlements.



PTB 189-011

B. Mechanically Stabilized Earth Walls

An MSE wall is typically associated with fill wall construction and consists of facing such as segmental precast units, dry block concrete or CIP concrete facing units connected to horizontal steel strips, bars or geosynthetic to create a reinforced soil mass. The reinforcement is typically placed in horizontal layers between successive layers of granular backfill. A free draining backfill is required to provide adequate performance of the wall. MSE walls can be used in cut situations as well. The additional cost of the excavations for an MSE wall is usually offset by the savings in construction costs and schedule as compared to a CIP wall on spread footings.

Advantages of the MSE wall include a relatively rapid construction schedule that does not require specialized labor or equipment, provided excavation for the reinforcement is not extensive. This type of retaining wall can accommodate relatively large total and differential settlements without distress, and the reinforcement materials are light and easy to handle. Facing panels can be designed for various architectural finishes.

The design of MSE walls for internal stability is the Contractor's responsibility and will need to be designed by a licensed Structural Engineer in the State of Illinois. The length of the reinforced soil mass from the outside face should be a minimum of 8 feet, but not less than 70% of the wall height. The length should be determined to satisfy eccentricity and sliding criteria and provide adequate length to prevent structural failure with respect to pullout and rupture of reinforcement. The MSE wall could be designed using a unit weight of 120 pcf and a friction angle of 34 degrees for the reinforced backfill soil.

C. Prefabricated Modular Gravity Walls

This type of wall typically consists of interlocking soil or rock-filled concrete, steel, or wire modules or bins (such as gabions). The combined weight of the wall materials resists the lateral loads from the soil embankment being retained. This type of wall may be used where conventional reinforced concrete walls are also being considered but are typically selected when the overall wall height will be less than 25 feet.

The advantage of this type of wall is that less select fill is required for the backfill behind the wall and the construction is relatively more economical compared to other wall types; however, this type of wall may require additional soil excavation for placement of the modules. The additional



PTB 189-011

cost of the excavations could be offset by the savings in construction costs and schedule as compared to other walls.

D. Soldier Pile and Lagging Walls

Soldier pile and lagging walls are typically used in cut areas where the existing ground surface needs to be maintained during construction or when a near vertical excavation is needed. The wall may be constructed with driven steel piles or steel piles placed in drilled holes and backfilled with concrete. The depth of the soldier pile is normally estimated to be two times the wall exposed height. Soldier piles are typically spaced at 8 foot on center and are faced with cast-in-place or precast concrete. The cost for this type of wall is generally higher than gravity wall. However, there is fewer restriction for the installation this type of wall.

E. Recommended Wall Type

Based on the nature of the site conditions and preliminary designs provided by the design team, GSG concurs with the Benesch's design selection of a MSE wall for this section of the project. Design plans indicate that the wall location would require filling to reach the proposed roadway subgrade.

GSG evaluated the global and external stability, and settlement to determine the suitability of the retaining wall for this section of the project. The wall section should be analyzed to determine that adequate factors of safety relative to sliding and overturning failure. The contractor is responsible for providing detailed internal stability design for the wall.

4.2 Retaining Wall Design Recommendations

The engineering analyses performed for evaluation of the retaining wall options followed the current AASHTO Load and Resistance Factor Design (LRFD) Methodology. LRFD methodology incorporates the use of load factors and resistance factors to account for uncertainty in applied loads and load resistance of structure elements separately. The AASHTO LRFD Bridge Design Specifications outline load factors and combinations for various strength, extreme event, service, and fatigue limit states. Section 11, which outlines geotechnical criteria for retaining walls, of the AASHTO Specifications requires the evaluation of bearing resistance failure, lateral sliding, and overturning at the strength limit state and excessive vertical displacement, excessive lateral displacement, and overall stability at the service limit state. The selected wall should be also



PTB 189-011

evaluated with respect to the collision load. **Table 4** outlines the load factors used in evaluation of the retaining wall in accordance with AASHTO Specification Tables 3.4.1-1 and 3.4.1-2.

Table 4 - LRFD Load Factors for Retaining Wall Analyses

	Type of Load	Sliding and Eccentricity	Bearing Resistance	Sliding and Eccentricity	Bearing Resistance	Settlement Service I
		Strength I	Strength I	Extreme II	Extreme II	
Load Factors for	Dead Load of Structural	0.90	1.25	1.00	1.00	1.00
Vertical Loads	Components (DC)					
	Vertical Earth Pressure Load (EV)	1.00	1.35	1.00	1.00	1.00
	Earth Surcharge Load (ES)		1.50			
	Live Load Surcharge (LS)		1.75		0.50	1.00
	Horizontal Earth Pressure	1.50		1.00	1.00	1.00
	Load (EH)					
Load Factors for	Active		1.50			
Horizontal	At-Rest		1.35			
Loads	AEP for anchored walls		1.35			
	Earth Surcharge (ES)	1.50	1.50			
	Live Load Surcharge (LS)	1.75	1.75	0.50	0.50	1.00
Load Factor for				1.00	1.00	
Vehicular						
Collision						

4.2.1 Lateral Earth Pressures and Loading

The wall should be designed to withstand earth and live lateral earth pressures. The lateral earth pressures on MSE walls should be determined in accordance with AASHTO 3.11.5.8. Earth loads of retained soils behind the MSE wall may be calculated using an active earth pressure coefficient, K_a, calculated using the Coulomb Theory with a back slope angle of 9.5° (1V:6H) shown in the GPE. **Table 5** presents soil design properties for the retaining wall for the anticipated soil types at this site.



Table 5 – Lateral Soil Parameters

		Long-term/Drained			Soil Parameters used in L-Pile		
Elevation Range (feet)	Soil Description	$ \begin{array}{cccccccccccccccccccccccccccccccccccc$		- 10 11000 = 011 011	Coefficient of Lateral Modulus of Subgrade Reaction (k _{py} , pci)	Soil Strain (E ₅₀)	Soil Type
	New Engineered Clay Fill	0.42	4.95	0.58	500	0.01	Stiff Clay w/o free water (Reese)
	New Engineered Granular Fill	0.34	7.56	0.50	90	N/A	Sand (Reese)
595-591	Brown and Gray FILL Silty Clay	0.42	4.95	0.58	1,240	0.005	Stiff Clay w/o free water (Reese)
591-583	Brown and Gray Very Stiff to Hard Silty Clay	0.37	6.80	0.53	2,050	0.004	Stiff Clay w/o free water (Reese)
583-579	Gray Very Stiff to Hard Silty Clay	0.37	6.80	0.53	1,740	0.004	Stiff Clay w/o free water (Reese)
579-574	Gray Medium Dense to Dense Loam or Gravel	0.26	16.40	0.41	90	N/A	Sand (Reese)

^{*}The initial p-y modulus, E_{py} , varies linearly with depth. To obtain E_{py} use the equation $E_{py} = k_{py} * z$, where k_{py} is the coefficient of lateral modulus of subgrade reaction given in the table and z is the distance from the surface to the center point of the layer in inches.

PTB 189-011

Traffic and other surcharge loads should be included in the retaining wall design. A live load surcharge shall be applied where vehicular load is expected to act on the surface of the backfill within a distance equal to one-half the wall height behind the back face of the wall in accordance with AASHTO 3.11.6.4. The live load surcharge may be estimated as a uniform horizontal earth pressure due to an equivalent height (H_{eq}) of two feet of soil.

The retaining walls design should include a drainage system to allow movement of any water behind the wall, and not allowing hydrostatic (seepage) pressures to develop in the active soil wedge behind the wall. This could be accomplished by placing a Geocomposite Wall Drain over the entire length of the back face of the wall connected to 6-inch diameter perforated drain pipe and backfilling a minimum of 2 feet of free draining materials, Porous Granular Embankment, as measured laterally from the back of the wall. The backfill should be placed in accordance with the IDOT SSRBC. Heavy compaction equipment should not be allowed closer than five (5) feet to the retaining wall to prevent inducing high lateral earth pressures and causing wall yielding and/or other damage. The passive lateral earth pressure coefficient (Kp) from the upper 3.5 feet of level backfill at the toe of the wall should be neglected, unless the soil is confined or protected by a concrete slab or well drained pavement. The passive lateral earth pressure coefficient from the upper 3.5 feet of soil for a descending slope at the wall toe should also be neglected, regardless of any surface protection.

4.2.2 Bearing Resistance

It is anticipated that the MSE wall will bear on existing/new fill, or native silty clay. Bearing resistance for the retaining wall founded on a granular fill leveling pad shall be evaluated at the strength limit state using load factors (See **Table 4**), and factored bearing resistance. The bearing resistance factor, φ_b , for an MSE wall is 0.65 per AASHTO Table 11.5.7-1. The bearing resistance shall be checked for the extreme limit state with a resistance factor of 1.0. **Table 6** presents the proposed bearing elevation and recommended bearing resistances of suitable materials to support the wall system. By preloading the bearing soils with the new embankment and wall construction for specific time periods as noted, the service limit bearing resistances can increase as the duration after construction. Bearing resistance values after one month and three months of preloading are presented in **Table 6**.



PTB 189-011

Table 6 – Recommended Bearing Resistance

Station	Bearing Elevation (feet) ¹	Maximum Retained Wall Height/Width	Nominal Resistance (ksf) ²	Factored Bearing Resistance (ksf)	inch Settlement Service inch Limit (ksf)		inch Set	Resistanc tlement S imit (ksf) oading Da	Service	Anticipated Bearing Soil	
		(ft)	(KSI)	(KSI)	0 ³	30 ⁴	90 ⁴	0 ³	30 ⁴	90 ⁴	
272+24.35 to 273+40	589.1 to 592.8	24.5/19.0	15.8	10.3	1.3	2.7	3.5	2.0	3.6	4.4	Existing /New Fill
273+40 to 279+35	592.8 to 589.2	14.5/12.0	15.8	10.3	1.8	3.4	4.2	3.9	5.6	6.1	Existing /New Fill or Native Silty Clay

^{1.} Elevations estimated from GP&E dated 02/08/2021

^{2.} Includes undercut recommendations in Table 7

^{3.} Based on the existing soil profile before any staged construction.

^{4.} Assuming preloading with the full height of new embankment and Wall #5 and the soil strength parameters be the same as existing soil profile.

The minimum depth of the wall foundation should be 3.5 feet below the final exterior grade to alleviate the effects of frost. The subgrade soils encountered at the bearing elevation should be cleared of any unsuitable material, such as topsoil. Based on the results of the subsurface exploration, we anticipate the wall would be supported upon the soil types noted in **Table 6.**

4.2.3 Subgrade Undercut Areas

Based on the soil conditions along the wall alignment, it is anticipated that existing silty clay fill with low unconfined compressive strength and/or high moisture contents will be encountered near bearing elevation between Stations 273+00 and 274+12, and Stations 277+25 and 278+00. When encountered, these soils are not generally considered suitable for bearing and should be removed during construction. Cohesive materials exhibiting moisture contents greater than 27% and unconfined compressive strengths less than 2.0 tsf if encountered should be removed during construction.

Table 7 – Potential Remedial Treatment Summary for MSE Wall

Station				Remedial	Undercut	
From	То	Wall Height (feet)	Soil Description	Top Elevation (feet)	Depth (feet)	Reason for Undercut
273+00	273+50	22.0	Existing Fill	592.0	2	Qu < 2 tsf, Moisture >27%
273+50	274+12	16.0	Existing Fill	592.5	3	Moisture >27%
277+25	278+00	14.0	Existing Fill	591.0	2	Qu < 2 tsf

Undercut areas should be replaced with granular structural fill in accordance with IDOT standard construction requirements. The lateral limit of the structural fill should extend a minimum of 1 foot beyond the edge of the MSE wall, then an additional 1 foot laterally for every 2 feet of structural fill depth as depicted in **Exhibit 3**. The granular structural fill should be placed and compacted to a minimum of 95% of the maximum dry density, as determined by AASHTO T-180: Standard Test Methods for Moisture-Density Relations of Soils and Soil-Aggregate Mixtures (ASTM D1557) in accordance with IDOT standard construction requirements.






Exhibit 3 - Structural Fill Placement below MSE Wall Footing

4.2.4 Sliding and Overturning Stability

The wall base width should be sufficient to resist sliding. The frictional resistance shall include the friction between granular backfill for the wall and supportive cohesive or granular soils, and the friction between the wall foundation and bearing soils.

The factored resistance against sliding should be calculated using equation 10.6.3.4-1 in the AASHTO LRFD manual. A sliding resistance factor, ϕ , of 1.0 (Table 11.5.7-1) shall be applied to the nominal sliding resistance of soil-on-soil beneath the MSE wall. A maximum frictional coefficient of 0.53 (tan 28 degrees) could be used for determining the sliding resistance for the soil to soil interfaces. The width of the MSE wall (length of the reinforcing) must be wide enough to resist overturning forces. The location of the resultant of the forces shall be within the middle two-thirds of the MSE base width.

4.2.5 Wall Settlement

Settlement of the MSE wall depends on the foundation size and strength and compressibility characteristics of the underlying bearing soil. Assuming the foundation subgrade has been prepared as recommended above and the service bearing resistances as mentioned in **Table 6** are used, the settlement of the MSE wall will be on the order of 1 to 2 inches. Differential



settlement between two points of 100 feet apart along the length of the wall will be ½ inch or less. AASHTO 11.10.4.1 provides guidelines regarding the maximum total and differential tolerable settlements for various facing of MSE walls. Settlement of the entire ramp embankment will be discussed in the roadway report.

4.2.6 Overall Stability

The MSE wall should be designed for external stability of the wall system as well as the internal stability of the reinforced soil mass behind the wall facing. The wall contractor should confirm stability requirements based on the final wall configurations. The following parameters were used to evaluate the wall.

Table 8a – Wall Description: Sta. 272+24.35 to Sta. 274+00 *Based on GPE dated 02/08/2021

Maximum total retained height of the retaining wall (H)*	24.5 feet
Minimum length of reinforcement	19.0 feet
Unit weight of the retained soil (embankment)	120 pcf
Unit weight of the reinforced soil mass	120 pcf

Table 8b – Wall Description: Sta. 274+00 to Sta. 279+35

*Based on GPE dated 02/08/2021

Maximum total retained height of the retaining wall (H)*	14.5 feet
Minimum length of reinforcement (0.7xH)	12.0 feet
Unit weight of the retained soil (embankment)	120 pcf
Unit weight of the reinforced soil mass	120 pcf

The actual wall width, and total height of the wall should be based on structural analysis performed by a Licensed Structural Engineer in the State of Illinois.

Slide 2018 is a comprehensive slope stability analysis software used to evaluate the proposed wall for the project based on the limit equilibrium method. The proposed wall was analyzed based on the preliminary grading and the soils encountered while drilling. A circular failure analyses were evaluated using the simplified Bishops analyses methods for the proposed wall geometry. The analyses were performed using the soil parameters in **Appendix C**. Based on the proposed geometry and the soil borings, global stability analyses were performed.



4.2.7 Global Slope Stability Results

A circular failure analysis was evaluated for both a short term (undrained) and long term (drained) conditions for the proposed retaining wall. The analyses were performed at Station 272+24, at the anticipated maximum wall height section, and Station 277+50 where undercuts are anticipated at bearing level. The results of the analyses are shown in **Table 11**.

Table 9 – Slope Stability Analyses Results

Analysis Exhibit	Station	Analysis Type	Factor of Safety	Minimum Factor of Safety
Exhibit 4a	272+24	Circular – Short Term	3.6	1.5
Exhibit 4b	2/2+24	Circular – Long Term	1.9	1.5
Exhibit 4c	277+50	Circular – Short Term	3.1	1.5
Exhibit 4d	277+30	Circular – Long Term	2.0	1.5

Based on the analyses performed, the proposed retaining wall meets the IDOT minimum factor of safety of 1.5 for a fill section. Summaries of the slope stability analyses are included in the Slope Stability Analyses Exhibits (**Appendix F**).

4.3 Drainage Recommendations

The wall should be designed to prevent the buildup of hydrostatic forces. This can be done with the construction of a base drain and back drain to collect and remove surface water away from the face of the wall. Geocomposite Wall Drain or open grade stone with a geotextile fabric system should be placed over the entire length of the back face of the wall.



PTB 189-011

5.0 CONSTRUCTION CONSIDERATIONS

All work performed for the proposed project should conform to the requirements in the IDOT Standard Specifications for Road and Bridge Construction (2016). Any deviation from the requirements in the manuals above should be approved by the design engineer.

5.1 Site Preparation

All of the borings were completed within the existing IDOT property right-of-way (ROW). Based on the existing site conditions at the proposed wall location west of the existing roadway, it is anticipated that the surface will require stripping of vegetation and surface topsoil from the vicinity of the proposed wall. It is anticipated that topsoil stripping depths could be on the order of about 6 inches, however thicker deposits may be present at the base of the drainage ditch. After stripping, areas intended to support new wall elements or new engineered fill should be carefully evaluated by a geotechnical engineer.

Where possible, the engineer may require proof-rolling of the subgrade with a 20 to 30-ton loaded truck or other pneumatic-tired vehicle of similar size and weight. The purpose of the proof-rolling is to locate soft, weak, or excessively wet soils present at the time of construction. Proof-rolling should be performed during a time of good weather and not while the site is wet, frozen, or severely desiccated. Any unsuitable materials observed during the evaluation and proof-rolling operations should be undercut and replaced with compacted structural fill and/or stabilized in-place. The possible need for, and extent of, undercutting and/or in-place stabilization required can best be determined by the geotechnical engineer at the time of construction. Once the site has been properly prepared, at grade construction may proceed.

5.2 Existing Utilities

Based on the existing site conditions, significant utilities may exist along the project corridor that may interfere with construction of the proposed widening of the roadway and the retaining wall construction.

Before proceeding with construction, any existing utility lines that will interfere with construction should be completely relocated from beneath the proposed construction areas. Where possible, existing utility lines that are to be abandoned in place should be removed and/or plugged with a minimum of 2 feet of cement grout. All excavations resulting from underground utility removal



PTB 189-011

activities should be cleaned of loose and disturbed materials, including all previously placed backfill, and backfilled with suitable fill materials in accordance with the requirements of this section. During the clearing and stripping operations, positive surface drainage should be maintained to prevent the accumulation of water.

5.3 Site Excavation

Site excavations are expected to encounter various types of soils as described in the Subsurface Exploration section of this report. The contractor will be responsible to provide a safe excavation during the construction activities of the project. All excavations should be conducted in accordance with applicable federal, state, and local safety regulations, including, but not limited to the Occupational Safety and Health Administration (OSHA) excavation safety standards. Excavation stability and soil pressures on temporary shoring are dependent on soil conditions, depth of excavations, installation procedures, and the magnitude of any surcharge loads on the ground surface adjacent to the excavation. Excavation near existing structures and underground utilities should be performed with extreme care to avoid undermining existing structures. Excavations should not extend below the level of adjacent existing foundations or utilities unless underpinning or other support is installed. It is the responsibility of the contractor for field determinations of applicable conditions and providing adequate shoring for all excavation activities.

5.4 Borrow Material and Compaction Requirements

If borrow material is to be used for onsite construction, it should conform to Section 204 "Borrow and Furnish Excavations" of the IDOT Construction Manual (2016).

5.5 Groundwater Management

It is anticipated that the long-term water table is between elevations 582.0 to 585.0 feet. GSG does not anticipate groundwater related issues during construction activity based on the predominantly cohesive nature of the site and propose design; however, water may become perched in the fill material encountered near the surface. If rainwater run-off or perched water is accumulated at the base of excavation, the contractor should remove accumulated water using conventional sump pit and pump procedures and maintain a dry and stable excavation. The location of the sump should be determined by the contractor based on field conditions. During earthmoving activities at the site, grading should be performed to ensure that drainage is maintained throughout the construction period. Water should not be allowed to accumulate



PTB 189-011

in the foundation area either during or after construction. Undercut and excavated areas should be sloped toward one corner to facilitate removal of any collected rainwater or surface run-off. Grades should be sloped away from the excavations to minimize runoff from entering.

If water seepage occurs during excavations or where wet conditions are encountered such that the water cannot be removed with conventional sumping, we recommend placing open grade stone similar to IDOT CA-7 to stabilize the bottom of the excavation below the water table. The CA-7 stone should be placed to 12 inches above the water table, in 12-inch lifts, and should be compacted with the use of a heavy smooth drum roller or heavy vibratory plate compactor until stable. The remaining portion of the excavation beneath the footings should be backfilled using approved structural fill.




6.0 LIMITATIONS


This report has been prepared for the exclusive use of the Illinois Department of Transportation and its Design Section Engineer consultant. The recommendations provided in the report are specific to the project described herein and are based on the information obtained at the soil boring locations within the proposed retaining wall area. The analyses have been performed, and the recommendations provided in this report, are based on subsurface conditions determined at the location of the borings. This report may not reflect all variations that may occur between boring locations or at some other time, the nature and extent of which may not become evident until during the time of construction. If variations in subsurface conditions become evident after submission of this report, it will be necessary to evaluate their nature and review the recommendations presented herein.



APPENDIX A

General Plans, Elevations, and Details





Ardmore Roderick
1500 West Carroll Ave
Ardmore Roderick
312-795-1400 PLOT DATE = 2/08/2021

DRAWN - JPK

CHECKED - JCE


REVISED -


REVISED -


STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION**


2018-075-R WILL CONTRACT NO. 62H15 SHEET 2 OF 2 SHEETS

APPENDIX B SOIL BORING LOCATION PLAN AND SUBSURFACE PROFILE









APPENDIX C SOIL BORING LOGS



Page $\underline{1}$ of $\underline{1}$

Date ___11/1/19

ROUTEI-5	5 and IL 59	DE	SCR	IPTIOI	N		Retaining Wall 5		LOG	SED BY _	NP
SECTION	2018-075-R		[_OCA1	TION _	I-55 SI	B off shoulder, SEC. , TV	VP., RNG.,			
						Latitu	ide , Longitude				
COUNTY	VILL D	RILLING	G ME	THOD			HSA	HAMMER	TYPE	AUTO)
STRUCT. NO	099-1003		D	В	U	M	Surface Water Elev	N/A	ft		
Station			E	L	С	0	Stream Bed Elev.				
			P	0	S	I					
BORING NO			T	W		S	Groundwater Elev.:				
Station	275+32.73		Н	S	Qu	T	First Encounter _				
Offset	112.32ft LT		,,,	//am		(0/)	Upon Completion _	N/A	ft		
Ground Surface		<u>ft</u>	(ft)	(/6")	(tsf)	(%)	After N/A Hrs.	N/A	ft		
6 inches of Topsoil		591.15									
Dark Gray, Moist				1							
FILL: SILTY CLAY	, trace organics	i		2							
			_	7	2.5	25					
				9	Р						
			_								
		588.15									
Very Stiff		500.10		3							
Brown and Gray, V				2	2.3	28					
SILTY CLAY, trace	e sand and			5	В						
gravel (CH)			5								
		E0E 0E	_	-							
Very Stiff to Hard		585.65		3							
Brown, Moist			_	5	5.2	21					
SILTY CLAY, trace	sand and			8	B.2						
gravel (CL/ML)			_		ь						
				-							
			_	2							
				3	4.0	00					
			_	-	4.2	22					
			<u>-10</u>	9	В						
			_								
				_							
			_	5							
				12	3.8	22					
				11	В						
		578.15									
Very Stiff				3							
Gray, Moist	1 (01 (141)			6	2.9	22					
SILTY CLAY, trace	sand (CL/ML)		-15	8	В						
		575.65		1							
LIMESTONE, high	ly weathered	575.55		50/1"/		6 /					
Auger refusal at 16		_									
End of Boring											
			_	1							
				-							
			_	-							
			<u> </u>	1							
			-20	į.			II.				



Page $\underline{1}$ of $\underline{1}$

Date 10/28/19

ROUTE	I-55 and IL 59	DE	SCR	IPTIO	N		Retaining Wall 5	L0	OGG	ED BY	N	IP
SECTION	2018-075-R		L	OCA1	TION _	I-55 SI	3 off shoulder, SEC., TWP., RNG.	,				
COUNTY	WILL D	RILLIN	G ME	THOD		Lautu	de , Longitude HSA HAMMER	RTYPE		AL	JTO	
Station	. 099-1003		D E P	B L O	U C %	0 - 0 M	Surface Water Elev. N/A Stream Bed Elev. N/A	ft ft	D E P	ВГО	% ∩ С	0-0
Station Offset	RWB-05 276+6.55 107.53ft LT face Elev. 595.60		H (ft)	W S (/6")	Qu (tsf)	S T (%)	Groundwater Elev.: First Encounter	ft	H (ft)	W S (/6")	Qu (tsf)	S T (%)
6 inches of To	psoil	595.10						_				
Brown and Gra	ay, Moist LAY, trace sand and			4	2.9	24	LIMESTONE, highly weathered and fractured	574.60		13 15		10
				8	В					33		
Very Stiff to Ha	ard ay, Moist	592.10		1 2	2.5	19	Auger refusal at 24.1 feet End of Boring	571.50		5 50/1"		11
SILTY CLAY, gravel (CL/ML	trace sand and)		<u>-5</u>	6	В		Little of Borning		-25			
				4	6.3	19						
				8	В				_			
			_	3	6.7	19			_			
			<u>-10</u>	7	В				-30			
Very Stiff Gray, Moist		584.60		3	3.3	23						
SILTY CLAY,	trace sand (CL/ML)			6	В							
			_	4	2.9	20			_			
			-15	7	В				-35			
Medium Dense Gray, Moist SILTY LOAM, gravel (ML)	e trace sand and	579.60		4 6 5		18						
. ,				2								
			-20	4 8		19			-40			



Page $\underline{1}$ of $\underline{1}$

Date __10/28/19_

ROUTE	I-55 and IL 59	DE	SCR	IPTIO	N		Retaining Wall 5		L0	OGG	ED BY	<u> </u>	IP
SECTION	2018-075-R		_ ı	_OCA1	TION _	I-55 SI	B off shoulder, SEC. , TWP. , l	RNG.,					
						Latitu	ide . Longitude						
COUNTY	WILL DI	RILLING	3 ME	THOD	·		HSA HA	MMER	TYPE		AL	JTO	
STRUCT. NO.	099-1003		D E P	B L O	U C S	M O I	Surface Water Elev Stream Bed Elev.	N/A	_ ft	D E P	B L O	U C S	M O I
Station Offset	RWB-06 276+79.52 102.60ft LT		H	W S	Qu	S T	Groundwater Elev.: First Encounter Upon Completion	N/A	_ ft	T H	W S (/6")	Qu (tsf)	s T (%)
	ace Elev. 595.40			(10)	(131)	(70)	After <u>N/A</u> Hrs	IN/A	_ π	(11)	(10)	(131)	(/0)
Brown and Gra	soil	__ 595.10	_										
FILL: SILTY CL	AY, trace sand and	i		2			LIMESTONE, highly weathe	red	574.40	<u> </u>	4		
gravel	,		_	4	2.1	26	and fractured	icu		_	10		14
				5	B	20					27		17
			_				Auger refusal at 23.0 feet		572.40	_			
		591.90					End of Boring		312.40				
Very Stiff to Ha	rd	001.00		2						-			
Brown and gray	, Moist to Very			3	2.3	25							
Moist SILTY CLAY, tr	ace sand and		-5	5	В					-25			
gravel (CL/ML)													
. ,													
			_	3	0.4	40							
				6 7	3.1	19							
			_	/	В					_			
			_	3									
				5	4.6	21							
			-10	R	В	'				-30			
			-10		_					30			
		584.40	_										
Hard				3									
Gray, Moist				6	5.6	21							
SILTY CLAY, tr gravel (CL/ML)				8	В								
gravor (OZ/MZ)													
				2		0.4							
			_	6	4.4 B	21							
			<u>-15</u>	9	В					35			
		F70 40	_							_			
Medium Dense		579.40		5									
Gray, Very Moi			-	7		23				-			
SILŤÝ LOAM, t	race sand (ML)			9									
			_							_			
				1									
			_	4						_			
				4		23							
			-20	5						-40			



Page $\underline{1}$ of $\underline{1}$

Date 11/1/19

ROUTE	I-55 and IL 59	DE	SCR	IPTIOI	N		Retaining Wall 5	L0	ogg	ED BY	N	NP
SECTION	2018-075-R		[_OCA	ΓΙΟΝ _	I-55 SI	3 off shoulder, SEC. , TWP. , RNG. ,					
						Latitu	ide Longitude					
COUNTY	WILL DI	RILLING	G ME	THOD)		HSA HAMMER	TYPE		AL	JTO	
			D	В	U	М			D	В	U	М
	099-1003		E	L	C	Ö	Surface Water Elev. N/A	_ ft	E	L	C	Ö
Station			P	ō	s	i	Stream Bed Elev. N/A	_ 11	P	0	s	i
BORING NO.	RWB-07		Т	W		S	Groundwater Elev.:		Т	W		S
Station	277+54.10		Н	S	Qu	T	First Encounter 574.3	ft ▼	Н	S	Qu	Т
Offset	99.68ft LT						Upon Completion N/A					
	ace Elev. 595.30	ft	(ft)	(/6")	(tsf)	(%)	After N/A Hrs. N/A	ft	(ft)	(/6")	(tsf)	(%)
6 inches of Top	osoil	594.80										
Gray and Black	k, Very Moist							574.30	▼_			
FILL: SILTY CI	_AY, trace organics			2			Dense		-	7		
				3	1.0	30	Gray, Moist			18		19
				3	Р		SAND AND GRAVEL, with Limestone fragments			23		
							Linestone hagments	572.30				
		591.80					LIMESTONE, highly weathered	571.70				
Soft to Hard				2			Auger and split spoon refusal at	<u> </u>		50/1"/		
Brown and gra	y, Moist to Very			2	0.8	25	23.6 feet End of Boring	J				
SILTY CLAY, t	race sand and			3	В		End of Borning		-25			
gravel (CL/ML)												
				_								
				3								
				4	6.7	28						
			_	4	В				_			
			_						_			
				3		40						
				7 9	6.7	19						
			10	9	В				30			
			_						_			
Very Stiff		584.30		5								
Gray, Moist			-	7	2.5	23			-			
	and gravel (CL)			9	2.5 B	23						
	• ,		_	3	В							
		504.00										
Stiff to Very Sti	ff	581.80		2								
Gray, Moist				4	3.5	23						
SILTY CLAY, t				7	В	20						
gravel (CL/ML)			15						35			
			_						_			
				5								
			_	4	1.0	23			-			
				6	В	-						
			_						_			
		576.80		1								
Medium Dense)	2. 0.00		2					_			
Gray, Moist				4		15						
SILTY LOAM,	trace sand (ML)		-20	8					-40			



Page $\underline{1}$ of $\underline{1}$

Date 11/6/19

ROUTE I-55 and IL 59	DESC	RIPTIO	N		Retaining Wall 5	LC	OGG	ED BY		NP
SECTION 2018-075-R		LOCA	TION _	I-55 SI	B off shoulder, SEC. , TWP. , RNG. ,	1				
			_	Latitu	ide , Longitude					
COUNTY WILL DRIL	LING N	ETHOL	·		HSA HAMMER	I I YPE		AL	110	
	D	В	U	М	2 6 14 6 -	•	D	В	U	М
STRUCT. NO. <u>099-1003</u>	- I -	1	C	Ö	Surface Water Elev. N/A	_ ft	E	Ľ	C	Ö
Station	- -	1	S	Ĭ	Stream Bed Elev. N/A	_ IL	P	ō	S	i
BORING NO. RWB-08	Т	W		S	Groundwater Elev.:		Т	W		s
Station278+69.27	- н	S	Qu	Т	First Encounter None	ft	Н	S	Qu	Т
Offset 100.57ft LT	-				Upon Completion N/A					
Ground Surface Elev. 594.60	ft (ft) (/6")	(tsf)	(%)	After N/A Hrs. N/A	ft	(ft)	(/6")	(tsf)	(%)
6 inches of Topsoil 50	94.10				Stiff					
Brown and Gray, Moist	, , , , , , , , , , , , , , , , , , , 				Gray, Moist	573.60	_			
FILL: SILTY CLAY, trace sand		3			SILTY CLAY, trace sand and			13		
gravel and organics	-	6	1.9	25	gravel, (CL/ML) (continued)	573.00	. —	50/1"		16
		7	В		LIMESTONE, highly weathered Auger refusal at 21.6 feet			i		
	-				End of Boring	J	_	1		
50	91.10				Lind of Borning					
Very Stiff to Hard		2					_	1		
Brown and gray, Moist		6	3.3	24						
SILTY CLAY, trace sand and gravel (CL/ML)	-	.5 6	В				-25]		
graver (CL/IVIL)								1		
	-							1		
		4]		
	_	8	5.8	20						
		10	В							
		2								
	_	7	3.8	21						
	1	0 9	В				-30			
	_									
	33.60									
Hard Gray, Moist	_	6		L						
SILTY CLAY, trace sand and		9	6.3	19						
gravel (CH)	_	12	В				_			
	<u>31.10 </u>	⊣ _								
Hard Gray, Moist		5 9	- 0	04						
SILTY CLAY, trace sand and	-	_ 11	5.8	21			_	-		
gravel (CL/ML)	1	5 11	В				-35			
	-	_								
Medium Dense 57	78.60	8								
Gray, Wet	=	11		18			_			
SILTY LOAM, trace sand (ML)		15		10						
` ,	-	+ 10		-			_	-		
		\dashv						1		
57	76.10	5					_	-		
		4	1.7	26						
		8	В				-40			



Page $\underline{1}$ of $\underline{1}$

Date 11/6/19

ROUTE	I-55 and IL 59	DE	SCR	IPTIO	N		Retaining Wall 5		L0	OGG	ED BY	<u> </u>	I P
CECTION	0040 07E D			0047	FION	LEE O	Doff aboutdon CEC TV	ND DNC					
SECTION _	2018-075-R		L	LUCA	IION _	I-55 SI	B off shoulder, <mark>SEC. , TV</mark> Ide,Longitude	<u>vP., RNG.,</u>					
COUNTY	WILL DI	RII I INC	з ме	тног)	Latite	HSA	HAMMER	TYPF		ΔΙ	ITO	
	J						11071				, , ,	,,,,	
STRUCT N	O . <u>099-1003</u>		D	В	U	М	Surface Water Elev	NI/A	ft	D	В	U	М
Station	O . <u>099-1003</u>		Е	L	С	0	Stream Bed Elev.	N/A	- It ft	E	L	С	0
			Р	0	S	ı		14// (- ''	Р	0	S	ı
BORING NO	D. RWB-09		Т	W		S	Groundwater Elev.:			T	W		S
Station	279+42.48		Н	S	Qu	T	First Encounter _	None	ft	Н	S	Qu	T
Offset	279+42.48 101.79ft LT						Upon Completion _	N/A	_ ft				
Ground St	urface Elev. 594.40	ft	(ft)	(/6")	(tsf)	(%)	After <u>N/A</u> Hrs	N/A	_ ft	(ft)	(/6")	(tsf)	(%)
6 inches of	Topsoil	593.90	•				Very Stiff to Hard		573.90				
Brown and i	Siack, ivioisi						Gray, Moist						
	CLAY, trace sand and			3			SILTY CLAY, trace sar and Limestone fragme	nd, gravei,					
organics				5	1.9	25	(continued)	into (OL/IVIL)					
				5	В		Auger refusal at 20.5 fe	eet					
							End of Boring	'					
		590.90											
Very Stiff to	Hard			2									
Diowii and g	gray, Moist /, trace sand and			4	2.7	19							
gravel (CL/N			5	5	В					25			
9.2.13. (32,1.	,		_							_			
				_									
			_	5						_			
				8	5.4	20							
			_	11	В					_			
			_							_			
				2	0.5	0.4					_		
				6 8	6.5	21							
			10	0	В					30			
			_							_			
Hord		583.40											
Hard Gray, Moist				8	G E	17					 		
	/, trace sand and			12	6.5 B	17							
gravel (CL/N			_	12	В					_			
				4						_			
				8	5.4	20							
				10	В	20							
			<u>-15</u>							35	<u> </u>		
		578.40	_							_			
Very Stiff		376.40		8									
Gray, Very I	Moist		_	8	4.5	25				_	1		
SILTY CLAY	/ LOAM, trace sand			8	P								
(ML/CL)			_							_	†		
		575.90		1							1		
		2. 3.00	_	4						_	1		
				5	2.9	13					1		
			-20	21	В					-40	1		



Page $\underline{1}$ of $\underline{1}$

Date <u>2/27/20</u>

ROUTE	I-55 and IL 59	DE	SCR	IPTIOI	N		Retaining Wall 5		LC	OGG	ED BY	<u> </u>	AB
SECTION	2019 075 D			004	TION .	I 55 CI	3 off shoulder, SEC. , T\	MD DNG					
SECTION _	2010-013-N		_ '	LOCA	ION _	Latitu	ide , Longitude	WP., KNG.,					
COUNTY	WILL DI	RILLING	З МЕ	THOD)		HSA	HAMMER	TYPE		Αl	JTO	
					-		I	_					
STRUCT. NO	099-1003		D	В	U	M	Surface Water Elev	N/A	ft	D	В	U	М
Station			Е	L	С	0	Stream Bed Elev.	N/A	ft	Е	L	С	0
			P	0	S	I				P	0	S	Ī
BORING NO	RWB-15		T	W		S	Groundwater Elev.:		_	T	W		S
Station	273+19.78 85.26ft LT		Н	S	Qu	Т	First Encounter _	582.9	_ ft <u>▼</u>	Н	S	Qu	Т
Offset	85.26ft L1	— <u>"</u>	(ft)	(/6")	(tsf)	(%)	Upon Completion _	N/A	_ ft	(ft)	(/6")	(tsf)	(%)
	face Elev. 593.90			(10)	(131)	(70)	After N/A Hrs.	IN/A	_ π	(11)	(10)	(131)	(70)
6 inches of 10	opsoil	593.40	_				A	54					
Brown and G Moist	ray, Moist to Very						Auger refusal at 21.0 f	feet	572.90				
	CLAY, trace sand		_	2	0.0	20	End of Boring			_			
	,			5	0.8 B	33							
			_		В					_			
			_	2						_			
				3	4.0	23							
			<u> </u>	6	В								
			5							-25			
		587.90	_							_			
Soft to Very S		007.00		4									
Gray, Moist to				10	2.9	20							
SILTY CLAY,	trace gravel (CL/ML))		12	В								
				5									
				8	3.8	16							
			10	10	В					-30			
			_							_			
			▼	,									
			_	3	1.7	23				_			
				6	1.7 B	23							
			_		В					_			
			_	3						_			
				4	0.4	23							
			-15	5	В					-35			
			_							_			
				3									
				6	1.3	33							
				18	В								
		575.40	_							_			
Dense Cray Majet				13									
Gray, Moist	, with gravel (ML)		_	14		14				_			
OIL I LOAW	, with graver (IVIL)		-20	26		1	I			-40			



Page $\underline{1}$ of $\underline{1}$

Date <u>2/27/20</u>

ROUTE	I-55 and IL 59	DE	SCR	IPTIOI	N		Retaining Wall 5		L(OGG	ED BY		λB
SECTION	2018-075-R		L	_OCA1	ΓΙΟΝ	I-55 SI	B off shoulder, SEC. , TV	VP., RNG.,					
						Latitu	de , Longitude						
COUNTY	WILL DE	RILLING	G ME	THOD			HSA	HAMMER	TYPE		ΑL	JTO	
OTPLICT NO	000 4000		D	В	U	М	Ofa a a Water Flore	NI/A	£4	D	В	U	М
	099-1003		E	L	C	Ö	Surface Water Elev.	N/A	_ π	E	L	C	0
Station			P	ō	s	ĭ	Stream Bed Elev.	N/A	_ π	P	ō	S	ĭ
DODING NO	DMD 40		Ť	w	•	s	O			Т	w		s
BURING NO.	RWB-16		Н	s	Qu	T	Groundwater Elev.:	574.4		H	S	Qu	T
Station	273+70.74		••	•	٩	•	First Encounter _			٠.		Qu	
Offset	90.34ft LT	— <u>,</u>	/ft\	(/6")	(tsf)	(%)	Upon Completion _	N/A	_ π	(ft)	(/6")	(tsf)	(%)
	face Elev. 595.40	π	(11)	(,,,	(131)	(70)	After N/A Hrs.	IN/A	_ π	(11)	(10)	(131)	(70)
6 inches of To	psoil	594.90											
	and Black, Very]					574.40	V			
Moist	I AV trace graval			3			Dense				15		
and organics	LAY, trace gravel			4	2.3	27	Gray, Moist				21		10
and organics				5	В		GRÅVEL, trace silt				17		
							Auger refusal at 23.0 fe	eet	572.40				
				1			End of Boring						
			_	2						_			
				3	1.9	27							
			-5	4	В					-25			
										-20			
		589.40	_	1						_			
Hard		505.40		5									
Brown, Moist			_	8	4.8	20				_			
SILTY CLAY,	trace gravel (CL/ML))		11	В								
			_							_			
			_	3						_			
				8	4.0	23							
			_	10	B	23				_			
			10		Ь					30			
			_	-						_			
Very Stiff to H	ord	584.40		6									
Gray, Moist to			_	7	4.0	22							
SILTY CLAY.	trace gravel (CL/ML))		9	4.8	23							
- ,	J (,		_	9	В					_			
0-1-1440	0 1 4 4 0 5 +												
Copples at 12	.0 and 14.0 feet		_							_			
				3									
			_	5	4.6	22							
			<u>-15</u>	8	В					-35			
			_										
				6									
				9	2.1	28							
				6	В								
				3									
				5	2.3	19							
			-20	25	В					-40			



Page $\underline{1}$ of $\underline{1}$

Date <u>2/27/20</u>

ROUTE	I-55 and IL 59	DE	SCR	IPTIOI	N		Retaining Wall 5		LC	GG	ED BY	<u> </u>	λB
SECTION	2019 075 D			004	TION .	I 55 CI	B off shoulder, SEC. , TWP. ,	DNG					
SECTION _	2010-073-IX		_	LOCA	110IN _	Latitu	ide , Longitude	KNG.,					
COUNTY	WILL DI	RII I INC	з ме	THOD)		HSA HA	MMFR 1	TYPF		Αl	ITO	
											, , ,		
STRUCT NO	D. 099-1003		D	В	U	М	Surface Water Floy	NI/A	£4	D	В	U	М
	J. 099-1003		Е	L	С	0	Surface Water Elev Stream Bed Elev	N/A_	ft	Е	L	С	0
Otation			Р	0	s	ı	Otream Bed Liev.		"	Р	0	S	ı
BORING NO	RWR-17		Т	w		S	Groundwater Elev.:			Т	W		S
Station	RWB-17 274+43.87 89.26ft LT		Н	S	Qu	T	First Encounter	576.8	ft ▼	Н	S	Qu	Т
Offset	89.26ft LT						Upon Completion	N/A	ft				
Ground Su	rface Elev. 595.30	ft	(ft)	(/6")	(tsf)	(%)	After N/A Hrs.	N/A	ft	(ft)	(/6")	(tsf)	(%)
	opsoil	594.80					Very Stiff						
	n, and Gray, Moist	394.60	_	-			Chair Maint to Maint			_			
	CLAY, trace sand			3			SILTY CLAY, trace gravel (CL/ML)					
	,		_	4	2.3	23		ŗ	5/3.80	_			
				5	2.5 B	23	Auger refusal at 21.5 feet		-				
			_		Ь		End of Boring			_			
				3									
				4	2.9	21							
			_	5	B B	21				_			
			5						-	- <u>25</u>			
			_							_			
				4					-				
			_	7	6.0	20				_			
				9	В				-				
			_							_			
		586.80											
Hard		500.00		5						_			
Brown, Moist				6	7.1	20							
SILTY CLAY	, trace gravel (CL/ML))	-10	9	В					-30			
										-00			
Cobbles at 1	1.0 feet			6					-				
				11	NR								
				15					-				
			_										
		581.80											
Very Stiff				4									
Gray, Moist t	o Very Moist			7	5.0	20							
SILTY CLAY	, tracé gravel (CL/ML))	-15	11	В					-35			
				5					•				
				9	3.5	25							
				8	В				•				
			_							_			
			lacksquare										
				6									
				13	1.3	19							
			-20	20	В					-40			



Page $\underline{1}$ of $\underline{1}$

Date 4/2/20

ROUTE	I-55 and IL 59	DE	SCR	IPTIOI	N		Retaining Wall 5	L0	OGG	ED BY	<u> </u>	EK
SECTION	2018-075-P			OCAT	TION .	L55 SI	3 off shoulder, SEC., TWP., RNG.					
SECTION	2010-013-IX		_ '	LOCA	IION _	Latitu	ide,Longitude	,				
COUNTY	WILL D	RILLING	G ME	THOD			HSA HAMME	R TYPE		Αl	JTO	
STRUCT. NO	. 099-1003		D	В	U	M	Surface Water Elev. N/A	ft	D	В	U	M
Station			E P	L	C S	0	Stream Bed ElevN/A	ft	E	L	C S	0
	DIA/D 00		T	O W	3	l S	0		T	O W	3	S
Station	RWB-30 272+58.54		Н	S	Qu	T	Groundwater Elev.: First Encounter 572.3	# ▼	H	S	Qu	T
Offset	84.79ft LT						Upon Completion N/A	ff T				
Ground Sur	face Elev. 593.33	ft	(ft)	(/6")	(tsf)	(%)	After N/A Hrs. N/A	ft	(ft)	(/6")	(tsf)	(%)
Black and Gra												
	ND GRAVEL		_					572.33	_			
				4			LIMESTONE, highly weathered	0.2.00	<u> </u>	50/6"		
		591.33		2	2.5	22						7
Very Stiff		,		4	Р							
Brown, Moist SILTY CLAY								570.33				
SILTI CLAT	(CL/IVIL)						End of Boring					
				3	0.5	00						
			_	ა 5	3.5 P	22			_			
			5		Г				<u>-25</u>			
			_						_			
				3								
			_	5	2.5	21			_			
				7	Р							
				3								
			_	6 9	3.0	19						
			<u>-10</u>	9	Р				-30			
		500.00	_						_			
Very Stiff		582.33		3								
Gray, Moist			_	3	3.0	19			_			
SILTY CLAY	(CL/ML)			5	Р							
			_						_			
				3								
			_	6	3.5	23						
			15	9	Р				<u>-35</u>			
			_						_			
Medium Dens	20	577.33		10								
Gray, Moist	o C			10		18						
SILT (ML)				9		10						
			_	-					_			
		574.83										
Very Stiff		5. 1.00	_	3					_			
Gray, Moist				5	2.5	15						
SIL I Y CLAY	LOAM (CL/ML)		-20	14	Р				-40			

APPENDIX D Laboratory Test Results



Tel: 630.994.2600 • Fax: 312.733.5612

Table D1a–Retaining Wall #5 Test Results – Atterberg Limits


Boring ID	Sample Depth (ft)	Liquid Limit (%)	Plastic Limit (%)	Plasticity Index (%)	Soil Classification
RWB-04	3.5-5	66.2	23.2	43.0	СН
RWB-07	11-12.5	43.4	21.0	22.4	CL
RWB-08	11-12.5	53.8	22.6	31.2	СН

Table D1b- Retaining Wall #5 Test Results - Organic Content

Boring ID	Sample Depth (ft)	Organic Content (%)	Soil Classification
RWB-04	3.5-5	5.8	СН

Table D1c- Retaining Wall #5 Test Results - Unit Weight

Boring ID	Sample Depth (ft)	Dry Unit Weight (pcf)	Wet Unit Weight (pcf)	Soil Classification	
RWB-07	11-12.5	104.7	129.0	CL	




APPENDIX E SOIL PARAMETERS TABLE

Soil Parameters Table


Elevation		In situ Unit Weight γ (pcf)	Undrained		Drained	
Range (feet)	Soil Description		Cohesion c (psf)	Friction Angle φ (°)	Cohesion c (psf)	Friction Angle φ (°)
	New Engineered Clay Fill	120	1,000	0	50	25
	New Engineered Granular Fill	125	0	30	0	30
595-591	Brown and Gray FILL Silty Clay	133	2,400	0	240	25
591-583	Brown and Gray Very Stiff to Hard Silty Clay	139	4,100	0	410	28
583-579	Gray Very Stiff to Hard Silty Clay	137	3,400	0	340	28
579-574	Gray Medium Dense to Dense Loam or Gravel	129	0	36	0	36


APPENDIX F SLOPE STABILTY ANALYSIS




Wall 5 short term 272+56

05/27/2020







Wall 5 short term 277+50

06/01/2020

