

SCHEDULE OF QUANTITIES

X0300136 BRIDGE APPROACH SHOULDER REMOVAL

SQ YD	LOCATION	REMARK'S
12	RT. STA. 769 + 5	TO 769 + 20
9.5	LT. STA. 769 + 8	TO 769 + 20
9.5	LT. STA. 770 + 76	TO 770 + 88
12	RT. STA. 770 + 76	TO 770 + 92
43	TOTAL	

REMARK'S
Silver Creek SE
Silver Creek SW
Silver Creek NW
Silver Creek NE

XZ127900 RETAINING WALL REMOVAL

EQOT	LOCATION	REMARK'S
72	LT. STA. 704 + 82	TO 705 + 39
72		

X0325519 DRAIN FOR AGGREGATE BASE COURSE

SQ YD	LOCATION	REMARK'S
0.90	RT. STA. 747 + 89	
0.88	RT. STA. 749 + 89	
0.93	RT. STA. 754 + 39	
0.90	RT. STA. 757 + 0	
0.90	RT. STA. 760 + 0	
0.90	RT. STA. 763 + 0	
0.90	RT. STA. 766 + 0	
0.90	RT. STA. 767 + 50	
1.30	RT. STA. 769 + 0	
0.73	LT. STA. 802 + 89	
0.90	LT. STA. 805 + 89	
0.90	LT. STA. 806 + 89	
0.90	LT. STA. 810 + 39	
0.90	LT. STA. 813 + 0	
0.90	RT. STA. 813 + 0	
0.90	LT. STA. 816 + 0	
0.90	RT. STA. 816 + 0	
0.90	LT. STA. 817 + 39	
0.90	RT. STA. 817 + 0	
1.50	RT. STA. 909 + 39	
0.77	RT. STA. 912 + 58	
0.67	LT. STA. 920 + 89	
0.90	RT. STA. 920 + 89	
0.90	LT. STA. 923 + 89	
0.90	RT. STA. 923 + 89	
0.90	LT. STA. 926 + 89	
0.90	RT. STA. 926 + 89	
0.90	LT. STA. 952 + 89	
0.90	RT. STA. 952 + 89	
0.90	LT. STA. 955 + 39	
0.90	RT. STA. 955 + 39	
0.90	LT. STA. 958 + 39	
0.90	RT. STA. 958 + 39	
0.90	LT. STA. 966 + 39	
0.90	RT. STA. 966 + 39	
0.90	LT. STA. 969 + 39	
0.90	RT. STA. 969 + 39	
0.90	LT. STA. 971 + 89	
0.90	RT. STA. 971 + 0	
0.90	LT. STA. 1023 + 39	
0.90	RT. STA. 1023 + 39	
0.87	LT. STA. 1025 + 89	
0.90	RT. STA. 1025 + 89	
39.14	TOTAL	

X2110100 TOPSOIL FURNISH AND PLACE, SPECIAL

CU YD	LOCATION	REMARK'S
608.5	RT. STA. 683 + 50	TO 712 + 50
370.5	RT. STA. 989 + 0	TO 998 + 50
979.1	TOTAL	

REMARK'S
ARTICULATED BLOCK REVETMENT MAT AREAS (Estimated Qty.)
ARTICULATED BLOCK REVETMENT MAT AREAS (Estimated Qty.)

X6063600 COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24

EQOT	LOCATION	REMARK'S
3549	LT. STA. 680 + 51	TO 716 + 0
2475	LT. STA. 726 + 75	TO 751 + 50
1224	LT. STA. 862 + 35	TO 874 + 59
175	LT. STA. 942 + 75	TO 944 + 50
300	LT. STA. 967 + 50	TO 970 + 50
600	LT. STA. 1030 + 50	TO 1036 + 50
8322	TOTAL	

X6064201 COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.06

EQOT	LOCATION	REMARK'S
69	LT. STA. 724 + 2	
43	LT. STA. 1060 + 27	
91	LT. STA. 1060 + 97	
203	TOTAL	

REMARK'S
Mud Creek Island
IL 72 Island
IL 72 Island

FILE NAME =	USER NAME = cushmanbw	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
en:\pwwork\pwidot\CUSHMANBW\dms31213\106608crr.dgn	PLOT SCALE = 50.0000' / IN.	DRAWN -	REVISED -			742	37R-4	OGLE	867	60	
PLOT DATE = Wed Mar 31 08:36:03 2010	DATE -	CHECKED -	REVISED -			CONTRACT NO. 64E17		ILLINOIS FED. AID PROJECT			
		DATE -	REVISED -			SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.