

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	99 (1&2) I-12	WILL	147	14
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
		SCHEDULE-02 OF 03		

66502300 WOVEN WIRE FENCE REMOVAL

LOCATION	FROM STATION	OFFSET	TO STATION	OFFSET	FOOT
WALL 7	610+00.00	RT	630+00.00	RT	2,000
FRONTAGE ROAD-WALL 8	652+80.00	RT	682+90.00	RT	3,010
FRONTAGE	685+50.00	RT	686+43.00	RT	93
	686+87.00	RT	709+65.00	RT	2,278
FRONTAGE ROAD-WALL 9B	711+00.00	RT	728+00.00	RT	1,700
FRONTAGE ROAD-WALL 9C	726+80.00	RT	737+35.00	RT	1,055
TOTAL					10,136

XX007763 TEMPORARY FENCE (SPECIAL)

LOCATION	FROM STATION	TO STATION	FOOT
WALL 8	652+00.00	684+00.00	3,200
WALL 9A	684+50.00	692+50.00	800
WALL 9C	726+50.00	738+50.00	1,200
TOTAL:			5,200

Z0018500 DRAINAGE STRUCTURES TO BE CLEANED

LOCATION	STATION	OFFSET	EACH
I-55	668+28.00	0' RT	1
	668+28.00	105' RT	1
	685+32.00	69' RT	1
	686+66.00	79' RT	1
	693+77.00	0' RT	1
	693+77.00	108' RT	1
	701+53.00	0' RT	1
	701+53.00	106' RT	1
	709+56.00	80' RT	1
	711+09.00	80' RT	1
721+56.00	0' RT	1	
721+56.00	102' RT	1	
TOTAL:			12

78000600 THERMOPLASTIC PAVEMENT MARKING - LINE 12"

LOCATION	FROM STATION	WIDTH	OFFSET	TO STATION	WIDTH	OFFSET	FOOT
I-55 WALL 7	610+25.64	5.5	RT	620+50.00	5.5	RT	16
	620+50.00	5.5	RT	622+87.17	12.0	RT	6
	622+87.17	12.0	RT	624+88.03	7.5	RT	6
	624+88.03	7.5	RT	629+51.00	7.5	RT	10
I-55 WALL 9B	688+60.00	7.5	RT	708+20.62	7.5	RT	42
	708+20.62	7.5	RT	709+38.23	1.4	RT	1
	711+31.48	1.4	RT	712+49.09	7.5	RT	1
	712+49.09	7.5	RT	730+05.00	7.5	RT	37
TOTAL:							119

CONCRETE BARRIER BASE, SPECIAL

LOCATION	FROM STATION	OFFSET	TO STATION	OFFSET	FOOT
I-55 WALL 7	610+25.64	67.5' RT	620+50.00	67.5' RT	1,042
	620+50.00	67.5' RT	624+88.03	61.5' RT	445
	624+88.03	61.5' RT	629+51.00	61.5' RT	463
I-55 WALL 9B	689+00.00	61.5' RT	708+20.62	61.5' RT	1,921
	708+20.62	61.5' RT	709+38.23	53.67' RT	118
	709+38.23	53.67' RT	709+63.23	53.67' RT	25
	711+06.48	53.67' RT	711+31.48	53.67' RT	25
	711+31.48	53.67' RT	712+49.09	61.50' RT	118
	712+49.09	61.5' RT	730+05.00	61.5' RT	1,756
	TOTAL:				

E20200G1 VINE-PARTHENOCISSUS QUINQUEFOLIA (VIRGINIA CREEPER), 1-GALLON POT

LOCATION	FROM STATION	OFFSET	TO STATION	OFFSET	EACH
I-55 WALL 8	654+00.00	RT	682+90.00	RT	1,928
WALL 9A	685+50.00	RT	690+50.00	RT	314
WALL 9C	728+00.00	RT	767+00.00	RT	2,580
TOTAL:					4,822

X0323973 SEDIMENT CONTROL, SILT FENCE

LOCATION	FROM STATION	OFFSET	TO STATION	OFFSET	FOOT
WALL 7	621+79.00	78' RT	629+26.00	72' RT	1917
WALL 8	654+00.00	85' RT	682+00.00	71' RT	2754
WALL 9A	685+30.00	99' RT	690+50.00	84' RT	533
WALL 9B	689+00.00	77' RT	702+00.00	81' RT	1365
WALL 9B	720+77.00	75' RT	727+00.00	79' RT	620
WALL 9C	728+00.00	82' RT	737+32	75' RT	933
TOTAL:					8,122

X6370912 CONCRETE BARRIER, SINGLE FACE, 32 INCH HEIGHT, SPECIAL

LOCATION	FROM STATION	OFFSET	TO STATION	OFFSET	FOOT
I-55 WALL 7	610+25.64	67.5' RT	620+50.00	67.5' RT	1,042
	620+50.00	67.5' RT	624+88.03	61.5' RT	445
	624+88.03	61.5' RT	628+76.00	61.5' RT	388
	628+76.00	61.5' RT	629+51.00	56.8' RT	75
	629+51.00	56.8' RT	629+63.84	56.8' RT	13
I-55 WALL 9B	689+00.00	61.5' RT	708+20.62	61.5' RT	1,921
	708+20.62	61.5' RT	709+38.23	53.67' RT	118
	709+38.23	53.67' RT	709+63.23	53.67' RT	25
	711+06.48	53.67' RT	711+31.48	53.67' RT	25
	711+31.48	53.67' RT	712+49.09	61.50' RT	118
	712+49.09	61.5' RT	730+05.74	61.5' RT	1,757
	TOTAL:				

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
FAI ROUTE 55  
US 30 (PLAINFIELD ROAD) TO WEBER ROAD

SCHEDULE OF QUANTITIES

SCALE:  
DATE: 6-12-09

DRAWN BY: MMS  
CHECKED BY: DM

