

	1	I. D. O.	. T.								
TRAFFIC SIGNAL INSTALLATION											
	ELECTRICAL SERVICE REQUIREMENTS										
TYPE	NO. LAMPS	WATTAGE		% OPERATIONS	TOTAL						
		INCAND.	LED		WATTAGE						
SIGNAL (RED)	12	1 35	1 7	0.50	102						
(YELLOW)	12	1 35	25	0.25	75						
( GREEN)	12	1 35	15	0.25	45						
ARROW	8	1 35	12	0.10	10						
PED. SIGNAL	4	90	25	1.00	100						
CONTROLLER	1	100	100	1.00	100						
ILLUM. SIGN		252	25	0.05							
VIDEO SYSTEM		150	-	1.00							
FLASHER LED											
				TOTAL =	432						

ENERGY COSTS-

BILLED TO: IDOT DISTRICT 1

201 WEST CENTER COURT SCHAUMBURG, IL 60196-1096

ENERGY SUPPLY -

CONTACT JOE STACHO

630-424-5704 COMMONWEALTH EDISON

**→**②→ Z — NO. 6 GREEN NO. 6-GREEN INTERCONNECT TO MONTROSE AVE. (EAST)/ AGATITE AVE. -TRACER CABLE WILSON **@**-2 TRACER CABLE -INTERCONNECT TO LAWRENCE AVE. (WEST) IL RTE. 43 (HARLEM AVE.) EXISTING INTERSECTION AND SAMPLING (SYSTEM) DETECTORS <del>-</del>5-E > 0 GREEN CARDINAL LIQUORS **ENTRANCE** 

## **CABLE PLAN**

## SCHEDULE OF QUANTITIES

QUANTITY <u>UNIT</u> MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION EACH PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER EACH EACH PEDESTRIAN PUSH-BUTTON MODIFY EXISTING CONTROLLER CABINET
REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT
UNINTERRUPTABLE POWER SUPPLY, SPECIAL EACH FACH

UPS SHALL BE INSTALLED ON LEFT SIDE OF CONTROLLER CABINET DUE TO PHYSICAL CONSTRAINT, OR AS DIRECTED BY THE ENGINEER

## REMOVAL OF EXISTING TRAFFIC SIGNAL EQUIPMENT

THE FOLLOWING ITEMS SHALL BE REMOVED BY THE CONTRACTOR AND SHALL BE DISPOSED OF BY THEM OUTSIDE THE RIGHT-OF-WAY AT THEIR EXPENSE. THE SALVAGE VALUE OF THE REMOVED EQUIPMENT SHALL BE REFLECTED IN THE CONTRACT BID PRICE.

PEDESTRIAN SIGNAL HEAD 4 EACH PEDESTRIAN PUSH-BUTTON

> TS #2430 HARWOOD HEIGHTS

USER NAME = _USERNAME_	DESIGNED -	DW	REVISED -		IL ROUTE 43 (HARLEM AVENUE) AT WILSON AVENUE SCHEDULE OF QUANTITIES, CABLE PLAN, AND PHASE DESIGNATION DIAGRAM						F.A.	SECTION	COUNTY	TOTAL	SHEET
	DRAWN -	CC	REVISED -	STATE OF ILLINOIS							11122	2014-019TS	СООК	90	50
PLOT SCALE = 20.000 ' / in.	CHECKED -	КММ	REVISED -	DEPARTMENT OF TRANSPORTATION									CONTRACT NO. 60Y05		OY05
PLOT DATE = 5/13/2014	DATE -		REVISED -		SCALE: N.T.S.	SHEET NO.	OF	SHEETS	STA.	TO STA.		ILLINOIS	1		