



Illinois Department of Transportation

Division of Aeronautics

1 Langhorne Bond Drive / Capital Airport / Springfield, Illinois / 62707-8415

July 28, 2014

SUBJECT: DeKalb Taylor Municipal Airport
DeKalb, Illinois
DeKalb County
Illinois Project Number: DKB-4069
SBG Project Number: 3-17-SBGP-XX
Contract No. DK056
Item No. 6A, August 1st, 2014 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

Reason for Addendum:

Revisions to Construction Plans and Special Provisions to allow Corrugated Polypropylene (CPP) Pipe as an alternate material for detention basin outlet pipe.

To All Plan Holders:

Plan Revisions:

Plan Sheet 1 of 16, **Cover Sheet**

- Noted Plan Sheets revised by Addendum and Addendum Date.

Plan Sheet 6 of 16, **Typical Sections & Details**

- Added alternate Pipe Trench detail for when using CPP pipe. Also revised compaction notes for original Pipe Trench detail.

Special Provisions Revisions:

Page 14, ITEM 701 – PIPE FOR STORM SEWERS AND CULVERTS

- Delete Page 14 and replace with Page 14A

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Questions on this addendum may be directed to Kyle Schweizer of Hanson Professional Services at 217-747-9219.

DIVISION IV – DRAINAGE

ITEM 701 PIPE FOR STORM SEWERS AND CULVERTS

Item 701 Pipe for Storm Sewers and Culverts is modified as outlined below.

MATERIALS

701-2.1 Add the following to this section:

“Corrugated Polypropylene (CPP) Double Wall Pipe shall be in accordance with ASTM F2736. It may be substituted at the Contractor’s discretion in place of 24-in RCP, Class IV. It shall be of the same nominal inside diameter, and measured and paid for under the same pay item as the 24-in RCP.”

CONSTRUCTION METHODS

701-3.3 Add the following to this section:

“C. Corrugated Polypropylene (CPP) Double Wall Pipe. CPP pipe shall be installed per the Construction Plans and the manufacturer’s recommendations. The more conservative of the two shall govern in the event of discrepancies. Connections to concrete end sections or manholes shall be sealed with concrete or as per the manufacturer’s recommendations.”

Also,

701-3.9 Add the following to this section:

“After a minimum period of 30 days from installation of the CPP pipe, the Contractor shall employ a qualified company or individual to perform a deflection evaluation on a minimum of 10% of the CPP pipe that was installed using visual, video, mandrel, or other accepted methods of inspection. Results of the evaluation shall be provided to the Resident Engineer. Areas of more than 7.5% deflection shall be uncovered and corrected, or replaced at the Contractor’s expense.”

BASIS OF PAYMENT

701-5.1 Add the following to this section:

“Payment will be made under:

Item AR701512 12” RCP, Class IV - per linear foot
Item AR701518 18” RCP, Class IV - per linear foot
Item AR701524 24” RCP, Class IV - per linear foot
Item AR701536 36” RCP, Class IV - per linear foot
Item AR701900 Remove Pipe - per linear foot
Item AR800543 Field Tile Repair – per each”

END OF ITEM 701