

Structural Geotechnical Report

Proposed Retaining Wall #5 along Center Street

IDOT PTB 198-003

FAI-80 (I-80) over Des Plaines River

Will County, Illinois

Prepared for



Illinois Department of Transportation

Contract Number: D-91-204-19

Project Design Engineer Team

WSP USA

Geotechnical Consultant



October 14, 2022
Updated May 3, 2024



735 Remington Road
Schaumburg, IL 60173
Tel: 630.994.2600
www.gsg-consultants.com

May 3, 2024

David Skaleski, P.E.
Project Manager
WSP USA
30 N. LaSalle Street, Suite 4200
Chicago, Illinois 60602

Structural Geotechnical Report
Proposed Retaining Walls #5 along Center Street
Will County, IL
PTB 198-003

Dear Mr. Skaleski:

Attached is a copy of the Structural Geotechnical Report for the above-referenced project. The report provides a description of the site investigation, site conditions, and foundation and construction recommendations. The site investigation for the proposed retaining wall #5 and embankment included advancing eight (8) soil borings to depths of 3 to 24 feet and four (4) rock cores.

Should you have any questions or require additional information, please call us at 630-994-2600.

Sincerely,

A handwritten signature in black ink that reads "Matthew J Heron".

Matthew J Heron, P.E.
Project Engineer

A handwritten signature in blue ink that reads "Ala E Sassila".

Ala E Sassila, Ph.D., P.E.
Principal

TABLE OF CONTENTS

| | | |
|------------|-------------------------------------------------------|-----------|
| 1.0 | INTRODUCTION..... | 1 |
| 1.1 | Existing Retaining Wall Information..... | 2 |
| 1.2 | Proposed Structure Information | 3 |
| 2.0 | SITE SUBSURFACE CONDITIONS..... | 5 |
| 2.1 | Subsurface Exploration and Laboratory Testing | 5 |
| 2.2 | Laboratory Testing Program..... | 6 |
| 2.3 | Subsurface Soil Conditions..... | 6 |
| 2.4 | Subsurface Bedrock Conditions..... | 7 |
| 2.5 | Groundwater Conditions..... | 8 |
| 3.0 | GEOTECHNICAL ANALYSES | 9 |
| 3.1 | Embankment Settlement | 9 |
| 3.2 | Seismic Parameters..... | 9 |
| 4.0 | GEOTECHNICAL WALL DESIGN RECOMMENDATIONS | 11 |
| 4.1 | Retaining Wall Type Recommendations..... | 11 |
| 4.1.1 | CIP Concrete Cantilever Walls | 11 |
| 4.1.2 | Mechanically Stabilized Earth Walls | 11 |
| 4.1.3 | Prefabricated Modular Gravity Walls | 12 |
| 4.1.4 | Recommended Wall Type..... | 12 |
| 4.2 | Retaining Wall Design Recommendations..... | 13 |
| 4.2.1 | Lateral Earth Pressures and Loading | 13 |
| 4.2.2 | Bearing Resistance – MSE Wall..... | 15 |
| 4.2.3 | Subgrade Undercut Areas..... | 16 |
| 4.3 | Sliding and Overturning Stability | 17 |
| 4.4 | Wall and Embankment Settlement | 17 |
| 4.5 | Global Slope Stability | 18 |
| 4.5.1 | Global Slope Stability Results | 18 |
| 4.6 | Drainage Recommendations..... | 19 |
| 5.0 | CONSTRUCTION CONSIDERATIONS | 20 |
| 5.1 | Site Preparation..... | 20 |
| 5.2 | Existing Utilities | 20 |
| 5.3 | Site Excavation..... | 21 |
| 5.4 | Borrow Material and Compaction Requirements | 21 |
| 5.5 | Groundwater Management | 22 |
| 6.0 | LIMITATIONS..... | 23 |

Exhibits

| | |
|-----------|--------------------------------------------------------------|
| Exhibit 1 | Project Location Map |
| Exhibit 2 | Existing Site Conditions at Proposed Retaining Wall Location |
| Exhibit 3 | Structural Fill Placement below MSE Wall |

Tables

| | |
|----------|---------------------------------------------------------------------------|
| Table 1 | Improvement Summary |
| Table 2 | Summary of Subsurface Exploration Borings |
| Table 3 | Rock Quality Designation |
| Table 4 | Rock Core Summary and Classification |
| Table 5 | Anticipated Embankment Settlement |
| Table 6 | Seismic Parameters |
| Table 7 | LRFD Load Factors for Retaining Wall Analyses |
| Table 8 | Lateral Soil Parameters |
| Table 9 | Equivalent Height of Soil for Vehicular Loading on RW Parallel to Traffic |
| Table 10 | Recommended Bearing Resistance for Retaining Wall |
| Table 11 | MSE Wall Description |
| Table 12 | Retaining Wall Global Slope Stability Analyses Results |

Appendices

| | |
|------------|--------------------------------------------------|
| Appendix A | General Plan and Elevation |
| Appendix B | Soil Boring Location Plan and Subsurface Profile |
| Appendix C | Soil Boring Logs |
| Appendix D | Soil Parameter Table |
| Appendix E | Laboratory Test Results |
| Appendix F | Slope Stability Analyses Exhibits |

Will County, Illinois

GSG Consultants, Inc. (GSG) completed a geotechnical investigation for the proposed Retaining Wall #5 and associated embankment in the City of Joliet in Will County, Illinois. The purpose of the investigation was to explore the subsurface conditions, to determine engineering properties of the subsurface soil, and develop design and construction recommendations for the proposed construction. **Exhibit 1** shows the general project location.



(Source: USGS Topographic Maps, [usgs.gov](https://www.usgs.gov))

1.1 Existing Retaining Wall Information

The overall proposed improvements at this location will include the realignment of Center Street and the entrance/exit ramps for I-80 as part of the relocation of the Center Street bridge. The realignment of Center Street Ramp will require a retaining wall for the construction of a new embankment based on the existing IDOT right of way. According to the proposed plan drawings provided, the proposed retaining wall will be in a “fill” section. **Exhibits 2a and 2b** show the existing conditions where the proposed retaining wall and embankment will be constructed.



Exhibit 2a – Existing Center Street Exit Ramp to EB I-80, Looking North




Exhibit 2b – Existing Retaining Wall Location, Looking from Top

1.2 Proposed Structure Information

Based on design information provided by WSP, a new bridge will be constructed to carry Center Street over I-80 and I-80 eastbound ramp. A new retaining wall and embankment will be constructed due to the realignment of Center Street and the entrance/exit ramps for I-80. Based on the design information and of the site topography, the proposed wall will preliminary be in a “fill” section. It is anticipated that the proposed wall will have a maximum exposed height of up to approximately 9.7 feet, for a maximum total height of 13.2 feet. The proposed retaining wall will be approximately 470 feet in length along Center Street between Sta. 17+25 and Sta. 22+00.17. It is anticipated that the proposed structure will consist of an MSE wall. A new embankment will be constructed along Center Street between Sta. 16+75 and Sta. 22+50. It is anticipated that the new embankment will have a maximum height of 11 feet.

Table 1 presents a summary of the proposed retaining wall and embankment.

Table 1 – Improvement Summary

| Structure Name | * Wall Stations | Approximate Length (ft) | Maximum Anticipated Exposed Wall Height (ft) | Maximum Anticipated Embankment Height (ft) |
|-------------------|------------------------|-------------------------|----------------------------------------------|--------------------------------------------|
| Retaining Wall #5 | Sta. 17+25 to 22+00.17 | 470 | 13.25 | n/a |
| Embankment | Sta. 16+75 to 22+50 | 575 | n/a | 11.0 |

* Based on proposed Ramp D Stationing

2.0 SITE SUBSURFACE CONDITIONS

This section describes the subsurface exploration program and laboratory testing program completed as part of this project. The proposed locations and depths of the soil borings were selected in accordance with IDOT requirements. The borings were completed in the field based on field conditions and accessibility.

2.1 Subsurface Exploration and Laboratory Testing

The site subsurface exploration for the proposed retaining wall structure was conducted between July 7 and August 18, 2022. The investigation included advancing eight (8) borings to depths of 3 to 24 feet. The locations of these soil borings were reviewed by WSP and adjusted in the field as necessary based on utilities and access. Elevations and as-drilled locations for the borings were gathered by GSG's field crew using GPS surveying equipment. The approximate as-drilled locations of the soil borings are shown on the Soil Boring Location Plan & Subsurface Profiles (**Appendix B**). **Table 2** presents a summary of the borings used for the analyses.

Table 2 – Summary of Subsurface Exploration Borings

| Boring ID | Station ** | Offset (ft) | Northing | Easting | Depth (ft) | Surface Elevation (ft) |
|-----------|------------|-------------|-------------|-------------|------------|------------------------|
| RWB-137 | 16+99.21 | 37.42 RT | 1764215.686 | 1048074.254 | 8.0 | 587.94 |
| RWB-138 | 17+74.54 | 39.27 RT | 1764273.362 | 1048120.181 | 24.0* | 588.87 |
| RWB-139 | 18+47.24 | 31.37 RT | 1764333.409 | 1048159.377 | 4.0 | 591.27 |
| RWB-140 | 19+9.85 | 26.96 RT | 1764382.389 | 1048196.982 | 16.0* | 592.48 |
| RWB-41 | 19+84.74 | 35.90 RT | 1764429.511 | 1048254.502 | 15.0* | 591.91 |
| RWB-42 | 21+0.15 | 43.21 RT | 1764506.539 | 1048340.744 | 3.0 | 589.35 |
| RWB-43 | 21+47.19 | 42.82 RT | 1764540.297 | 1048373.501 | 14.0* | 590.02 |
| RWB-144 | 22+13.28 | 48.10 RT | 1764583.635 | 1048423.677 | 4.5 | 589.37 |

* Depth includes Bedrock Core (10 feet)

** Based on proposed Ramp Stationing

Copies of the Soil Boring Logs are provided in **Appendix C**.

The soil borings were drilled using truck mounted Diedrich D-50 ATV (hammer efficiency 101.6%) drill rig, each equipped with 3¼-inch I.D. hollow stem augers and an automatic hammer. Soil sampling was performed according to AASHTO T 206, "Penetration Test and Split Barrel Sampling of Soils." Soil samples were obtained at 2.5-foot intervals to the planned boring termination depths or auger refusal on bedrock. Water level measurements were made in each boring when

evidence of free groundwater was detected on the drill rods or in the samples. The boreholes were also checked for free water immediately after auger removal, and before filling the open boreholes with soil cuttings.

GSG's field representative inspected, visually classified and logged the soil samples during the subsurface exploration activities. Representative soil samples were collected from each sample interval and were placed in jars and returned to the laboratory for further testing and evaluation.

2.2 Laboratory Testing Program

All samples were inspected in the laboratory to verify the field classifications. A laboratory testing program was undertaken to characterize and determine engineering properties of the subsurface soils encountered in the area. The following laboratory tests were performed on representative soil and rock samples:

- Moisture Content – ASTM D2216 / AASHTO T-265
- Unconfined Compression Strength on Rock – ASTM D2938

The laboratory tests were performed in accordance with test procedures outlined in the most current IDOT Geotechnical Manual, and per ASTM and AASHTO requirements. Based on the laboratory test results, the soils encountered were classified according to the AASHTO and the Illinois Division of Highways (IDH) classification systems. The results of the laboratory testing program are included in the Laboratory Test Results (**Appendix E**) and are also shown along with the field test results in the Soil Boring Logs (**Appendix C**).

2.3 Subsurface Soil Conditions

This section provides a brief description of the soils encountered in the borings performed in the vicinity of the proposed retaining wall and embankment. Variations in the general subsurface soil profile were noted during the drilling activities. Detailed descriptions of the subsurface soils are provided in the soil boring logs and are shown graphically in the Boring Location Plan & Subsurface Profiles. The soil boring logs provide specific conditions encountered at each boring location and include soil descriptions, stratifications, penetration resistance, elevations, location of the samples, and laboratory test data. Unless otherwise noted, soil descriptions indicated on boring logs are visual identifications. The stratifications shown on the boring logs represent the

conditions only at the actual boring locations and represent the approximate boundary between subsurface materials; however, the actual transition may be gradual.

The surface elevations of the borings ranged between 592.5 and 587.9 feet. The boring initially noted 2 to 3 inches of topsoil. Borings RWB-138 noted loose brown silty loam to a depth of 2.5 feet; boring RWB-140 noted hard brown silty clay to a depth of 2.5 feet; and boring RWB-144 noted brown silty loam fill to a depth of 2.5 feet. Below these cohesive materials, and below the topsoil at the remaining locations, the borings encountered medium dense to very dense sand and gravel to the borings' termination depth. All the borings encountered practical auger refusal or split-spoon refusal on apparent bedrock at depths ranging from 4.0 to 14.0 feet below existing grade (elevations 587.3 and 574.9 feet).

The native cohesive soils have unconfined compressive strength value of 4.5 tsf. The native gravel and sand had SPT blow count (N) values ranging from 7 to 100 blows per foot (bpf).

2.4 Subsurface Bedrock Conditions

When bedrock was encountered, a 10-foot bedrock core was collected at 4 boring locations, RWB-138, RWB-140, RWB-41 and RWB-43. The extracted bedrock cores were visually inspected, classified and the Rock Quality Designation (RQD) was determined according to ASTM D 6032, "Standard Test Method for Determining Rock Quality Designation (RQD) of Rock Core" and as per the IDOT geotechnical manual by totaling all sections with a length in excess of four inches (4") and dividing it by the total length of the core run. The RQD is given a classification based upon the numeric value as indicated in **Table 3**. Photographs of the rock cores are included with the respective soil borings in **Appendix C**.

Table 3 - Rock Quality Designation

| Rock Quality Designation | Descriptions |
|--------------------------|--------------|
| < 25% | Very Poor |
| 25 – 50% | Poor |
| 51 – 75% | Fair |
| 76 – 90% | Good |
| 91 – 100% | Excellent |

Table 4 provides a summary of the RQD values and unconfined compressive strength values of the rock cores extracted during the site investigation.

Table 4 – Rock Core Summary and Classification

| Boring Number | Core Run | Core Depth (feet) | Type of Rock | RQD (%) | RQD Classification | Depth (ft)/ Unconfined Compression Strength (psi) |
|---------------|----------|-------------------|--------------|---------|--------------------|------------------------------------------------------|
| RWB-138 | 1 | 14.0-24.0 | Limestone | 91.3 | Excellent | 23.0 / 8,749 |
| RWB-140 | 1 | 6.0-16.0 | Limestone | 3.3 | Very Poor | - |
| RWB-41 | 1 | 5.0-10.0 | Limestone | 11.6 | Very Poor | - |
| | 2 | 10.0-15.0 | Limestone | 0 | Very Poor | - |
| RWB-43 | 1 | 4.0-9.0 | Limestone | 0 | Very Poor | - |
| | 2 | 9.0-14.0 | Limestone | 14.2 | Very Poor | - |

The soil boring logs provide bedrock conditions encountered at each location. The bedrock cores consisted of limestone that was moderately to heavily weathered and moderately to heavily fractured. RQD values ranged from 0 to 91.5 percent: Very Poor to Excellent as shown in **Table 4**.

2.5 Groundwater Conditions

Water levels were checked in each boring to determine the general groundwater conditions present at the site and were measured while drilling and after each boring was completed. Groundwater was only observed while drilling in boring RWB-138 at a depth of 6 feet below grade (Elev. 582.9). Groundwater was not encountered during or immediately after drilling at any of the remaining borings. None of the borings were left open after leaving the site due to safety concerns.

Based on the general lack of water levels and color change from brown to gray observed in the soil borings, it is anticipated that the long-term groundwater level may be near the bedrock interface due to the proximity of the Des Plaines River. Perched water may also be present within the fill observed in the borings. Water level readings were made in the boreholes at times and under conditions shown on the boring logs and stated in the text of this report. However, it should be noted that fluctuations in groundwater level may occur due to variations in the rainfall, other climatic conditions, or other factors not evident at the time measurements were made and reported herein.

3.0 GEOTECHNICAL ANALYSES

This section provides GSG's geotechnical analysis for the design of the proposed retaining wall and embankment based on the results of the field exploration, laboratory testing, and geotechnical analysis. Subsurface conditions between borings may vary from those encountered at the boring locations. If structure locations, loadings, or elevations are changed, we request that GSG be contacted so that we may re-evaluate our recommendations.

3.1 Embankment Settlement

It is anticipated that fill soils will be required to construct the proposed wall and embankment. Up to 11 feet of new fill may be required to construct the new retaining wall.

The proposed new embankment behind the proposed wall was evaluated with respect to settlement. Based on the proposed embankment heights of 11 feet, analyses were performed at the boring locations to evaluate the anticipated amount of total settlement that may be expected. The maximum estimated settlement within the native non-cohesive soils was calculated as shown in **Table 5**.

Table 5 – Anticipated Embankment Settlement

| Structure Name | Structure Stations * | Embankment Height (ft) | Anticipated Settlement (inches) | Differential Settlement (%) |
|----------------|----------------------|------------------------|---------------------------------|-----------------------------|
| New Embankment | 16+75 to Sta. 22+50 | 11.0 | <0.5 | <0.5 |

* Based on proposed Ramp Stationing

3.2 Seismic Parameters

The seismic hazard for the site was analyzed per the IDOT Geotechnical Manual, IDOT Bridge Design Manual, and AASHTO LRFD Bridge Design Specifications. The Seismic Soil Site Class was determined per the requirements of All Geotechnical Manual Users (AGMU) Memo 9.1, Design Guide for Seismic Site Class Determination, and the "Seismic Site Class Determination" Excel spreadsheet provided by IDOT. A global Site Class Definition was determined for this project, and was found to be Soil Site Class C. The Seismic Performance Zone (SPZ) was determined using Figure 2.3.10-2 in the IDOT Bridge Manual and was found to be Seismic Performance Zone 1.

The AASHTO Seismic Design Parameters program was used to determine the peak ground acceleration coefficient (PGA), and the short (S_{DS}) and long (S_{D1}) period design spectral acceleration coefficients for the proposed structure. For this section of the project, the S_{DS} and the S_{D1} were determined using 2020 AASHTO Guide Specifications as shown in **Table 6**. Given the site location and materials encountered, the potential for liquefaction is minimal.

Table 6 – Seismic Parameters

| Building Code Reference | PGA | S_{DS} | S_{D1} |
|--------------------------------------------------|--------|----------|----------|
| 2020 AASHTO Guide for LRFD Seismic Bridge Design | 0.049g | 0.126g | 0.068g |

4.0 GEOTECHNICAL WALL DESIGN RECOMMENDATIONS

This section provides retaining wall design parameters including recommendations on foundation type, bearing capacity, settlement, and lateral earth pressures. The foundations for the proposed retaining wall must provide sufficient support to resist the dead and live loads, as well as seismic loading.

4.1 Retaining Wall Type Recommendations

It is anticipated that the wall will be constructed in a fill section for the proposed new embankment. There are various types of retaining walls that could be utilized for retaining earth embankments in fill areas. This section discusses several earth retaining structures that could be used for the proposed project. Several typical wall types are described in the section below.

4.1.1 CIP Concrete Cantilever Walls

CIP concrete cantilever retaining walls are typically used in fill areas. They are constructed with a footing that extends laterally both in front of and behind the wall. They can be designed to resist horizontal loading with or without tiebacks by changing the geometry of the foundation. This type of wall typically requires that the area behind the wall be excavated to facilitate construction or are constructed where new fill embankments are necessary.

The advantages of a CIP wall include that it is a conventional system with well-established design procedures and performance characteristics; it is durable; and it has the ability to easily be formed, textured, or colored to meet aesthetic requirements. Disadvantages include a relatively long construction period due to undercutting, excavation, form work, steel placement, and curing of the concrete. This wall system is also sensitive to total and differential settlements.

4.1.2 Mechanically Stabilized Earth Walls

An MSE wall is typically associated with fill wall construction and consists of facing such as segmental precast units, dry block concrete or CIP concrete facing units connected to horizontal steel strips, bars or geosynthetic to create a reinforced soil mass. The reinforcement is typically placed in horizontal layers between successive layers of granular backfill. A free draining backfill is required to provide adequate performance of the wall. MSE walls can be used in cut situations as well. The additional cost of the excavations for an MSE wall is usually offset by the savings in construction costs and schedule as compared to a CIP wall on spread footings.

Advantages of the MSE wall include a relatively rapid construction schedule that does not require specialized labor or equipment, provided excavation for the reinforcement is not extensive. This type of retaining wall can accommodate relatively large total and differential settlements without distress, and the reinforcement materials are light and easy to handle. Facing panels can be designed for various architectural finishes.

The design of MSE walls for internal stability is the Contractor's responsibility and will need to be designed by a licensed Structural Engineer in the State of Illinois. The length of the reinforced soil mass from the outside face should be a minimum of 8 feet, but not less than 70% of the wall height. The length should be determined to satisfy eccentricity and sliding criteria and provide adequate length to prevent structural failure with respect to pullout and rupture of reinforcement. The MSE wall could be designed using a unit weight of 120 pcf and a friction angle of 34 degrees for the reinforced backfill soil.

4.1.3 Prefabricated Modular Gravity Walls

This type of wall typically consists of interlocking soil or rock-filled concrete, steel, or wire modules or bins (such as gabions). The combined weight of the wall materials resists the lateral loads from the soil embankment being retained. This type of wall may be used where conventional reinforced concrete walls are also being considered but are typically selected when the overall wall height will be less than 25 feet.

The advantage of this type of wall is that less select fill is required for the backfill behind the wall and the construction is relatively more economical compared to other wall types; however, this type of wall may require additional soil excavation for placement of the modules. The additional cost of the excavations could be offset by the savings in construction costs and schedule as compared to other walls.

4.1.4 Recommended Wall Type

Based on the proposed grading plan, proposed adjacent structures and final location of the wall within a fill area, a MSE wall may be considered for this project. Design plans indicate that the wall location would require a new embankment to reach the proposed roadway subgrade.

GSG evaluated the global and external stability, and settlement to determine the suitability of the retaining wall for this section of the project. The wall section should be analyzed to determine that adequate factors of safety relative to sliding and overturning failure.

4.2 Retaining Wall Design Recommendations

The engineering analyses performed for evaluation of the retaining wall options followed the current AASHTO Load and Resistance Factor Design (LRFD) Methodology as required by IDOT. LRFD methodology incorporates the use of load factors and resistance factors to account for uncertainty in applied loads and load resistance of structure elements separately. The AASHTO LRFD Bridge Design Specifications outline load factors and combinations for various strength, extreme event, service, and fatigue limit states. Section 11, which outlines geotechnical criteria for retaining walls, of the AASHTO Specifications requires the evaluation of bearing resistance failure, lateral sliding, and overturning at the strength limit state and excessive vertical displacement, excessive lateral displacement, and overall stability at the service limit state. The selected wall should be also evaluated with respect to the collision load. **Table 7** outlines the load factors used in evaluation of the retaining wall in accordance with AASHTO Specification Tables 3.4.1-1 and 3.4.1-2.

Table 7 - LRFD Load Factors for Retaining Wall Analyses

| | Type of Load | Sliding and Eccentricity Strength | Bearing Resistance Strength I | Sliding and Eccentricity Extreme II | Bearing Resistance Extreme II | Settlement Service I |
|-------------------------------------|-----------------------------------------|-----------------------------------|-------------------------------|-------------------------------------|-------------------------------|----------------------|
| Load Factors for Vertical Loads | Dead Load of Structural Components (DC) | 0.90 | 1.25 | 1.00 | 1.00 | 1.00 |
| | Vertical Earth Pressure Load (EV) | 1.00 | 1.35 | 1.00 | 1.00 | 1.00 |
| | Earth Surcharge Load (ES) | | 1.50 | | | |
| | Live Load Surcharge (LS) | | 1.75 | | 0.50 | 1.00 |
| Load Factors for Horizontal Loads | Horizontal Earth Pressure Load (EH) | 1.50 | | 1.00 | 1.00 | 1.00 |
| | Active | | 1.50 | | | |
| | At-Rest | | 1.35 | | | |
| | AEP for anchored walls | | 1.35 | | | |
| | Earth Surcharge (ES) | 1.50 | 1.50 | | | |
| | Live Load Surcharge (LS) | 1.75 | 1.75 | 0.50 | 0.50 | 1.00 |
| Load Factor for Vehicular Collision | | | | 1.00 | 1.00 | |

4.2.1 Lateral Earth Pressures and Loading

The wall should be designed to withstand earth and live lateral earth pressures. The lateral earth pressures on retaining walls depend on the type of wall (i.e. restrained or unrestrained), the type of backfill and the method of placement against the wall, and the magnitude of surcharge weight on the ground surface adjacent to the wall. The active earth pressure coefficient (K_a), and the

passive earth pressure coefficient (K_p) were determined in accordance with AASHTO Section 3.11.5.3 and 3.11.5.4. **Table 8** present soil design properties for the retaining wall for the anticipated soil types at the site and provide recommended lateral soil modulus and soil strain parameters that can be used for laterally loaded pile analysis via the p-y curve method based on the encountered subsurface conditions. Additional soil parameters for the site are included in **Appendix D**.

Table 8 – Lateral Soil Parameters

| Elevation Range (feet) | Soil Description | Long-term/Drained | | |
|-------------------------------|-----------------------------------------------------------------|------------------------------------------------------|-------------------------------------------------------|----------------------------------------------------|
| | | Active Earth Pressure Coefficient (K_a) | Passive Earth Pressure Coefficient (K_p) | At-Rest Earth Pressure Coefficient (K_o) |
| | New Engineered Clay Fill | 0.41 | 2.46 | 0.58 |
| | New Engineered Granular Fill | 0.33 | 3.00 | 0.50 |
| 0 - 5.0 (590.0 - 585.0) | Medium Dense to Very Dense Brown and Gray Gravel and Sand | 0.20 | 5.04 | 0.33 |
| 5.0 - 15.0 (585.0 - 575.0) | Gray Limestone | 0.17 | 5.83 | 0.29 |

Traffic and other surcharge loads should be included in the retaining wall design as applicable. A live load surcharge shall be applied where vehicular load is expected to act on the surface of the backfill within a distance equal to one-half the wall height behind the back face of the wall in accordance with AASHTO 3.11.6.4. The live load surcharge may be estimated as a uniform horizontal earth pressure due to an equivalent height (H_{eq}) of soil. **Table 9** provides the equivalent heights of soils for vehicular loadings on retaining walls.

Table 9 - Equivalent Height of Soil for Vehicular Loading on Retaining Walls Parallel to Traffic

| Retaining Wall Height (ft) | H _{eq} Distance from Wall Back face to Edge of Traffic | |
|----------------------------|-----------------------------------------------------------------|---------------------|
| | 0 feet | 1.0 feet or Further |
| 5 | 5.0 feet | 2.0 feet |
| 10 | 3.5 feet | 2.0 feet |
| ≥20 | 2.0 feet | 2.0 feet |

Reference: AASHTO LRFD Table 3.11.6.4-2

The retaining wall design should include a drainage system to allow movement of any water behind the wall, and not allowing hydrostatic (seepage) pressures to develop in the active soil wedge behind the wall. This could be accomplished by placing a Geocomposite Wall Drain over the entire length of the back face of the wall connected to 6-inch diameter perforated drainpipe and backfilling a minimum of 2 feet of free draining materials, Porous Granular Embankment, as measured laterally from the back of the wall. The backfill should be placed in accordance with the IDOT SSRBC.

Heavy compaction equipment should not be allowed closer than five (5) feet to the retaining wall to prevent inducing high lateral earth pressures and causing wall yielding and/or other damage. The passive lateral earth pressure coefficient (K_p) from the upper 3.5 feet of level backfill at the toe of the wall should be neglected unless the soil is confined or protected by a concrete slab or well drained pavement. The passive lateral earth pressure coefficient from the upper 3.5 feet of soil for a descending slope at the wall toe should also be neglected, regardless of any surface protection.

4.2.2 Bearing Resistance – MSE Wall

It is anticipated that the retaining wall will bear on new engineered fill or native gravel and sand. Bearing resistance for the retaining wall shall be evaluated at the strength limit state using load factors (see **Table 7**), and factored bearing resistances. The bearing resistance factor, ϕ_b , for a gravity wall is 0.55 and for a MSE wall is 0.65 per AASHTO Table 11.5.7-1. The bearing resistance shall be checked for the extreme limit state with a resistance factor of 1.0.

Table 10 – Recommended Bearing Resistance for Retaining Wall

| Wall Type | Stations | Elevation (feet) | Nominal Resistance (ksf) | Factored Bearing Resistance (ksf) | Bearing Resistance for 1-inch Settlement Service Limit (ksf) | Bearing Resistance for 2-inch Settlement Service Limit (ksf) | Bearing Resistance for 3-inch Settlement Service Limit (ksf) | Anticipated Bearing Soil |
|-----------|-----------------------|------------------|--------------------------|-----------------------------------|--------------------------------------------------------------|--------------------------------------------------------------|--------------------------------------------------------------|--------------------------|
| MSE wall | Sta.17+25 to 21+50 | 586.7 to 591.5 | 96.3 | 62.6 | 10.0 | 17.5 | 24.5 | Native Gravel and Sand |
| | Sta.21+50 to 22+00.17 | 591.5 to 599.6 | 5.3 | 3.4 | 3.4 | 3.4 | 3.4 | New Clay Fill |

The minimum depth of the wall should be 3.5 feet below the final exterior grade to alleviate the effects of frost. The subgrade soils encountered at the bearing elevations should be cleared of any unsuitable material, such as topsoil. Based on the results of the subsurface exploration, and the assumed wall geometry for the wall shown in **Table 11**, we anticipate the wall would be supported upon the soil types noted in **Table 10**.

4.2.3 Subgrade Undercut Areas

Based on the soil conditions along the wall alignment, little to no undercuts are anticipated.

Undercut areas (if needed) should be replaced with granular structural fill in accordance with IDOT standard construction requirements. The lateral limit of the structural fill should extend a minimum of 1 foot beyond the edge of the footing, then an additional 1 foot laterally for every 2 feet of structural fill depth as depicted in **Exhibit 3**. The granular structural fill should be placed and compacted to a minimum of 95% of the maximum dry density, as determined by AASHTO T-180: Standard Test Methods for Moisture-Density Relations of Soils and Soil-Aggregate Mixtures (ASTM D1557) in accordance with IDOT standard construction requirements.




Exhibit 3 - Structural Fill Placement below MSE Wall

4.3 Sliding and Overturning Stability

The wall base width should be sufficient to resist sliding. The frictional resistance shall include the friction between granular backfill for the wall and supportive granular soils, and the friction between the wall foundation and bearing soils.

The factored resistance against sliding should be calculated using equation 10.6.3.4-1 in the AASHTO LRFD manual. A sliding resistance factor, ϕ , of 1.0 (Table 11.5.7-1) shall be applied to the nominal sliding resistance of soil beneath the wall footing. Assuming a layer of compacted granular material under the footing, the sliding resistance may be taken as one-half the normal stress on the interface between the footing and soil. The width of the footing must be wide enough to resist overturning forces. The location of the resultant of the forces shall be within the middle two-thirds of the base width.

4.4 Wall and Embankment Settlement

Settlement of the proposed wall and embankment system depends on the foundation size and bearing resistance, as well as the strength and compressibility characteristics of the underlying bearing soil. Assuming the foundation subgrade has been prepared as recommended above and the service bearing resistances as noted in **Table 7** are used, the settlement of the retaining wall

will be on the order of 1 inch. Differential settlement between two points of 100 feet apart along the length of the wall will be ½ inch or less.

4.5 Global Slope Stability

Based on the preliminary information provided by WSP, the retaining wall should be designed for external stability of the wall system. The parameters in **Table 11** were used to evaluate the proposed MSE preliminary wall types in order to reach a minimum Factor of Safety of 1.5.

Table 11 – MSE Wall Description

*Based on preliminary drawings provided

| Description | Value at Station | | |
|------------------------------------------------------------|------------------|-------|-------|
| | 17+75 | 21+25 | 21+75 |
| Maximum total retained height of retaining wall (H)*, feet | 10.0 | 13.2 | 7.5 |
| Minimum length of reinforcement 0.7XH or 8.0 feet | 8.0 | 10.0 | 8.0 |
| Unit weight of the retained soil (embankment), pcf | 120 | | |
| Unit weight of the reinforced soil mass, pcf | 120 | | |
| Assumed bearing elevation, feet | 586.5 | 589.3 | 595.5 |

The actual wall width, and total height of the wall should be based on structural analysis performed by a Licensed Structural Engineer in the State of Illinois.

Slide2 is a comprehensive slope stability analysis software used to evaluate the proposed wall for the project based on the limit equilibrium method. The proposed wall was analyzed based on the preliminary grading and the soils encountered while drilling. Circular failure analyses were evaluated using the simplified Bishops analyses methods for the proposed wall geometries. Based on the proposed geometry and the soil borings, global stability analyses were performed.

4.5.1 Global Slope Stability Results

Circular failure analyses were evaluated for both a short term (undrained) and long term (drained) condition based on the proposed geometries (**Table 11**) for the proposed MSE retaining wall scenarios. The analyses were performed at Stations 17+75, 21+25 and 21+75. The results of the analyses are shown in **Table 12**.

Table 12 – Retaining Wall Global Slope Stability Analyses Results

| Analysis Exhibit | Location | Wall Type | Analysis Type | Factor of Safety | Minimum Factor of Safety |
|------------------|---------------|-----------|-----------------------|------------------|--------------------------|
| Exhibit 1 | Station 17+75 | MSE Wall | Circular – Short Term | 3.7 | 1.5 |
| Exhibit 2 | | | Circular – Long Term | 3.0 | 1.5 |
| Exhibit 3 | Station 21+25 | | Circular – Short Term | 2.9 | 1.5 |
| Exhibit 4 | | | Circular – Long Term | 2.3 | 1.5 |
| Exhibit 5 | Station 21+75 | | Circular – Short Term | 3.2 | 1.5 |
| Exhibit 6 | | | Circular – Long Term | 1.9 | 1.5 |

Based on the analyses performed, the proposed retaining wall meets the minimum factor of safety of 1.5. Copies of the slope stability analyses are included in the Slope Stability Analyses Exhibits (**Appendix F**).

4.6 Drainage Recommendations

The wall design should include a drainage system to prevent the buildup of hydrostatic forces behind the wall. This could be accomplished with the installation of drainage blankets, geocomposite drainage panels, or gravel drains behind the facing of the wall with outlet pipes below the facing to collect and remove surface water away from the face of the MSE wall. If weep holes are to be used, it is recommended that a geocomposite wall drain be placed over the interlocks and area of the weep holes. If drainage is not provided, hydrostatic pressure should be included in the wall design and the horizontal earth pressure should be determined in accordance with AASHTO article 3.11.3.

5.0 CONSTRUCTION CONSIDERATIONS

All work performed for the proposed project should conform to the requirements in the IDOT Standard Specifications for Road and Bridge Construction (2022). Any deviation from the requirements in the manuals above should be approved by the design engineer.

5.1 Site Preparation

All trees, pavements, vegetation, landscaping, and surface topsoil should be cleared and removed from the vicinity of the proposed construction. Where possible, the engineer may require proof-rolling of the subgrade with a 35-ton loaded truck or other pneumatic-tired vehicle of similar size and weight. The purpose of the proof-rolling is to locate soft, weak, or excessively wet soils present at the time of construction. Proof-rolling should be performed during a time of good weather and not while the site is wet, frozen, or severely desiccated. Any unsuitable materials observed during the evaluation and proof-rolling operations should be undercut and replaced with compacted structural fill and/or stabilized in-place. The possible need for, and extent of, undercutting and/or in-place stabilization required can best be determined by the geotechnical engineer at the time of construction. Once the site has been properly prepared, at grade construction may proceed.

Foundation aggregate fill should not be placed upon wet or frozen subgrade soils. If the subgrade or structural fill becomes frozen, desiccated, wet, disturbed, softened, or loose, the affected materials should be scarified, dried and moisture conditioned, and compacted to the full depth of the affected area or the soils should be removed. Rainfall and runoff can soften soils and affect the load bearing capacity of the soils. All water entering the foundation excavation should be removed prior to placement of backfill materials above the wall bottom.

5.2 Existing Utilities

Based on the existing site conditions, utilities exist along the project corridor. Before proceeding with construction, all existing underground utility lines or structures that will interfere with construction should be completely relocated from the proposed construction areas. Where possible, existing utility lines that are to be abandoned in place should be removed and/or plugged with a minimum of 2 feet of cement grout. All excavations resulting from underground utilities removal activities should be cleaned of loose and disturbed materials, including all previously placed backfill, and backfilled with suitable fill materials in accordance with the

requirements of this section. During the clearing and stripping operations, positive surface drainage should be maintained to prevent the accumulation of water.

5.3 Site Excavation

Site excavations are expected to encounter various types of soils as described in the Subsurface Exploration section of this report. The contractor will be responsible to provide a safe excavation during the construction activities of the project. All excavations should be conducted in accordance with applicable federal, state, and local safety regulations, including, but not limited to the Occupational Safety and Health Administration (OSHA) excavation safety standards. Excavation stability and soil pressures on temporary shoring are dependent on soil conditions, depth of excavations, installation procedures, and the magnitude of any surcharge loads on the ground surface adjacent to the excavation. Excavation near existing structures and underground utilities should be performed with extreme care to avoid undermining existing structures. Excavations should not extend below the level of adjacent existing foundations or utilities unless underpinning or other support is installed. It is the responsibility of the contractor for field determinations of applicable conditions and providing adequate shoring (if needed) for all excavation activities.

5.4 Borrow Material and Compaction Requirements

If borrow material is to be used for onsite construction, it should conform to Section 204 “Borrow and Furnish Excavations” of the IDOT Construction Manual (2022). The fill material should be free of organic matter and debris and should be placed and compacted in accordance with Section 205, Embankment, of the IDOT Construction Manual. Should fill be placed during cool, wet seasons, the use of granular fill may be necessary since weather conditions will make compaction of cohesive soils more difficult. If water seepage while excavating and backfilling procedures, or where wet conditions are encountered such that the water cannot be removed with conventional sump and pump procedures, GSG recommends placing open grade stone similar to IDOT CA-7 to stabilize the bottom of the excavation. The CA-7 stone should be placed 12 inches above the water level, in 12-inch lifts, and should be compacted with the use of a heavy smooth drum roller or heavy vibratory plate compactor until stable. The remaining portion of the excavation should be backfilled using approved engineered fill.

GSG recommends that subgrade preparation, and structural fill placement and compaction be inspected by a GSG geotechnical engineer to verify the type and strength of soil materials present at the site and their conformance with the geotechnical recommendations in this report.

5.5 Groundwater Management

Based on the general lack of water levels and color change from brown to gray observed in the soil borings, it is anticipated that the long-term groundwater level may be near the bedrock interface. GSG does not anticipate that significant groundwater related issues will occur during construction activity, however perched water may be encountered within the existing fill. If rainwater run-off or groundwater is accumulated at the base of excavations, the contractor should remove accumulated water using conventional sump pit and pump procedures and maintain a dry and stable excavation. The location of the sump should be determined by the contractor based on field conditions. During earthmoving activities at the site, grading should be performed to ensure that drainage is maintained throughout the construction period. Water should not be allowed to accumulate in the foundation area either during or after construction. Undercut and excavated areas should be sloped toward one corner to facilitate removal of any collected rainwater or surface run-off. Grades should be sloped away from the excavations to minimize runoff from entering.

If water seepage occurs during excavations or where wet conditions are encountered such that the water cannot be removed with conventional sumping, we recommend placing open grade stone similar to IDOT CA-7 to stabilize the bottom of the excavation below the water table. The CA-7 stone should be placed 12 inches above the water table, in 12-inch lifts, and should be compacted with the use of a heavy smooth drum roller or heavy vibratory plate compactor until stable. The remaining portion of the excavation beneath the footings should be backfilled using approved structural fill.

6.0 LIMITATIONS

This report has been prepared for the exclusive use of the Illinois Department of Transportation (IDOT) and its Design Section Engineer consultant. The recommendations provided in the report are specific to the project described herein and are based on the information obtained at the soil boring locations within the proposed project area. The analyses have been performed and the recommendations provided in this report are based on subsurface conditions determined at the location of the borings. This report may not reflect all variations that may occur between boring locations or at some other time, the nature and extent of which may not become evident until during the time of construction. If variations in subsurface conditions become evident after submission of this report, it will be necessary to evaluate their nature and review the recommendations presented herein.

Appendix A
General Plan
and Elevation

Benchmark: Chiseled "X" on top of SE bolt of Fire Hydrant at South ROW of Jasper St. (in front of 640 Jasper St. address), Elev. 585.86.

Existing Structure: None.

Traffic Control: Traffic will be detoured during construction.

Salvage: *None.*

DESIGN STRESSES

PRECAST UNITS

$$f_c = 4,500 \text{ psi}$$

FIELD UNITS


$$f_c = 3,500 \text{ psi}$$
 $f_y = 60,000 \text{ psi (Reinforcement)}$

DESIGN SPECIFICATIONS

2020 AASHTO LRFD Bridge Design
Specifications, 9th Edition

HIGHWAY SPECIFICATION

Center Street
Functional Class: Minor Arterial
ADT: 18,900 (2019); 29,100 (2040)
ADTT: 1,266 (2019); 1,950 (2040)
DHV: 3,201 (2040)
Design Speed: 35 m.p.h.
Posted Speed: 35 m.p.h.
2-Way Traffic
Direction Distribution: 50-50



NOTES:

1. Stations and offsets are measured along the ℄ of Center Street to the front face of the precast panels.
2. For Table 1- Wall Elevations, Typical Section thru MSE Walls, Profile Grade Lines and Curve Data, See Sheet 2 of 2.


GENERAL PLAN & ELEVATION
RETAINING WALL 5
ALONG CENTER STREET
F.A.I. ROUTE I-80
SECTION FAI 80 21 INTERCHANGE
WILL COUNTY
STA. 17+25.00 TO STA. 22+00.17
STRUCTURE NO. 099-WXXX

TABLE 1- WALL ELEVATIONS

| Station | A | B | C | D | E |
|----------|---------------|------------------|-------------------------|------------------------|----------------------|
| | Top of Coping | Bottom of Coping | Exist. Grade at FF Wall | T/Prop. Ground FF Wall | Top of Levelling Pad |
| 17+25.00 | 595.48 | 593.73 | 588.61 | 593.73 | 589.94 |
| 17+50.00 | 595.82 | 594.07 | 588.99 | 593.24 | 588.92 |
| 17+75.00 | 596.17 | 594.42 | 589.55 | 591.41 | 587.91 |
| 18+00.00 | 596.53 | 594.78 | 589.96 | 590.39 | 586.89 |
| 18+25.00 | 596.88 | 595.13 | 590.39 | 590.89 | 587.36 |
| 18+50.00 | 597.23 | 595.48 | 591.11 | 591.63 | 587.83 |
| 18+75.00 | 597.58 | 595.83 | 591.48 | 592.03 | 588.31 |
| 19+00.00 | 597.96 | 596.21 | 591.84 | 592.40 | 588.78 |
| 19+25.00 | 598.34 | 596.59 | 592.18 | 592.75 | 589.25 |
| 19+50.00 | 598.74 | 596.99 | 592.62 | 593.22 | 589.72 |
| 19+75.00 | 599.22 | 597.47 | 592.59 | 593.31 | 589.42 |
| 20+00.00 | 599.70 | 597.95 | 592.09 | 592.81 | 589.12 |
| 20+25.00 | 600.18 | 598.43 | 591.59 | 592.32 | 588.82 |
| 20+50.00 | 600.67 | 598.92 | 591.46 | 592.27 | 588.84 |
| 20+75.00 | 601.16 | 599.41 | 591.72 | 592.49 | 588.86 |
| 21+00.00 | 601.64 | 599.89 | 591.63 | 592.49 | 588.88 |
| 21+25.00 | 602.11 | 600.36 | 591.53 | 592.49 | 588.90 |
| 21+50.00 | 602.58 | 600.83 | 591.44 | 594.13 | 590.63 |
| 21+75.00 | 603.05 | 601.30 | 591.83 | 599.12 | 595.25 |
| 22+00.17 | 603.59 | 601.84 | 591.47 | 603.36 | 599.89 |

PR CURVE CENTER-3

PI Sta. = 25+64.87
Δ = 33° 44' 53" (LT)
D = 5° 43' 46"
R = 1,000.00'
T = 303.33'
L = 589.01'
E = 44.99'
e = 3.00%
T.R. = 80.00'
S.E. RUN = 160'
P.C. STA. = 22+61.54
P.T. STA. = 28+50.55




TYPICAL SECTION THRU M.S.E WALL
(Looking North)

* Sonotubes and traffic signals foundations shall be placed during the backfilling of the reinforced soil zone to allow for the installation of the guardrail and the traffic signals without damaging the soil reinforcement. Coordinate with Roadway plans for the location of the guardrail posts and traffic signals.

** Catch Basin A4 shall be placed during the backfilling of the reinforced soil zone without damaging the soil reinforcement.

*** Sta. 17+85.00 to Sta. 20+50.00



CENTER ST. PROFILE GRADE
(Along B Roadway)

SECTION & DETAILS
RETAINING WALL 5
ALONG CENTER STREET
F.A.I. ROUTE I-80
SECTION FAI 80 21 INTERCHANGE
WILL COUNTY
STA. 17+25.00 TO STA. 22+00.17
STRUCTURE NO. 099-WXXX

MODEL: Default
FILE NAME: p:\projects\systems-pw-bentley\comtrans\scorp-pw1\hatched\Documents\Projects_2018\CH401\401180022\03-W59\CAD\62R22-NIT-4 [Center]Sheet5Structural\SN-099-WXXX-RW5\099-WXXX-62R22-TS12




| | | | | | |
|------------|---------------------|----------|----------|---------|---|
| USER NAME | stoyanka.kotorokova | DESIGNED | PG | REVISED | - |
| | | DRAWN | PG | REVISED | - |
| PLOT SCALE | 5,000' / in. | CHECKED | MI, SK | REVISED | - |
| PLOT DATE | 10/19/2022 | DATE | 10/18/22 | REVISED | - |

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCALE: SHEET 2 OF 2 SHEETS STA. TO STA.

| | | | | |
|---------------------------|-----------------------|--------|--------------|-----------|
| F.A.I. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 80 | FAI 80 21 INTERCHANGE | WILL | 2 | 2 |
| CONTRACT NO. 62R22 | | | | |
| ILLINOIS FED. AID PROJECT | | | | |

Appendix B
Soil Boring Location Plan and Subsurface Profile



LEGEND

 SOIL BORINGS

FILE NAME: \$FILEL\$
PEN TABLE: \$PENTBL\$
PLOT DATE: \$DATE\$
SHEET SIZE: \$SHEETSIZE\$
PLOT SCALE: \$SCALE\$
USER NAME: \$USER\$



GSG CONSULTANTS, INC.
735 E. REMINGTON RD, SCHAUMBURG, IL 60173
TEL: +1630.994.2600 | WWW.GSG-CONSULTANTS.COM


| | | | |
|------------|-----------------|----------|--------------|
| USER NAME | = \$USER\$ | DESIGNED | - ES |
| SHEET SIZE | = \$SHEETSIZE\$ | DRAWN | - NN |
| PLOT SCALE | = \$SCALE\$ | CHECKED | - DE |
| PLOT DATE | = \$DATE\$ | DATE | - 08/24/2022 |

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

| | | | |
|---------------------------|---------|-------------|--------------|
| RETAINING WALL NO. 5 | | | |
| SOIL BORING LOCATION PLAN | | | |
| JOLIET, ILLINOIS | | | |
| SCALE: 1:50 | SHEET 1 | OF 1 SHEETS | STA. TO STA. |

| | | | | |
|---------------------------|---------|--------|--------------|-----------|
| F.A. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| | | WILL | XX | 1 |
| CONTRACT NO. PTB-198-003 | | | | |
| ILLINOIS FED. AID PROJECT | | | | |

FILE NAME = \\gsg\GIS\Projects - Engineering\Illinois DOT\MSR_198-003\Geotechnical\Retaining Wall No. 5 - PR-21.dgn
PEN TABLE = X:\Clients\Tollway\WorkSpace\tables\pen\gsg mono.ctb
PLOT DATE = 9/13/2022
PLOT TIME = 1:55:44 PM
SHEET SIZE = 1.41667x0.916667 (ft.)
PLOT SCALE = 1200:0.0000 " = 1' / ft.
USER NAME = mnano



GSG CONSULTANTS, INC.
735 E. REMINGTON RD, SCHAUMBURG, IL 60173
TEL: +1630.994.2600 | WWW.GSG-CONSULTANTS.COM

| | | | |
|------------|----------------------------|----------|--------------|
| USER NAME | = mnano | DESIGNED | = ES |
| SHEET SIZE | = 1.41667x0.916667 (ft.) | DRAWN | = NN |
| PLOT SCALE | = 1200:0.0000 " = 1' / ft. | CHECKED | = DE |
| PLOT DATE | = 9/13/2022 | DATE | = 09/12/2022 |


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

RETAINING WALL NO. 5
SOIL BORING PROFILE

| | | | | |
|---------------------------|---------|--------|--------------|-----------|
| F.A. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| | | WILL | xx | 2 |
| CONTRACT NO. PTB- 198-003 | | | | |

SCALE: AS NOTED | SHEET 1 OF xx SHEETS | STA. 16+75 TO STA. 19+25 | ILLINOIS | FED. AID PROJECT

FILE NAME = \\gsg\GIS\projects-engineering\Illinois DOT\WSP_198-003\Geotechnical\Retaining Walls\Retaining Wall No. 5 - PR-02.dgn
PEN TABLE = X:\Clients\ToWay\WorkSpace\tables\pen\gsg mono.tbl
PLOT DATE = 9/13/2022
PLOT SCALE = 1.41667x0.916667 (ft.)
USER NAME = mmano




| | | | |
|------------|---------------------------|----------|--------------|
| USER NAME | = mmano | DESIGNED | - ES |
| SHEET SIZE | = 1.41667x0.916667 (ft.) | DRAWN | - NN |
| PLOT SCALE | = 1200:0.0000 " : " / ft. | CHECKED | - DE |
| PLOT DATE | = 9/13/2022 | DATE | - 09/12/2022 |

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

| | | | | | | | | |
|----------------------|--|--|--|---------------------------|---------|--------|--------------|-----------|
| RETAINING WALL NO. 5 | | | | F.A. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| SOIL BORING PROFILE | | | | | | WILL | 4 | 3 |
| SCALE: AS NOTED | | | | CONTRACT NO. PTB- 198-003 | | | | |
| SHEET 2 OF 3 SHEETS | | | | ILLINOIS FED. AID PROJECT | | | | |

FILE NAME = \\gsg\GIS\projects-engineering\Illinois DOT\WSP_198-003\Geotechnical\Retaining Walls\Retaining Wall No. 5 - PR-03.dgn
PEN TABLE = X:\Clients\ToWay\WorkSpace\tables\pen\gas mono.tbl
PLOT DATE = 9/13/2022
PLOT SCALE = 1:1000
SHEET SIZE = 1.41667x0.91667 (ft.)
PLOT SCALE = 1200:0.0000 " = 1' / ft.
USER NAME = mnano



Appendix C
Soil Boring Logs



Illinois Department of Transportation

Division of Highways
GSG Consultants, Inc.

SOIL BORING LOG

Page 1 of 1

Date 8/18/22

ROUTE I-80 DESCRIPTION Retaining Wall No. 5 - Center Street Sta 20+60 LOGGED BY KA

SECTION C-91-109-22 LOCATION SEC. , TWP. , RNG. ,

Latitude 41.5102468, Longitude -88.1003021

COUNTY Will DRILLING RIG Diedrich D-50 ATV HAMMER TYPE Auto

DRILLING METHOD

HSA

HAMMER EFF (%)

102

STRUCT. NO.
Station

BORING NO. RWB-137
Station 16+99.2138
Offset 37.42ft RT
Ground Surface Elev. 587.94 ft

| D E P T H (ft) | B L O W S (/6") | U C S Qu (tsf) | M O I S T (%) |
|-------------------------------|--------------------------------|----------------------------|------------------------------|
|-------------------------------|--------------------------------|----------------------------|------------------------------|

Surface Water Elev. N/A ft
Stream Bed Elev. N/A ft

Groundwater Elev.:
First Encounter Dry ft
Upon Completion N/A ft
After Hrs. N/A ft

2 inches of Topsoil 587.78

Dense to Very Dense
Brown and Gray, Moist
GRAVEL, with sand (GPS)

9
20
18

8

50

582.94 -5

Very Dense
Gray, Moist
GRAVEL (GP)

50

Auger refusal at 8.0 feet 579.94
End of Boring


-10

-15

-20

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)

BBS, form 137 (Rev. 8-99)


Page 1 of 1

Date 8/18/22


| | | | | | | | | |
|-----------------------------------------------------------------|--------|----|---|----|------------------------------------------------------------|--|--|--|
| 2 inches of Topsoil | 588.71 | | | | Gray Limestone, moderately weathered, moderately fractured | | | |
| Loose Brown, Very Moist SILTY LOAM, trace sand, gravel (ML) | 586.37 | 3 | 4 | 19 | Run 1: 14' - 24' | | | |
| | | 3 | | | Recovery: 100% | | | |
| Medium Dense Gray and Brown, Wet GRAVEL (GP) | | 11 | | | RQD: 91.3% (Excellent) | | | |
| Cobble at 3.5 feet | | 16 | | | (continued) | | | |
| | 583.87 | 9 | | | 564.87 | | | |
| Loose to Very Dense Brown, Moist to Wet GRAVEL, with sand (GPS) | | 11 | | | End of Boring | | | |
| | | 13 | | 19 | | | | |
| | | 9 | | | | | | |
| | | 7 | | | | | | |
| | | 5 | | 17 | | | | |
| | -10 | 7 | | | | | | |
| | | 3 | | | | | | |
| | | 3 | | 14 | | | | |
| | | 4 | | | | | | |
| | | 50 | | | | | | |
| Auger refusal at 14.0 feet | 574.87 | | | 13 | | | | |
| Gray Limestone, moderately weathered, moderately fractured | -15 | | | | | | | |
| Run 1: 14' - 24' | | | | | | | | |
| Recovery: 100% | | | | | | | | |
| RQD: 91.3% (Excellent) | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | -20 | | | | | | | |

BBS, form 137 (Rev. 8-99)

Retaining Wall #5
Boring Number: RWB-138



| Boring No. | Run | Depth (ft) | Recovery (%) | RQD (%) | RQD Classification | Description | Depth (ft)/ Unconfined Compression Strength (psi) |
|------------|-----|------------|--------------|---------|--------------------|-----------------------------------------------------------------|---------------------------------------------------|
| RWB-138 | 1 | 14' – 24' | 100.0 | 91.3 | Excellent | Gray Limestone Moderately Weathered, Moderately Fractured | 23.0 / 8,749 |

Page 1 of 1

Date 8/17/22

[illegible]

BBS, form 137 (Rev. 8-99)



Illinois Department of Transportation

Division of Highways
GSG Consultants, Inc.

SOIL BORING LOG

Page 1 of 1

Date 8/17/22

ROUTE I-80 DESCRIPTION Retaining Wall No. 5 - Center Street Sta 20+60 LOGGED BY KA

SECTION C-91-109-22 LOCATION SEC. , TWP. , RNG. ,

COUNTY Will DRILLING RIG Diedrich D-50 ATV Latitude 41.5107034, Longitude -88.0998523
DRILLING METHOD HSA HAMMER TYPE Auto
HAMMER EFF (%) 102

STRUCT. NO. _____
Station _____

BORING NO. RWB-140
Station 19+9.8549
Offset 26.96ft RT
Ground Surface Elev. 592.48 ft

| D E P T H (ft) | B L O W S (/6") | U C S Qu (tsf) | M O I S T (%) |
|-------------------------------|--------------------------------|----------------------------|------------------------------|
|-------------------------------|--------------------------------|----------------------------|------------------------------|

Surface Water Elev. N/A ft
Stream Bed Elev. N/A ft
Groundwater Elev.:
First Encounter Dry ft
Upon Completion N/A ft
After Hrs. N/A ft

3 inches of Topsoil 592.23
Hard
Brown, Moist
SILTY CLAY, trace sand, gravel
(CL/ML) 589.98

| | | | |
|---|---|-----|----|
| 8 | 7 | 4.5 | 17 |
| 9 | 9 | P | |

Medium Dense
Light Brown, Moist
GRAVEL, with sand (GPS)
11
13
10
-5

| |
|---|
| 2 |
|---|

Auger refusal at 6.0 feet 586.48
Gray
LIMESTONE, moderately
weathered, heavily fractured,
vertical fractures
Run 1: 6' - 16'
Recovery: 100%
RQD: 3.33% (Very poor)
-10

| |
|--|
| |
|--|


End of Boring 576.48

| |
|--|
| |
|--|


The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)

BBS, form 137 (Rev. 8-99)

Retaining Wall #5
Boring Number: RWB-140



| Boring No. | Run | Depth (ft) | Recovery (%) | RQD (%) | RQD Classification | Description |
|------------|-----|------------|--------------|---------|--------------------|----------------------------------------------------------------------------|
| RWB-140 | 1 | 6' – 16' | 100.0 | 3.333 | Very Poor | Gray Limestone Moderately Weathered, Heavily Fractured, Vertical Fractures |

Page 1 of 1

Date 8/15/22

This image shows a completely blank white page enclosed within a thin black rectangular frame. There are no markings, text, or illustrations on the page.

BBS, form 137 (Rev. 8-99)



Illinois Department of Transportation

Division of Highways
GSG Consultants, Inc.

SOIL BORING LOG

Page 1 of 1

Date 7/12/22

ROUTE I-80 DESCRIPTION Retaining Wall No. 5 - Center Street Sta 20+60 LOGGED BY KA

SECTION C-91-109-22 LOCATION SEC. 16, TWP. 35 N, RNG. 10 E,

Latitude 41.5108323, Longitude -88.0996418

COUNTY Will DRILLING RIG Diedrich D-50 ATV HAMMER TYPE Auto

DRILLING METHOD HSA

HAMMER EFF (%) 102

STRUCT. NO. _____
Station _____

BORING NO. RWB-41
Station 19+84.7434
Offset 35.90ft RT
Ground Surface Elev. 591.91 ft

| D E P T H (ft) | B L O W S (/6") | U C S Qu (tsf) | M O I S T (%) |
|-------------------------------|--------------------------------|----------------------------|------------------------------|
|-------------------------------|--------------------------------|----------------------------|------------------------------|

Surface Water Elev. N/A ft
Stream Bed Elev. N/A ft
Groundwater Elev.:
First Encounter Dry ft
Upon Completion N/A ft
After _____ Hrs. N/A ft

3 inches of Topsoil 591.66

Dense to Very Dense
Brown and Light Gray, Moist to
Wet
SAND, with gravel and silt (SPG)

| | | |
|----|----|----|
| 9 | 26 | 16 |
| 17 | | |

Cobbles at 2.5 feet

| | | |
|---|-------|----|
| 9 | 50/2" | 12 |
|---|-------|----|

586.91 -5

Auger refusal at 5.0 feet

Light Gray
LIMESTONE, slightly weathered,
moderately fractured

Run 1: 5' - 10'
Recovery: 100%
RQD: 11.6% (Very Poor)

Run 2: 10' - 15'
Recovery: 100%
RQD: 0% (Very Poor)

-10

576.91 -15

End of Boring

-20

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)

BBS, form 137 (Rev. 8-99)

Retaining Wall #5
Boring Number: RWB-41




| Boring No. | Run | Depth (ft) | Recovery (%) | RQD (%) | RQD Classification | Description |
|------------|-----|------------|--------------|---------|--------------------|---------------------------------------------------------------|
| RWB-41 | 1 | 5.0' – 10' | 100.0 | 11.6 | Poor | Light Gray Limestone Slightly Weathered, Moderately Fractured |
| RWB-41 | 2 | 10' – 15' | 100.0 | 0 | Very Poor | Light Gray Limestone Slightly Weathered, Moderately Fractured |

Page 1 of 1

Date 7/7/22


BBS, form 137 (Rev. 8-99)

Page 1 of 1

Date 7/12/22

BBS, form 137 (Rev. 8-99)

Retaining Wall #5
Boring Number: RWB-43



| Boring No. | Run | Depth (ft) | Recovery (%) | RQD (%) | RQD Classification | Description |
|------------|-----|--------------|--------------|---------|--------------------|--------------------------------------------------------------|
| RWB-41 | 1 | 4.0' – 9.0' | 100.0 | 0 | Very Poor | Light Gray Limestone Heavily Weathered, Moderately Fractured |
| RWB-41 | 2 | 9.0' – 14.0' | 100.0 | 14.2 | Very Poor | |

Appendix D
Soil Parameter Table

**Table – Summary of Soil Parameters
Retaining Wall #5**

| Depth Range (Elevation, feet) | Soil Description | In situ Unit Weight γ (pcf) | Undrained | | Drained | |
|----------------------------------|-----------------------------------------------------------|------------------------------------------|---------------------|------------------------------|----------------------|-------------------------------|
| | | | Cohesion C (psf) | Friction Angle ϕ (°) | Cohesion C' (psf) | Friction Angle ϕ' (°) |
| | New Engineered Clay Fill | 125 | 1,000 | 0 | 100 | 25 |
| | New Engineered Granular Fill | 125 | 0 | 30 | 0 | 30 |
| 0 - 5.0 (590.0 - 585.0) | Medium Dense to Very Dense Brown and Gray Gravel and Sand | 129 | 0 | 42 | 0 | 42 |
| 5.0 - 15.0 (585.0 - 575.0) | Gray Limestone | 150 | 0 | 45 | 0 | 45 |

Appendix E
Laboratory Test Results

Compressive Strength of Rock by ASTM D7012 - Method C



GSG CONSULTANTS, INC.
735 Remington Road, Schaumburg, IL 60173
Tel: 630.994.2600, www.gsg-consultants.com

Project Name: WSP_198-003 I-80
Boring ID: RWB-138
Sample Depth (ft): 23
Lithological Description: Lime Stone
Formation Name: _____ Load Direction: _____
Appearance (e.g. cracks, shearing, spalling): _____

Project No: 21-2007
Bulk/Prep MC/CS
Tester: SM Tester: SM
Date: 09/07/22 Date: 09/07/22
Angle Drilled: Vertical

Bulk Density Determination

| | 1 | 2 | 3 | Average |
|--------------------------|--------|--------|--------|-----------------|
| Height, <i>in.</i> | 4.7785 | 4.7730 | 4.7760 | 4.7758 |
| Diameter, <i>in.</i> | 1.9850 | 1.9840 | 1.9825 | 1.9838 |
| Specimen Mass, <i>g</i> | 650.1 | | | Ratio (2.0-2.5) |
| Bulk Density, <i>pcf</i> | 167.8 | | | 2.41 |

Moisture Condition - D2216

| | |
|-------------------------|-------|
| Container ID | Taffy |
| container, g | 226.6 |
| container + wet rock, g | 745.8 |
| container + dry soil, g | 744.5 |
| moisture content, w% | 0.3 |

Preparation Check

| | Yes | No | Reason/Readings If No: |
|--------------------------------------------------|-----|----|------------------------|
| Ends Flat within 0.02 mm prior to capping? | X | | |
| Ends perpendicular to side within 0.25 degrees? | | | |
| Ends parallel to each other within 0.25 degrees? | X | | |

Axial Loading

| | | Remarks |
|------------------------------------|--------------|----------------------------------------------------------------------------------------------------------------------------|
| Seating Load (≤ 1000 psi) | 1000 | Best efforts have been made for the specimen to meet the required tolerances of D4543. See IH3 Procedure for efforts made. |
| Rate of Loading (73-145 psi/s) | 75 | |
| Time to Failure (2-15 min) | 3 min 27 sec | |
| Load @ Failure, lbf | 27,042 | |
| Uniaxial Compressive Strength, psi | 8,749 | |

After Preparation




After Break (check applicable appearance)

| | | |
|------------------------------|------------------------------|-----------------------------------------|
| <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
| <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |





| | | | |
|---------------|------------|-------------|--|
| Form ID | TF-RCS | Reviewed By | |
| Revision Date | 10/21/2021 | Review Date | |


Appendix F
Slope Stability Analysis Exhibits



| Material Name | Color | Unit Weight (lbs/ft3) | Strength Type | Cohesion (psf) | Phi (deg) |
|--------------------------------|-------------|-----------------------|-------------------|----------------|-----------|
| New Clay Fill Undrained | <div></div> | 125 | Mohr-Coulomb | 1000 | 0 |
| Brown and Gray Sand and Gravel | <div></div> | 129 | Mohr-Coulomb | 0 | 42 |
| Limestone | <div></div> | 150 | Mohr-Coulomb | 0 | 45 |
| Brown Silty Loam | <div></div> | 120 | Mohr-Coulomb | 0 | 37 |
| MSE Wall | <div></div> | 120 | Infinite strength | | |




| Material Name | Color | Unit Weight (lbs/ft3) | Strength Type | Cohesion (psf) | Phi (deg) |
|--------------------------------|-------|-----------------------|-------------------|----------------|-----------|
| New Silty Clay Fill Drained | | 125 | Mohr-Coulomb | 100 | 25 |
| Brown and Gray Sand and Gravel | | 129 | Mohr-Coulomb | 0 | 42 |
| Limestone | | 150 | Mohr-Coulomb | 0 | 45 |
| Brown Silty Loam | | 120 | Mohr-Coulomb | 0 | 37 |
| MSE Wall | | 120 | Infinite strength | | |




GSG CONSULTANTS, INC.
735 Remington Road, Schaumburg, IL 60173
Tel: 630.994.2600, www.gsg-consultants.com


SLIDEINTERPRET 9.031

| | | | |
|----------------------|-----------------------------------------------------------------------|-----------|-----------------------|
| Project | I-80: IDOT PTB 198-003 - Retaining Wall #5 - MSE Wall - Station 21+25 | | |
| Analysis Description | Exhibit 3 - Circular Failure Short Term | | |
| Drawn By | MH | Company | GSG Consultants, Inc. |
| Date | 9/27/2019, 2:18:40 PM | File Name | MSE Wall 21+25.slm |





| Material Name | Color | Unit Weight (lbs/ft3) | Strength Type | Cohesion (psf) | Phi (deg) |
|--------------------------------|-------------|-----------------------|-------------------|----------------|-----------|
| New Clay Fill Undrained | <div></div> | 125 | Mohr-Coulomb | 1000 | 0 |
| Brown and Gray Sand and Gravel | <div></div> | 129 | Mohr-Coulomb | 0 | 42 |
| Limestone | <div></div> | 150 | Mohr-Coulomb | 0 | 45 |
| MSE Wall | <div></div> | 120 | Infinite strength | | |



| Material Name | Color | Unit Weight (lbs/ft3) | Strength Type | Cohesion (psf) | Phi (deg) |
|--------------------------------|-------------|-----------------------|-------------------|----------------|-----------|
| New Silty Clay Fill Drained | <div></div> | 125 | Mohr-Coulomb | 100 | 25 |
| Brown and Gray Sand and Gravel | <div></div> | 129 | Mohr-Coulomb | 0 | 42 |
| Limestone | <div></div> | 150 | Mohr-Coulomb | 0 | 45 |
| MSE Wall | <div></div> | 120 | Infinite strength | | |