

PA:2320800-Marion\VA\Resto\CGT\ra\01_CADD\Maril\07-10_Schedules.dwg 7-16-25 03:24:02 PM mkrumrey

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
N/A	23-00131-00-BT	WILLIAMSON	55	07
ILLINOIS		VA/HALFWAY RD. GREENWAY		
CONTRACT NO. 99760				

CURB & GUTTER REMOVAL

LOCATION - STATION	44000300	44000500
	CURB REMOVAL	COMBINATION CURB AND GUTTER REMOVAL
	FOOT	FOOT
WEST MAIN STREET		
748+20		16
750+48		12
750+85		11
754+82		13
755+09		11
771+93		15
772+84		15
777+47		12
777+87		12
GREYHOUND TRAIL		
2+82	17	
SOUTH HALFWAY ROAD		
3+37		14
14+10		37
15+00		85
17+19 TO 18+49		130
17+10	46	
18+10	33	
43+87	17	
PROJECT TOTAL	113	383

SIDEWALK & RETAINING WALL REMOVAL

LOCATION STATION TO STATION	44000600	Z0075496
	SIDEWALK REMOVAL	CONCRETE RETAINING WALL REMOVAL
	SQ FT	FOOT
WEST MAIN STREET		
755+30	162	
761+52 TO 761+94	240	11
762+19 TO 764+10	931	
764+10 TO 766+01	947	
767+69 TO 771+90	2,103	
772+90 TO 773+10	135	
773+10 TO 777+46	2,080	
777+88 TO 778+15.5	115	
GREYHOUND TRAIL		
0+00 TO 2+82	1,360	
PROJECT TOTAL	8,073	11

PAVEMENT-SHOULDER-DITCH REMOVALS

LOCATION STATION TO STATION	44000200	44004250	44004000
	DRIVEWAY PAVEMENT REMOVAL	PAVED SHOULDER REMOVAL	PAVED DITCH REMOVAL
	SQ YD	SQ YD	FOOT
WEST MAIN STREET			
755+18 TO 761+84		142	
762+30 TO 764+88		53	
768+25 TO 771+57		101	
GREYHOUND TRAIL			
0+00 TO 2+82			
SOUTH HALFWAY ROAD			
14+60	265		
PEPSI			
758+70			218
PROJECT TOTAL	265	296	218

EARTHWORK SCHEDULE

LOCATION STATION TO STATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	CU YD	CU YD	CU YD	CU YD
	CU YD	CU YD	CU YD	CU YD
WEST MAIN STREET TRAIL				
748+50 TO 750+50	40.0	30.0	4.0	26.0
750+82 TO 754+80	137.0	102.8	7.0	95.8
755+07 TO 762+00	8.0	6.0	1515.0	-1509.0
762+15 TO 766+00	120.0	90.0	358.0	-268.0
767+65 TO 771+87	54.0	40.5	631.0	-590.5
772+80 TO 778+11	104.0	78.0	9.0	69.0
SOUTH HALFWAY ROAD TRAIL				
2+54 to 14+50	70.0	52.5	98.0	-45.5
14+50 to 44+00	776.0	582.0	183.0	399.0
TOTAL	1,309	982	2,805	-1,823

THE EARTHWORK SCHEDULE IS PROVIDED FOR INFORMATION ONLY. ADDITIONAL MATERIAL REQUIRED FOR EMBANKMENT SHALL BE PROVIDED IN ACCORDANCE TO ARTICLE 204 OF THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION. THIS WORK WILL BE INCIDENTAL TO THE PCC SIDEWALK PAY ITEM AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

DRAINAGE REMOVAL

LOCATION - STATION	50104400	50105220	X5427602
	CONCRETE HEADWALL REMOVAL	PIPE CULVERT REMOVAL	REMOVE EXISTING FLARED END SECTION
	EACH	FOOT	EACH
WEST MAIN STREET			
758+70 (PEPSI)	1		
770+88		45	
771+00			1
PROJECT TOTAL	1	45	1

PAVEMENT MARKING REMOVAL

LOCATION	DESCRIPTION	78300202	COMMENTS
		PAVEMENT MARKING REMOVAL - WATER BLASTING	
		SQ FT	
WEST MAIN STREET INTERSECTIONS			
SOUTH HALFWAY ROAD	SE QUADRANT	24	LTL STOP BAR
SOUTH HALFWAY ROAD	SE QUADRANT	40	RTL STOP BAR
SOUTH HALFWAY ROAD	SE QUADRANT	61	DIAGONALS & OUTLINE
PROJECT TOTAL		125	

DISCIPLINE: PROFESSIONAL ENGINEERING CERTIFICATE OF AUTHORITY: 000159			
EXPIRATION DATE: DECEMBER 31, 2025			
STATE OF ILLINOIS PROFESSIONAL DESIGN FIRM LICENSE NO. 184000435-0014			
REVISIONS		© 2023 ALL RIGHTS RESERVED	
DATE	NO.	 410 NORTH COURT ST, MARION, ILLINOIS 622959 618-993-6411 FAX 618-993-6750 WWW.HORNERSHIFRIN.COM SCHEDULES VA/HALFWAY ROAD GREENWAY CITY OF MARION, ILLINOIS	
7/16/25			
Date 03/2025		DR. By PLD	CK'D By JVZ
Scale N/A		Job No.2320800	Sheet No. 7 of 55