

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		100% STATE					
				I000-2A					
20201006	GRADING AND SHAPING SHOULDERS	UNIT	104	104					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	5.5	5.5					
40600300	AGGREGATE (PRIME COAT)	TON	27	27					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	4	4					
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	733	733					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	22	22					
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	1094	1094					
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	241	241					
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	531	531					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3					
67100100	MOBILIZATION	L SUM	1	1					
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1					
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1					
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	942	942					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	11650	11650					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	4198	4198					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	11650	11650					
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4					
X4420454	CLASS D PATCHES, TYPE III, 4 INCH	SQ YD	230	230					
X4420456	CLASS D PATCHES, TYPE IV, 4 INCH	SQ YD	1454	1454					

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT							

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI 55: I-55 EAST FRONTAGE ROAD
SUMMARY OF QUANTITIES

PLOT DATE: 6/21/2007

6/21/2007 10:00:00 AM