CONTRACT NO. 62636

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	2003-071 RS	COOK	91	6
STA.		TO STA.		
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

URBAN
90% FED./10% STATE

	CODE NO	ITEM	UNIT	TOTAL QUANTITIES	NB ROADWAY I000	SB ROADWAY I000	DRAINAGE I000		BRIDGES X031-2A	
*	X0325816	CONDUIT IN TRENCH, P-DUCT, 1 1/4"	FOOT	1,000	1,000					
*	X0325823	WASH LUMINAIRES, LIGHT POLES	EACH	521	521					
*	X0325824	WASH LUMINAIRES, UNDERPASSES AND TUNNELS	EACH	52	52					
	X4063000	PRELIMINARY TEST STRIP (STONE MATRIX ASPHALT)	EACH	2	1	1				
	X4066580	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	TON	35986	18014	17972				
	X4066685	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, STONE MATRIX ASPHALT, N80	TON	29855	14945	14910				
	X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	12567	6291	6276				
	X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	0.5	0.5				
	X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	202	101	101				
	70106800	CHANGEABLE MESSAGE SIGN	CAL MO	46	23	23				
	X8850102	INDUCTION LOOP	FOOT	3,524	3,524					
	Z0006110	BRIDGE DECK MICROSILICA CONCRETE OVERLAY, 2 1/2"	SQ YD	770					770	
	Z0006204	BRIDGE DECK HYDRO-SCARIFICATION, 1/2"	SQ YD	770					770	
	~~Z0010900~~	~~COLD MILLING (SPECIAL)~~	~~FOOT~~	~~75,927~~	~~36851~~	~~39076~~				
	Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	5					5	
	Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	39					39	
	Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	560			560			
	Z0030280	IMPACT ATTENUATORS, TEMPORARY (SEVERE USE, NARROW), TEST LEVEL 3	EACH	2	1	1				
	Z0030360	IMPACT ATTENUATORS, RELOCATE (SEVERE USE), TEST LEVEL 3	EACH	2	1	1				
	Z0075315	TIE BARS 5/8"	EACH	1598	1380	218				
	63301210	REMOVE AND RE-ERECT STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	113	100	13				
*	63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	2	2					
*	63100169	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)	EACH	1		1				
	44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	47,569	23,596	23,973				
	X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	106,781	53,142	53,639				

* NP-100% STATE

PLOT DATE = 05/23/2007
FILE NAME = $FILE$
PLOT SCALE = $SCALE$
USER NAME = default

REVISIONS NAME	DATE

Rev.

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
F.A.I. 94 (I-94)

SCALE:
DATE JAN 2007
DRAWN BY DCS
CHECKED BY

Edens I 94 Resurfacing Project