STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION





INSTALLATION AND SETTING METHODS

"A" : Set bar splicer assembly by means of a template bolt. "B" : Set bar splicer assembly by nailing to wood forms or cementing to steel forms. (E) : Indicates epoxy coating,

Bar splicer assemblies shall be of an approved type and shall develop in tension at least 125 percent of the yield strength of the lapped reinforcement bars. Splicer rods shall be of minimum 60 ksi yield strength, threaded or coiled full length. All reinforcement bars shall be lapped and tied to the splicer rods or dowel bars. Bar splicer assemblies shall be epoxy coated according to the requirements for reinforcement bars.

Other systems of similar design may be submitted to the Engineer for approval. Approval shall be based on certified test results from an approved testing laboratory that the proposed bar splicer assembly satisfies the following requirements:

Minimum Capacity
(Tension in kips) = 1.25 x fy x A_t

(Tension III κιμο) Minimum *Pull-out Strength = 1.25 x fs_{allow} x A₁ 2 Where fy = Yield strength of lapped reinforcement bars in ksi.

 $A_1 = Tensile stress area of lapped reinforcement bars. * = 28 day concrete$

BAR SPLICER ASSEMBLIES						
0 0 1		Strength Requirements				
	Splicer Rod or Dowel Bar Length		Min. Pull-Out Strength kips - tension			
#4	1'-8''	14.7	5.9			
#5	2'-0''	23.0	9.2			
#6	2'-7''	33.1	13.3			
#7	3'-5''	45.1	18.0			
#8	4'-6''	58.9	23.6			
#9	5'-9''	75.0	30,0			
#10	7'-3''	95.0	38.0			
#11	9'-0''	117.4	46.8			

Bar splicer assemblies shall be according to Section 508 of the Standard Specifications, except as noted. The furnishing and installation of bar splicer assemblies will be measured and paid for at the contract unit price each for "BAR SPLICERS."



ROUTE NO.	SECTION	COUNTY	r	TOTAL SHEETS	SHEET NO.
FAI 90/94	•	COOF		344	235
FEO.ROAD DIST	.NO.	ILLIN0IS	PROJEC	r	

Sheet No. 8 of 8 Sheets

NOTES

fs_{allow} = Allowable tensile stress in lapped reinforcement bars in ksi (Service Load)

Assemblics equired			Location			
24	At	Stage	Construction	Line	in	Deck

	PIER NO. 7						
	BAR SPLICER ASSEMBLY DETAILS						
REVISI	ONS	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS	DRAWN BY DATE RLK 5/03 CHECKED BY DATE SDS 5/03				
2 3 4 5 6		FAI RTE 90/94 SB DAN RYAN EXPRESSWAY SN 016-1111 (SOUTHBOUND) SEC 2003-029 1 CODK COUNTY	PROJECT No.				
8 9 10		HOMER L CHASTAIN & ASSOCIATES CONSULTING ENGINEERS BI-TI-0060 FAX 32: -TI-0050	4222-3 SHEET NO.				