

CONCRETE FOUNDATIONS

DRILLED SHAFT CONCRETE FOUNDATIONS

NWARK

CHECKED 0S-A-1

1-7-05

MOUTE HO. TOTAL. No. SHEET NO. F.A.I. 0-6 55 ITS #1 SANGAHON SHEETS PEGLAGAG DISTLACT ILLINOLS PEGLAGS PAGE

GENERAL NOTES

DESIGN: AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires and Traffic Signals. ("AASHTO Specifications")

Contract #

CONSTRUCTION: Current (at time of letting) Illinois Department of Transportation Standard Specifications for Road and Bridge Construction, Supplemental Specifications and Special Provisions. ("Standard Specifications")

LOADING: 90 M.P.H. WIND VELOCITY

WIND LOADING: 30 p.s.f. normal to Sign Ponel Area and truss elements not behind sign

WALKWAY LOADING: Dead load plus 500 lbs. concentrated live load.

fy = 60,000 p.s.i, (reinforcement)

Cu. Yds. 26.0

Cu. Yds. 21.2

WELDING: All welds to be continuous unless otherwise shown. All welding to be done in accordance with current AWS DL1 and DL2 Structural Welding Codes (Steel and Aluminum) and the Standard Specificiations.

MATERIALS: Aluminum Alloys as shown throughout plans. All Structural Steel Pipe shall be ASTM A53 Grade B with a minimum yield of 35,000 p.s.i., or A500 Grade B or C with a minimum yield of 46,000 p.s.i. If A500 pipe is substituted for A53, then the outside diameter shall be as detailed and wall thickness greater than or equal to A53.

All Structural Steel Plates and Shapes shall conform to AASHTO M270 Gr. 36, Gr. 50 or

Gr. 50W*. Stainless steet for shims, sleeves and handhole covers shall be ASTM A240. Type 302 or 304, or another alloy sultable for exterior exposure and acceptable to the Engineer. The steel pipe and stiffening ribs at the base plate for the column shall have a minimum longitudinal Charpy V-Notch (CVN) energy of 15 lb.-ft. at 40° F. (Zane 2) before galvanizing.

FASTENERS FOR ALUMINUM TRUSSES: All bolts noted as "high strength" must satisfy the requirements of AASHTO MI64 (ASTM A325), or approved alternate, and must have matching lock nuts. Threaded studs for splices (if Members Interfere) must satisfy the requirements of ASTM A449, ASTM A193, Grade B7, or approved alternate, and must have matching lock nuts. Bolts and lock nuts not required to be high strength must satisfy the requirements of ASTM A307. All bolls and lock nuts must be hat dip galvanized per AASHTO M232. The lock nuts must have nylon or steel inserts. A stainless steel flat washer conforming to ASTM A240 Type 302 or 304, is required under both head and nut or under both nuts where threaded studs are used. High strength bolt installation shall conform to Article 505.04 (f) (2)d of the IDOT Standard Specifications for Road and Bridge Construction. Rotational capacity ("ROCAP") testing of boits will not be required.

U-BOLTS AND EYEBOLTS: U-Bolts and Eyebolts must be produced from ASTM A276 Type 304, 304L, 316 or 316L, Candition A, cold finished stainless steel, or an equivalent material acceptable to the Engineer. All nuts for U-Bolts and Eyebolts must be lock nuts equivalent to ASTM A307 with nylon or steel inserts and hot dip gaivanized per AASHTO M232. A stainless steel flat washer conforming to ASTM A240, Type 302 or 304, is required under each U-Boit and Eyebolt lock nut.

GALVANIZING: All Steel Grating, Plates, Shapes and Pipe shall be Hot Dip Galvanized after fabrication in accordance with AASHTO MILL. Painting is not permitted.

ANCHOR RODS: Shall conform to AASHTO M314 Gr. 36 or 55 with a minimum Charpy V-Notch (CVN) energy of 15 lb.-ft. at 40° F.

CONCRETE SURFACES: All concrete surfaces above an elevation 6" below the lowest final ground line at each foundation shall be cleaned and coated with Bridge Seat Sealer in accordance with the Standard Specifications.

REINFORCEMENT BARS: Reinforcement Bars designated (E) shall be epoxy coated in accordance with the Standard Specifications.

> OVERHEAD SIGN STRUCTURES GENERAL PLAN & ELEVATION ALUMINUM TRUSS & STEEL SUPPORTS

> > F.A.I. 55 (I-55) SECTION D-6 ITS #1 SANGAMON COUNTY

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

Top of WF(A-N)4x3.06 walkway

support and sign bracket

 $B \blacktriangleleft$

 $B \blacktriangleleft$

`	RGUTE HO.	BEETTON	EDIATY		YOTAL WISSAM	patr MG	Si
	F.A.J. 55	D-6 [75 *]	SAN	MOMA		47	
	PED, MBAG DIRY	EC. MBAG DIRY, MG. 7		PRE-NO PROJECTA			


Top of WF(A-N)4x3.06
walkway support only

Bracket and grating dimensions are naminal and will vary based on

actual DMS cabinet dimensions plus

manufacturer's mounting devices.

SHEET NO. __




WALKWAY AND HANDRAIL SKETCH

(Road plan beneath truss varies)

BRACKET TABLE

WF(A-N)4x3.06 ASTW B308, Alloy 6061-76			
Sign V	Number		
Greater Than	Less Than or Equal To	Brockets Required	
	10'-0"	2	
10'-0"	<i>16'-0''</i>	3	
<i>16'-0"</i>	22'-0"	4	
22'-0"	28'-0"	5	
28'-0"	34'-0"	6	

Walkway and Truss Grating width dimensions are nominal and may vary ±½" based on available standard widths.



TYPICAL FRONT ELEVATION

With handrail omitted for clarity. For Section B-B, see Base Sheet QS-A-10.

Notes: *Space walkway brackets WF(A-N)4x3.06 and sign brackets WF(A-N)4x3.06 for efficiency and within limits shown:

- f = 12" maximum, 4" minimum (End of sign to € of nearest bracket)
- g = 12" maximum, 4" minimum (End of walkway grating to \mathfrak{L} of nearest support bracket)
- n = 6'-0" maximum (€ to € sign and/or walkway support brackets, WF(A-N)4x1.79 or WF(A-N)4x3.06)
- **If walkway bracket at safety chain location is behind sign, add angle to bracket, see Alternate Safety Chain Attachment on Base Sheet OS-A-II.

For Details T and W. Section B-B and Grating Splice Details, see Base Sheet OS-A-10. For Details D, F, G and P and Handrail Splice Details, see Base Sheet OS-A-11.

DESIGNED		
CHECKEO		
DRAWN		
CHECKED	 ······································	j

OS-A-9-DMS

EXAMINED

PASSED

ENGINEER OF STRUCTURAL SERVICES

ENGINEER OF PARKEES AND STRUCTURES

NUMBER	REVISION	DATE
44864444		-
		-

SECTION A-A

Handrail and walkway shall span a minimum of three brackets between splices and/or gap joints. Place all sign and walkway brackets as close to panel points as practical.

Grating and handrail splices placed as needed.

Structure	Station	a	<i>b</i> .	G	Walkway Grating and	
Number					Handrail Lengths	
6S0841055R86.9	234+00	68'-3"	10'-9"	1'-0"	40'-9"	
6S0841055L107.0	202+54	71'-3"	10'-9"	1'-0"	37′-9"	

Truss grating to facilitate inspection shall run full length (center to center of support frames) $\pm 12^{\prime\prime}$ on overhead trusses. Cost of truss grating is included in "Overhead Sign Structure".

OVERHEAD SIGN STRUCTURES ALUMINUM WALKWAY DETAILS

F.A.I. 55 (I-55) SECTION D-6 ITS #1 SANGAMON COUNTY

