

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	100% STATE URBAN TOTAL QUANTITY	ST. CLAIR COUNTY											
				ROADWAY	BRIDGE REL. IL ROUTE 3	RET. WALL RAMPS	LIGHTING	CONSTRUCTION TYPE CODE							
				0001	0008	0040	0021								
60240324	INLETS, TYPE B, TYPE 20 FRAME AND GRATE	EACH	7	7											
60602800	CONCRETE GUTTER, TYPE B	FOOT	1,501	1,501											
X6063100	CONCRETE GUTTER TRANSITION (SPECIAL)	FOOT	66	66											
60605000	COMBINATION CONCRETE CURB AND GUTTER,TYPE B-6.24	FOOT	152	152											
60609000	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06 (SPECIAL)	FOOT	29	29											
60610800	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24 (SPECIAL)	FOOT	23	23											
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SO FT	4,528	4,528											
60620000	CONCRETE MEDIAN, TYPE SB-6.24	SO FT	60	60											
63200310	GUARDRAIL REMOVAL	FOOT	26	26											
66400305	CHAIN LINK FENCE, 6'	FOOT	198	198											
66402900	CHAIN LINK GATES, 6' X 6' SINGLE	EACH	1	1											
66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	6,240	6,240											
66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1											
66900530	SOIL DISPOSAL ANALYSIS	EACH	3	3											
67100100	MOBILIZATION	L SUM	1	1											
72000100	SIGN PANEL - TYPE 1	SO FT	4	4											
72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	2	2											
80300100	LOCATING UNDERGROUND CABLE	FOOT	50				50								
80400100	ELECTRIC SERVICE INSTALLATION	EACH	1				1								
81012700	CONDUIT IN TRENCH, 2 1/2" DIA., PVC	FOOT	150				150								
81018600	CONDUIT PUSHED, 2 1/2" DIA., GALVANIZED STEEL	FOOT	150				150								
81100300	CONDUIT ATTACHED TO STRUCTURE, 1" DIA., GALVANIZED STEEL	FOOT	285				285								
81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT	340				340								
81300550	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 12" X 6"	EACH	2				2								
81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	1				1								
81702420	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 8	FOOT	300				300								
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	205				205								
82107200	UNDERPASS LUMINAIRE, 100 WATT, HIGH PRESSURE SODIUM VAPOR	EACH	6				6								
82500310	LIGHTING CONTROLLER, POLE MOUNTED, 240VOLT, 60AMP	EACH	1				1								
83600300	LIGHT POLE FOUNDATION, 30" DIAMETER	FOOT	33				33								
X0324045	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE REMOVAL	EACH	1	1											
X0324775	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE MAINTENANCE	SO YD	1,588	1,588											
X0325155	REMOVE ABANDONED GAS MAIN	FOOT	172	172											

• DENOTES SPECIALTY ITEMS

REvised 7/22/11

FILE NAME = #FILE#	USER NAME = #USER#	DESIGNED - JB	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION				SUMMARY OF QUANTITIES 3				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN - JB	REVISED -	RELOCATED ILLINOIS ROUTE 3								998	82-2-1HVB-1	ST. CLAIR	345	6
TENG & ASSOCIATES, INC. ENGINEERS/ARCHITECTS/PLANNERS CHICAGO, ILLINOIS		CHECKED - ACL	REVISED -	SCALE: N.T.S.				SHEET NO. OF SHEETS STA. TO STA.				FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				CONTRACT NO. 76D05
PLOT DATE = #DATE#		DATE - 05/13/11	REVISED -													