

--D:\BCCONN-10-BORDER\LDON.._UBCCONN-99-MOTIF\LDON.._UBCCONN-10-MOTIF\LDON.._UBCCONN-10-SCHEDULE2.DGN
7-22-2011, 15:44:19 BONDHUJO \\\FS-004\AMVA\VALT.D-TRANS.07\2202\20068-00\1\CIVIL\CAO\99 ALL CONTRACTS\CONNSHEETS CONTRACT 10\UBCCONN-10-SHT-SCHEDULE2.DGN

TREE REMOVAL (OVER 15 UNITS DIAMETER)					TOTAL	32	UNIT
LOCATION	STA.	OFF	LT/RT	DIAMETER FEET	SUBTOTALS		
PR REL IL 3	1687+84	129.4	LT	16	16		
PR REL IL 3	1687+98	133.1	LT	16	16		

TREE REMOVAL, ACRES						TOTAL	3.5	ACRE
LOCATION	VERTEX I.D.#	STATION	OFFSET	LT / RT	AREA SQFT	SUBTOTALS		
PR REL IL 3	D1	1671+75	167	RT				
	D2	1677+55	129	RT				
	D3	1677+63	112	RT				
	D4	1677+67	155	LT				
	D5	1677+44	235	LT				
	D6	1677+26	243	LT				
	D7	1677+31	160	LT				
	D8	1675+74	160	LT				
	D9	1675+89	61	RT				
	D10	1671+99	109	RT	82,411	1.89		
PR REL IL 3	E1	1678+46	129	LT				
	E2	1678+39	56	LT				
	E3	1678+59	69	RT				
	E4	1679+50	63	RT				
	E5	1679+50	130	LT	20,214	0.46		
PR REL IL 3	E4	1679+50	63	RT				
	E5	1679+50	130	LT				
	E6	1679+90	60	RT				
	E7	1680+49	2	LT				
	E8	1681+06	130	LT	20,684	0.47		
PR REL IL 3	F1	1690+77	4	LT				
	F2	1691+10	6	LT				
	F3	1691+45	44	LT				
	F4	1692+84	63	LT				
	F5	1692+96	94	LT				
	F6	1692+97	134	LT				
	F7	1692+43	130	LT				
	F8	1691+72	86	LT				
	F9	1691+48	94	LT				
	F10	1691+01	79	LT				
	F11	1690+81	116	LT				
	F12	1690+66	110	LT	14,329	0.33		
PR REL IL 3	G1	1671+27	52	RT				
	G2	1671+70	81	RT				
	G3	1672+09	83	RT				
	G4	1672+01	118	LT				
	G5	1671+70	124	LT				
	G6	1671+63	169	LT				
	G7	1671+23	138	LT	16,906	0.39		

TRENCH BACKFILL					TOTAL	906	CU YD
LOCATION	STA.	OFF.	STA.	OFF.	SUBTOTALS		
PR RAMP A	23+70.0	18.0	RT	23+70.0	28.0	LT	10.6
PR RAMP A	23+70.0	28.0	LT	22+00.0	28.0	LT	76.3
PR RAMP A	22+00.0	17.4	RT	22+00.0	28.0	LT	8.0
PR RAMP A	22+01.4	56.5	LT	22+00.0	28.0	LT	7.5
PR RAMP A	22+00.0	28.0	LT	20+50.0	28.0	LT	224.0
PR RAMP A	20+50.0	6.0	RT	20+50.0	28.0	LT	5.2
PR RAMP A	20+50.0	28.0	LT	19+12.0	26.2	LT	110.7
PR RAMP A	19+12.0	6.0	RT	19+12.0	26.2	LT	3.5
PR RAMP A	19+12.0	26.2	LT	17+33.5	20.0	LT	47.7
PR RAMP A	17+33.5	20.0	LT	17+33.5	6.0	RT	3.7
PR RAMP A	17+33.5	6.0	RT	17+33.5	19.9	RT	1.0
PR RAMP B	51+30.0	6.0	RT	51+30.0	20.0	LT	4.3
PR RAMP B	51+30.0	20.0	LT	53+30.0	20.0	LT	143.9
PR RAMP B	53+30.0	6.0	RT	53+30.0	20.0	LT	2.8
PR RAMP B	53+30.0	20.0	LT	55+30.0	20.0	LT	64.4
PR RAMP B	55+30.0	6.0	RT	55+30.0	20.0	LT	3.3
PR RAMP B	55+29.4	36.5	LT	55+30.0	20.0	LT	4.0
PR RAMP B	55+30.0	20.0	LT	56+30.0	20.0	LT	99.8
PR RAMP B	56+30.0	20.0	LT	56+85.0	20.0	LT	55.3
PR RAMP B	56+85.0	20.0	LT	56+85.0	52.1	RT	30.3

POROUS GRANULAR BACKFILL					TOTAL	272	CU YD
LOCATION	DESCRIPTION	FROM STA.	TO STA.	LT/RT	SUBTOTALS		
I-70 RAMP A	AT RETAINING WALL BETWEEN BARRIER WALLS	170+00.00	176+50.00	RT	231		
		19+00.00	20+10.61	LT	41		

SEEDING, CLASS 3A						TOTAL	1.25	ACRE
LOCATION	FROM STA.	OFFSET	TO STA.	OFFSET	AREA (SF)	SUBTOTALS		
PR REL IL 3	1680+79.49	23.6	1680+85.86	131.9	2,721	0.06		
PR REL IL 3	1681+17.77	-55.6	1682+41.66	-516.8	5,641	0.13		
PR RAMP B	50+16.86	-44.7	53+50.00	-42.5	8,612	0.20		
PR RAMP B	53+50.00	-21.6	55+31.40	-37.1	3,624	0.08		
PR RAMP A	24+48.12	95.9	22+42.49	19.6	6,521	0.15		
PR RAMP A	21+52.62	13.3	20+00.00	7.6	496	0.01		
PR RAMP A	24+58.68	-39.6	20+10.86	-29.6	8,342	0.19		
PR RAMP A	20+00.00	28.8	16+50.00	0.0	13,785	0.32		

MULCH, METHOD 2						TOTAL	15.75	ACRE
LOCATION	FROM STA.	OFFSET	TO STA.	OFFSET	AREA (SF)	SUBTOTALS		
REL IL RTE 3	1671+03.00	122.1	LT	1677+90.70	64.6	RT	199,238	4.57
REL IL RTE 3	1678+29.71	51.6	LT	1679+50.00	127.0	LT	9,223	0.21
REL IL RTE 3	1678+34.62	67.0	RT	1679+50.00	23.6	RT	4,691	0.11
REL IL RTE 3	1679+50.00	51.6	LT	1681+00.93	126.9	LT	10,123	0.23
REL IL RTE 3	1679+50.00	60.0	RT	1680+20.89	23.58	RT	1,907	0.04
RAMP A	16+50.00	75.0	LT	20+00.00	28.9	RT	37,022	0.85
RAMP A	20+00.00	28.8	RT	24+59.08	118.7	RT	5,642	0.13
RAMP A	21+52.62	13.3	RT	20+00.00	7.58	RT	496	0.01
RAMP A	22+06.70	19.3	RT	24+48.10	95.9	RT	6,521	0.15
RAMP A	20+10.90	29.6	LT	24+57.70	39.7	LT	8,342	0.19
RAMP B	50+28.82	134.5	RT	53+50.00	7.6	RT	39,692	0.91
RAMP B	50+16.90	44.7	LT	53+50.00	42.5	LT	8,612	0.20
RAMP B	53+50.00	94.8	LT	59+00.62	140.08	RT	95,362	2.19
REL IL RTE 3	1683+11.10	506.4	LT	1685+65.90	164.0	RT	127,809	2.93
REL IL RTE 3	1685+91.70	162.0	LT	1689+55.40	117.0	RT	108,062	2.48
REL IL RTE 3	1690+70.80	117.0	LT	1692+89.50	86.7	LT	19,867	0.46

EROSION CONTROL BLANKET				TOTAL	76,230	SQ YD
		ACRES	"SY FOR CLASS 7 (SPECIAL) OR 3A SEEDING"	SUBTOTALS		
FROM SEEDING CLASS 7 (SPECIAL)		14.5	70,180	70,180		
FROM SEEDING CLASS 3A		1.25	6,050	6,050		

TEMPORARY EROSION CONTROL SEEDING				TOTAL	1,575	POUND
		AREA ACRE	APPLICATION RATE LBS/ACRE	SUBTOTALS		
AREA FROM 25100115 MULCH, METHOD 2		15.75	100	1,575		

TEMPORARY DITCH CHECKS					TOTAL	60	FOOT
LOCATION	STA.	OFF.			SUBTOTALS		
REL IL RTE 3	1673+50	129	LT		10		
REL IL RTE 3	1673+50	96.4	RT		10		
REL IL RTE 3	1675+50	141	LT		10		
REL IL RTE 3	1675+50	110	RT		10		
REL IL RTE 3	1686+75	119	LT		10		
REL IL RTE 3	1686+75	98	RT		10		

PERIMETER EROSION BARRIER						TOTAL	8,454	FOOT
LOCATION	FROM STA.	OFFSET	TO STA.	OFFSET	SUBTOTALS			
REL IL RTE 3	1671+21.2	138.4	LT	1677+90.7	64.6	RT	2,048	
REL IL RTE 3	1678+28.5	107.1	LT	1679+50.0	127.0	LT	162	
REL IL RTE 3	1678+29.2	77.1	LT	1679+50.0	60.0	RT	260	
REL IL RTE 3	1679+50.0	60.0	RT	1679+50.0	127.0	LT	409	
REL IL RTE 3	1680+82.5	18.6	RT	1682+41.7	516.8	LT	563	
REL IL RTE 3	1680+82.5	18.6	RT	1680+93.1	345.5	RT	339	
REL IL RTE 3	1683+73.9	500.5	RT	1684+66.7	164.3	LT	447	
REL IL RTE 3	1682+96.2	353.4	RT	1684+17.2	162.2	RT	287	
REL IL RTE 3	1685+18.1	163.4	LT	1689+59.7	5.32	LT	622	
REL IL RTE 3	1684+74.0	162.9	RT	1689+49.5	34.8	RT	567	
REL IL RTE 3	1690+70.8	117.0	LT	1692+89.5	86.7	LT	695	
RAMP A	20+00.0	28.8	RT	16+50.0	48.2	RT	367	
RAMP A	16+50.0	22.4	RT	19+96.5	104.4	LT	432	
RAMP B	53+50.0	108.4	RT	59+03.9	87.8	RT	607	
RAMP B	59+06.2	40.1	RT	53+50.0	94.8	LT	649	

STONE RIPRAP, CLASS A4				TOTAL	59	SQ YD
FILTER FABRIC				TOTAL	59	SQ YD
LOCATION	STA.	OFF.	AREA SQ FT	SUBTOTALS		
RAMP A	18+42	16	RT	150	16.7	
RAMP A RW	807+03	2	RT	66.5	7.4	
RAMP B	51+19	126	RT	221.7	24.6	
RAMP B	56+85	64	RT	96	10.7	

FILE NAME =		USER NAME = #USER#	DESIGNED - JB	REVISED 07/22/11 JB	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION RELOCATED ILLINOIS ROUTE 3	SCHEDULE OF QUANTITIES 2					F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILEL#			DRAWN - JFS	REVISED -							998	82-2-1HV8-1	ST. CLAIR	345	16
 TENG & ASSOCIATES, INC. ENGINEERS/ARCHITECTS/PLANNERS CHICAGO, ILLINOIS		PLOT SCALE = #SCALE#	CHECKED - JB	REVISED -		CONTRACT NO. 76D05									
		PLOT DATE = #DATE#	DATE - 05/13/11	REVISED -											
						SCALE: N.T.S.	SHEET NO. 2 OF 5	SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		