

\\DBCONN-10-SBORDERL.DGN, \\DBCONN-10-SCHEDULE.DGN, \\DBCONN-99-MOTIFL.DGN, \\DBCONN-10-MOTIFL.DGN, \\DBCONN-10-SHT-SCHEDULE3.DGN
7-22-2011, 15:44:27 \\FS-0044\AMVAULT\0-TRANS_07\2202\20668-00\CIVIL\CA0\99 ALL CONTRACTS\CONNSHEETS CONTRACT 10\DBCONN-10-SHT-SCHEDULE3.DGN

INLET FILTERS				TOTAL	22	EACH
LOCATION	STA.	OFF.	LT / RT	SUBTOTALS		
PR RAMP A	23+86.08	69	RT	1		
PR RAMP A	23+68.25	62	RT	1		
PR RAMP A	23+70.00	18	RT	1		
PR RAMP A	23+70.00	28	LT	1		
PR RAMP A	22+00.00	17	RT	1		
PR RAMP A	22+01.36	57	LT	1		
PR RAMP A	22+00.00	28	LT	1		
PR RAMP A	20+50.00	6	RT	1		
PR RAMP A	20+50.00	28	LT	1		
PR RAMP A	19+12.00	6	RT	1		
PR RAMP A	19+12.00	26	LT	1		
PR RAMP A	17+33.50	20	LT	1		
PR RAMP A	17+33.50	6	RT	1		
PR RAMP B	51+30.00	6	RT	1		
PR RAMP B	51+30.00	20	LT	1		
PR RAMP B	53+30.00	6	RT	1		
PR RAMP B	53+30.00	20	LT	1		
PR RAMP B	55+30.00	6	RT	1		
PR RAMP B	55+29.35	36	LT	1		
PR RAMP B	55+30.00	20	LT	1		
PR RAMP B	56+30.00	20	LT	1		
PR RAMP B	56+85.00	20	LT	1		

STABILIZED SUBBASE - HOT-MIX ASPHALT, 4"					TOTAL	4,292	SQ YD
LOCATION	DESCRIPTION	FROM STA.	TO STA.	LT/RT	SUBTOTALS		
RAMP A	PAVEMENT AREA	17+25.00	20+00.00		600		
RAMP A	1.5' STRIP	17+25.00	19+00.35	LT	29		
RAMP A	PAVEMENT AREA	20+00.00	25+14.68	LT & RT	2,161		
RAMP A	DEDUCT FOR 2' ANCHOR SLAB INSIDE LT EOP	19+00.00	24+51.77	LT	-122		
RAMP B	PAVEMENT AREA	50+00.00	53+50.00	LT & RT	854		
RAMP B	PAVEMENT AREA	53+50.00	58+14.00	LT & RT	825		
RAMP B	1.5' STRIP	55+37.85	58+14.00	RT	46		
RAMP B	1.5' STRIP	57+00.00	58+14.00	LT	19		
RAMP B	DEDUCT FOR 2' ANCHOR SLAB INSIDE LT EOP	50+24.10	57+00.00	LT	-151		
REL IL RTE 3	CB & GUTTER AREA	1618+49.07	1682+21.10	LT	31		

AGGREGATE BASE COURSE, TYPE B 4"						TOTAL	100	SQ YD
LOCATION	DESCRIPTION	FROM STA.	TO STA.	LT/RT	AREA (SF)	SUBTOTALS		
REL IL RTE 3	CENTER MEDIAN	1681+48.84	1682+21.10	LT	670	74.4		
RAMP A	CORNER ISLAND	24+50.69	24+67.10	RT	228	25.3		

PORTLAND CEMENT CONCRETE PAVEMENT 11" (JOINTED)					TOTAL	4,120	SQ YD
LOCATION	FROM STA.	TO STA.	SUBTOTALS				
RAMP A	17+25.00	20+00.00	571				
RAMP A	20+00.00	25+14.68	2,022				
RAMP B	50+00.00	53+50.00	781				
RAMP B	53+50.00	58+14.00	747				

PROTECTIVE COAT			TOTAL	7,717	SQ YD
			SUBTOTALS		
FROM ITEM 42000521 PORTLAND CEMENT CONCRETE PAVEMENT 11"(JOINTED)			4,120		
FROM ITEM 48300600 PORTLAND CEMENT CONCRETE SHOULDERS 11"			319		
FROM ITEM 60602800 CONCRETE GUTTER, TYPE B			2,627		
FROM ITEM 60603200 CONCRETE GUTTER TRANSITION (SPECIAL)			22		
FROM ITEM 60605000 COMB CC&G TYPE B-6.24			51		
FROM ITEM 60609000 COMB CC&G TYPE M-6.06 (SPECIAL)			34		
FROM TIME 60610800 COMB CC&G TYPE M-6.24 (SPECIAL)			21		
FROM ITEM 60618300 CONCRETE MEDIAN SURFACE, 4 INCH			503		
FROM ITEM 60620000 CONCRETE MEDIAN, TYPESB-6.24			7		
FROM ITEM 20002005 ATTENUATOR BASE			13		

PAVEMENT REMOVAL							TOTAL	827	SQ YD
LOCATION	STA.	OFF	RT / LT	TO STA.	TO OFF	SUBTOTALS			
PR REL IL 3	1687+71.90	100.29	LT	1689+96.95	89.21	LT	469		
PR REL IL 3	1687+76.11	32.36	LT	1690+00.35	27.26	LT	358		

AGGREGATE SHOULDERS, TYPE B 6"							TOTAL	120	SQ YD
LOCATION	FROM STA.	TO STA.	LT/RT	LENGTH	WIDTH	AREA (SF)	SUBTOTALS		
RAMP A	17+25.00	18+70.01	LT	149.0	2	298.0	33.1		
RAMP B	57+00.00	58+14.00	LT	14.0	2	228.0	25.3		
RAMP B	55+37.85	58+14.00	RT	276.2	2	552.3	61.4		

PORTLAND CEMENT CONCRETE SHOULDERS 11"						TOTAL	319	SQ YD
LOCATION	FROM STA.	TO STA.	LT/RT	SUBTOTALS				
RAMP A	17+25.00	19+00.43	LT			84.4		
RAMP B	57+00.00	58+14.00	LT			50.7		
RAMP B	55+37.85	58+14.00	RT			184.1		

STORM SEWER REMOVAL 6"					TOTAL	43	FOOT
LOCATION	FROM STA.	FROM OFF	TO STA	TO OFF	SUBTOTALS		
UNVERIFIED STORM SEWER, 6"							
REL IL RTE 3	1688+50	87 LT	1688+48	130 LT	43		

STORM SEWER REMOVAL 8"						TOTAL	311	FOOT
LOCATION	FROM STA.	FROM OFF	TO STA	TO OFF	SUBTOTALS			
UNVERIFIED STORM SEWER, 8"								
REL IL RTE 3	1688+76	23	LT	1689+62	31	LT	86	
REL IL RTE 3	1688+94	37	LT	1688+95	24	LT	13	
REL IL RTE 3	1689+13	44	LT	1689+15	27	LT	17	
REL IL RTE 3	1689+41	43	LT	1689+42	29	LT	14	
REL IL RTE 3	1689+60	48	LT	1689+62	31	LT	17	
REL IL RTE 3	1689+32	120	LT	1689+38	117	LT	6	
REL IL RTE 3	1689+38	117	LT	1689+96	111	LT	58	
REL IL RTE 3	1687+74	68	LT	1688+72	87	LT	100	

STORM SEWER REMOVAL 12"						TOTAL 214	FOOT
LOCATION	FROM STA.	FROM OFF	TO STA	TO OFF	SUBTOTALS		
UNVERIFIED STORM SEWER REMOVAL, 12							
REL IL RTE 3	1687+73	82 LT	1687+83	83 LT	10		
REL IL RTE 3	1687+77	139 LT	1687+83	83 LT	57		
REL IL RTE 3	1687+83	83 LT	1688+72	87 LT	89		
UNVERIFIED STORM SEWER REMOVAL, DIA. UNKNOWN							
REL IL RTE 3	1689+82	65 LT	1689+97	95 LT	33		
REL IL RTE 3	1688+57	67 LT	1688+72	87 LT	25		

STORM SEWER REMOVAL 15"					TOTAL	116	FOOT
LOCATION	FROM STA.	FROM OFF	TO STA	TO OFF	SUBTOTALS		
UNVERIFIED STORM SEWER, 15"							
REL IL RTE 3	1687+81	40 RT	1688+79	29 RT	116		

STORM SEWER REMOVAL 16"					TOTAL	183	FOOT
LOCATION	FROM STA.	FROM OFF	TO STA	TO OFF	SUBTOTALS		
UNVERIFIED STORM SEWER, 16"							
REL IL RTE 3	1687+81	40 RT	1688+79	29 RT	99		
REL IL RTE 3	1688+48	24 RT	1688+56	31 RT	11		
REL IL RTE 3	1688+79	29 RT	1689+01	27 RT	22		
REL IL RTE 3	1689+01	27 RT	1689+52	22 RT	51		

STORM SEWER REMOVAL 18"					TOTAL	172	FOOT
LOCATION	FROM STA.	FROM OFF	TO STA	TO OFF	SUBTOTALS		
VERIFIED STORM SEWER REL IL RTE 3	1687+80	23 RT	1689+50	12 RT	172		

CONCRETE HEADWALLS FOR PIPE DRAINS					TOTAL	10	EACH
LOCATION	STA.	OFF.	SUBTOTALS				
REL IL RTE 3	1674+25	84.7 RT			1		
REL IL RTE 3	1674+25	121.8 LT			1		
REL IL RTE 3	1675+06	93.9 RT			1		
REL IL RTE 3	1675+06	125.5 LT			1		
REL IL RTE 3	1675+88	99.9 RT			1		
REL IL RTE 3	1675+88	129.5 LT			1		
REL IL RTE 3	1676+69	97.4 RT			1		
REL IL RTE 3	1676+69	125.8 LT			1		
REL IL RTE 3	1677+50	89.5 RT			1		
REL IL RTE 3	1677+50	126.1 RT			1		

PIPE UNDERDRAINS 6"					TOTAL	150	FOOT
LOCATION	STA.	FROM OFF.	TO OFF.	SUBTOTALS			
REL IL RTE 3	1674+25	69.7 RT	84.7 RT		15		
REL IL RTE 3	1674+25	106.8 LT	121.8 LT		15		
REL IL RTE 3	1675+15	178.9 RT	93.9 RT		15		
REL IL RTE 3	1675+15	110.5 LT	125.5 LT		15		
REL IL RTE 3	1676+05	84.9 RT	99.9 RT		15		
REL IL RTE 3	1676+05	114.5 LT	129.5 LT		15		
REL IL RTE 3	1676+95	82.4 RT	97.4 RT		15		
REL IL RTE 3	1676+95	110.8 LT	125.8 LT		15		
REL IL RTE 3	1677+50	74.5 RT	89.5 RT		15		
REL IL RTE 3	1677+50	111.1 RT	126.1 RT		15		

FILE NAME =		USER NAME = #USER#	DESIGNED - JB	REVISED 07/22/11 JB	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION RELOCATED ILLINOIS ROUTE 3	SCHEDULE OF QUANTITIES 3					F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#			DRAWN - JFS	REVISED -							998	82-2-1HV8-1	ST. CLAIR	345	17
TENG TENG & ASSOCIATES, INC. ENGINEERS/ARCHITECTS/PLANNERS CHICAGO, ILLINOIS		PLOT SCALE = #SCALE#		CHECKED - JB		REVISED -	CONTRACT NO. 76D05								
		PLOT DATE = #DATE#		DATE - 05/13/11		REVISED -									
						SCALE: N.T.S.	SHEET NO. 3 OF 5	SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

