

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	100% STATE URBAN TOTAL QUANTITY	ST. CLAIR COUNTY											
				ROADWAY	BRIDGE REL. IL ROUTE 3	RET. WALL RAMPS	LIGHTING								
				0001	0008	0040	0021	CONSTRUCTION TYPE CODE							
X0325833	WICK DRAINS	FOOT	73,200	73,200											
X0326802	UTILITY STRUCTURE REMOVAL	EACH	15	15											
X0326807	CONCRETE BARRIER WALL (SPECIAL)	FOOT	1,142	1,142											
X0326936	CONTRACTOR DESIGNED GROUND IMPROVEMENT	L SUM	1	1											
X2010505	CLEARING, SPECIAL	L SUM	1	1											
X2020410	EARTH EXCAVATION (SPECIAL)	CU YD	5,000	5,000											
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	238		238										
X2501845	SEEDING, CLASS 7 (SPECIAL)	ACRE	14.50	14.50											
X4020700	AGGREGATE SURFACE COURSE, TYPE B 8"	SQ YD	2,152	2,152											
X5610704	WATER MAIN REMOVAL, 4"	FOOT	411	411											
X5610708	WATER MAIN REMOVAL, 8"	FOOT	263	263											
X5610710	WATER MAIN REMOVAL, 10"	FOOT	172	172											
X5610712	WATER MAIN REMOVAL, 12"	FOOT	912	912											
X6640300	CHAIN LINK FENCE REMOVAL	FOOT	670	670											
X6640525	CHAIN LINK FENCE, 4' ATTACHED TO STRUCTURE	FOOT	853			853									
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1											
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	7,037	7,037											
Z0002005	ATTENUATOR BASE	SQ YD	13	13											
Z0013300	CONCRETE REMOVAL (SPECIAL)	SQ YD	56	56											
Z0013796	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE	SQ YD	1,000	1,000											
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1											
Z0018002	DRAINAGE SCUPPERS, DS-11	EACH	11		11										
Z0030030	IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	1	1											
Z0034210	MECHANICALLY STABILIZED EARTH RETAINING WALL	SQ FT	21,501			21,501									
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	213		213										
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1											
Z0056100	SAND DRAINAGE BLANKET	CU YD	5,010	5,010											
Z0075496	CONCRETE RETAINING WALL REMOVAL	FOOT	10	10											
X0042 X0076602	TRAINEES ,SPECIAL	HOUR	5,000	5,000											
X5610717	WATER MAIN REMOVAL, 36" (SPECIAL)	FOOT	222	222											
81300915	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 20"x20"x8"	EACH	2												
* X6100510	ELECTRIC CABLE ASSEMBLY IN TRENCH, 600V (XLP-TYPE USE) 3-1/C NO. 8	FOOT	52				52								

• DENOTES SPECIALTY ITEMS

X0042

\\BCCON-10-BORDER\LDN...\\BCCON-10-500\LDN...\\BCCON-10-MOTIF\LDN...\\BCCON-10-LEGEND\LDN...\\BCCON-10-SHT-SUMMARY\LDN
5-12-2011, 12:35:06 NEWBRPD \\S\0044\DATA\PLT\0-TRANS\07\2282\228265-001\CIVIL\000\091 ALL CONTRACTS\CONNSHEETS\CONTRACT\10\BCCON-10-SHT-SUMMARY\LDN