SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES (URBAN)	CONSTRUCTION TYPE CODE: 100 % STATE 0005					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	107	107					
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	78	78					
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	132193	132193					
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	284	284					
*78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	261	261					
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	470	470					
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	107	107					
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	925	925					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	555	555					
X0322052	ASPHALT REJUVENATING AGENT	GALLON	13,248	13,248					
X2020110	GRADING AND SHAPING SHOULDERS	UNIT	851	851					
X4060110	BITUMINOUS MATERIALS (PRIME COAT)	POUND	88507	88507					

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES (URBAN)	CONSTRUCTION TYPE CODE: 100 % STATE 0005					
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	5	5					
Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	300	300					
Z0010619	HOT IN-PLACE RECYCLING	SQ YD	132,478	132,478					
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	1	1					
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4					

* SPECIALTY ITEMS

Rex.

FILE NAME =	USER NAME = Bateman	DESIGNED -	REVISED -
c:\pw_work\pwidot\bateman\d0351242\d10313-sht-plan.dgn		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 6/2/2014	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
852	(17&18) RS-6	WILL	33	4
		CONTRACT NO. 60W12		

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT