






Notes:

See sheet 12 of 31 for Detail A.
 Approach slab shall be paid for as Concrete Superstructure.
 Approach footing concrete shall be paid for as Concrete Structures.
 Reinforcement shall be paid for as Reinforcement Bars, Epoxy Coated.
 For v(E) bar details, see sheet 19 of 31.
 The approach footing maximum applied service bearing pressure (Qmax) = 2.0 ksf.
 For bar splicer details, see sheet 25 of 31.
 Cost of excavation for approach footing included with Concrete Structures.
 For Granular Backfill for Structures and drainage treatment details, see sheet 2 of 31.
 Cost of closed cell joint filler included with Concrete Superstructure.



* Tilt #9 b4(E) bars as required to maintain clearance.
 *** Cost included with Concrete Superstructure.



**TWO APPROACHES
 BILL OF MATERIAL**

Bar	No.	Size	Length	Shape	
a13(E)	36	#4	21'-9"	U	
a14(E)	36	#4	24'-2"	U	
a15(E)	14	#4	20'-4"	U	
a16(E)	14	#4	22'-9"	U	
a17(E)	66	#5	21'-6"	U	
a18(E)	66	#5	23'-11"	U	
a19(E)	24	#5	20'-4"	U	
a20(E)	24	#5	22'-9"	U	
b3(E)	60	#4	29'-8"	U	
b4(E)	172	#9	29'-9"	U	
b5(E)	8	#4	19'-7"	U	
b6(E)	8	#4	20'-6"	U	
t(E)	152	#4	11'-9"	U	
w(E)	80	#5	21'-6"	U	
w1(E)	80	#5	23'-11"	U	
Concrete Superstructure				Cu. Yd.	110.6
Concrete Structures				Cu. Yd.	28.6
Reinforcement Bars, Epoxy Coated				Pound	29,500

(Sheet 2 of 2)

PRINT DRIVER = L:\05-ESCA\B\11
 MAKE NAME = 09309-0219-13-Rev-01.dwg
 FILE NAME = 09309-0219-13-Rev-01.dwg



USER NAME = hos	DESIGNED - ELH 11/11	REVISED -
ESCA PROJECT NO. 933.14	CHECKED - RDP 01/14	REVISED -
PLOT SCALE = 0/2' = 1" / IN.	DRAWN - DWH 11/11	REVISED -
PLOT DATE = 6/10/2014 8:50:39 AM	CHECKED - ELH 11/11	REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

**BRIDGE APPROACH SLAB DETAILS
 STRUCTURE NO. 093-0025**

SHEET NO. 13 OF 31 SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332	(12,B2)B-1	WABASH	68	33
				CONTRACT NO. 74219
ILLINOIS FED. AID PROJECT				