



HOT-MIX ASPHALT MIXTURE REQUIREMENTS						
MIXTURE TYPE	AIR VOIDS	THICKNESS				
ROADWAY						
HMA SURFACE COURSE, MIX "C", N50 (IL-9.5 mm)	4% @ 50 GYR	2"				
HMA BINDER COURSE, IL-19.0, N50	4% @ 50 GYR	6"				
LEVELING BINDER (MACHINE METHOD), N50 (IL-9.5 mm)	4% @ 50 GYR	3/4"				
PAVEMENT PATCHING	1 4 . 4 . 4					
CLASS D PATCH (HMA BINDER IL-19 mm), 9 INCH	4% @ 70 GYR	9"				
HMA REPLACEMENT OVER PATCHES (HMA BINDER IL-19 mm)	4% @ 70 GYR	23/4"				
SHOULDER						
HMA SURFACE COURSE, MIX "C", N50 (IL-9.5 mm)	4% @ 50 GYR	2"				
HMA BINDER COURSE, IL-19.0, N50	4% @ 50 GYR	6"				
DRIVEWAY						
HMA SURFACE COURSE, MIX "C", N50 (IL-9.5 mm)	4% @ 50 GYR	2"				
HMA BASE COURSE (HMA BINDER IL-19 mm)	4% @ 50 GYR	4"				

NOTES:

THE UNIT WEIGHT USED TO CALCULATE ALL HMA SURFACE COURSE MIXTURES IS 112 LBS/SQ-YD/IN.

THE CONTRACTOR SHALL PATCH FIRST BEFORE MILLING

THE "AC TYPE" FOR POLYMERIZED HMA MIXES SHALL BE "SBS/SBR PG 70 -22" AND FOR NON-POLYMERIZED HMA THE "AC TYPE" SHALL BE "PG 64 -22" UNLESS MODIFIED BY DISTRICT ONE SPECIAL PROVISIONS. FOR "PERCENT OF RAP" SEE DISTRICT ONE SPECIAL PROVISIONS.

LEGEND

- 1) PAVEMENT REMOVAL
- (2) EXISTING HMA OVERLAY, 2"
- 3 EXISTING PCC PAVEMENT, 9-6-9
- 4) EXISTING STABILIZED BIT. BASE COURSE, VARIABLE DEPTH
- (5) EXISTING STABILIZED SHOULDER (B.A.M.)
- (6) EXISTING AGGREGATE SHOULDER
- 7) EXISTING STEEL PLATE BEAM GUARDRAIL TO BE REMOVED
- (8) EXISTING HEADWALL TO BE REMOVED
- 9) PROPOSED HMA SURFACE COURSE, MIX "C", N50, 2"
- 10) PROPOSED HMA BINDER COURSE, IL-19.0, N50, 6" (IN 3 LIFTS)
- 11) PROPOSED HMA SHOULDER, 8" (IN 3 LIFTS)
- (12) PROPOSED AGGREGATE SUBGRADE, 12"
- (13) PROPOSED STEEL PLATE BEAM GUARDRAIL, TYPE A (6 FOOT POST)

- (14) PROPOSED AGGREGATE SHOULDER, 6"
- (15) PROPOSED HEADWALL (PAID FOR AS CONCRETE BOX CULVERT)
- (16) HMA SURFACE REMOVAL, 2 3/4"
- (17) EARTH EXCAVATION
- 18 REMOVAL OF EXISTING STRUCTURES
- 19) STRUCTURE EXCAVATION
- (20) REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL
- (21) PROPOSED PRECAST CONCRETE BOX CULVERT 2-BARREL 8'X8'
- PROPOSED BITUMINOUS MATERIAL (PRIME COAT) & AGGREGATE (PRIME COAT)
- 23) PROPOSED POROUS GRANULAR EMBANKMENT, SUBGRADE
- 24) PROPOSED GRANULAR CULVERT BACKFILL
- (25) PROPOSED CA-7, 6"
- (26) LEVELING BINDER (MACHINE METHOD) N50, 34"

ı	IONO, INC.		DESIGNED	-	MJY	REVISED	-
			DRAWN		ST, TSC	REVISED	-
	CONSULTING ENGINEERS 1560 WALL ST. SUITE 222		CHECKED	-	MJY, SLV	REVISED	-
	NAPERVILLE, ILLINOIS 60563 PH: (630) 577-9100		DATE	-	06/25/2010	REVISED	av .
							

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

TYPICAL SECTIONS
WEST RIVER ROAD OVER UNNAMED TRIBUTARY (0.1 MI N OF IL RT 113)
SCALE: NONE SHEET NO. 3 OF 3 SHEETS STA. 81+40 TO STA. 84+20