

INDEX OF SHEETS

| | |
|---------|---|
| 1 | COVER SHEET |
| 2 | INDEX OF SHEETS, LIST OF STATE STANDARDS, SCOPE OF WORK AND GENERAL NOTES |
| 3 | SUMMARY OF QUANTITIES |
| 4 | TYPICAL SECTIONS AND DETAILS |
| 5 | ALIGNMENT, TIES AND PAVEMENT MARKINGS U.S. 45/52 |
| 6 | EXISTING CONDITIONS AND PROPOSED PLAN AND PROFILE U.S. 45/52 |
| 7 | CONSTRUCTION STAGING AND MAINTENANCE OF TRAFFIC NOTES AND DETAILS U.S. 45/52 |
| 8 | SUGGESTED TRAFFIC CONTROL AND STAGING PLAN U.S. 45/52 |
| 9 - 10 | TEMPORARY TRAFFIC SIGNAL PLANS |
| 11 | TEMPORARY LIGHTING PLAN U.S. 45/52 |
| 12 | TEMPORARY LIGHTING NOTES AND DETAILS U.S. 45/52 |
| 13 - 23 | STRUCTURAL DRAWINGS U.S. 45/52 OVER SMALL STREAM |
| 24 | TEMPORARY LIGHT POLE DETAILS (BE-800) |
| 25 | TEMPORARY AERIAL CABLE INSTALLATION (BE-801) |
| 26 | TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS (SNOW-PLOW RESISTANT) (TC-11) |
| 27 | DISTRICT ONE TYPICAL PAVEMENT MARKINGS (TC-13) |
| 28 | BUTT JOINT AND HMA TAPER DETAIL (BD-32) |
| 29 | STEEL PLATE BEAM GUARDRAIL ADJACENT TO CURB AND GUTTER AND STABILIZATION AT TBT TY 1 SPL. (BD-34) |

LIST OF STATE STANDARDS

| STANDARD NO. | DESCRIPTION |
|--------------|--|
| 000001-05 | STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS |
| 420401-06 | BRIDGE APPROACH PAVEMENT |
| 542301-01 | PRECAST REINFORCED CONCRETE FLARED END SECTION |
| 630001-07 | STEEL PLATE BEAM GUARDRAIL |
| 630301-04 | SHOULDER WIDENING FOR TYPE 1 (SPECIAL) GUARDRAIL |
| 631031-06 | TRAFFIC BARRIER TERMINAL, TYPE 6 |
| 635006-02 | REFLECTOR AND TERMINAL MARKER PLACEMENT |
| 635011-01 | REFLECTOR AND MARKER AND MOUNTING DETAILS |
| 701201-02 | LANE CLOSURE, 2L, 2W, DAY ONLY, FOR SPEEDS > 45 MPH |
| 701321-09 | LANE CLOSURE, 2L, 2W, BRIDGE REPAIR, WITH BARRIER |
| 701901 | TRAFFIC CONTROL DEVICES |
| 704001-04 | TEMPORARY CONCRETE BARRIER |
| 880001 | SPAN WIRE MOUNTED SIGNALS AND FLASHING BEACON INSTALLATION |

SCOPE OF WORK

THE SCOPE OF WORK FOR THIS PROJECT CONSISTS OF:

- INSTALLING TEMPORARY LIGHTING AND BRIDGE TRAFFIC SIGNALS.
- REMOVE EXISTING HMA BRIDGE DECK.
- REMOVE AND REPLACE BEAMS.
- PLACE CONCRETE WEARING SURFACE.
- REPLACE APPROACH SLABS.
- INSTALL NEW GUARDRAIL TERMINALS.

GENERAL NOTES

1. THESE PLANS HAVE BEEN PREPARED FROM NOTES RECEIVED FROM IDOT FIELD MAINTENANCE ENGINEERS.
2. PLAN DIMENSIONS AND DETAILS RELATIVE TO EXISTING PLANS ARE SUBJECT TO ROUTINE VARIATIONS. THE CONTRACTOR SHALL FIELD VERIFY EXISTING DIMENSIONS AND DETAILS AFFECTING NEW CONSTRUCTION AND MAKE NECESSARY APPROVED ADJUSTMENTS PRIOR TO CONSTRUCTION OR ORDERING MATERIALS. SUCH VARIATIONS SHALL NOT BE CAUSE FOR ADDITIONAL COMPENSATION FOR A CHANGE IN THE SCOPE OF THE WORK, HOWEVER, THE CONTRACTOR WILL BE PAID FOR THE QUANTITY ACTUALLY FURNISHED BASED UPON THE UNIT PRICE.
3. FORTY-EIGHT HOURS BEFORE STARTING EXCAVATION, THE CONTRACTOR WILL CALL J.U.L.I.E. (1-800-892-0123) OR 811 TO HAVE THE LOCATION OF EXISTING UTILITIES STAKED.
4. THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.
5. SAW CUTTING PRIOR TO ANY REMOVAL ITEMS NOTED ON THE PLANS OR DIRECTED BY THE ENGINEER SHALL BE CONSIDERED INCLUDED IN THE COST OF THE ITEMS BEING REMOVED.
6. DO NOT SCALE PLANS FOR CONSTRUCTION DIMENSIONS.
7. THE CONTRACTOR SHALL USE CARE IN REMOVING OR EXCAVATING NEAR ALL EXISTING ITEMS WHICH WILL REMAIN. ANY DAMAGE DONE TO EXISTING ITEMS BY THE CONTRACTOR SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE.
8. WHEN ARTIFICIAL LIGHTING IS UTILIZED IN NIGHT OPERATIONS, THE CONTRACTOR SHALL EXERCISE THE UTMOST PRECAUTIONS IN PREVENTING ADVERSE VISIBILITY TO THE MOTORING PUBLIC AS WELL AS ADJOINING RESIDENTIAL AREAS.
9. THE CONTRACTOR SHALL OBTAIN ALL NECESSARY PERMITS, AS REQUIRED, PRIOR TO COMMENCING WITH CONSTRUCTION.
10. THE CONTRACTOR SHALL TAKE ALL NECESSARY MEASURES TO ASSURE THAT NO DEBRIS FALLS IN THE CREEK. THE COST OF THIS WORK SHALL BE INCLUDED IN THE VARIOUS PAY ITEMS.
11. THE CONTRACTOR SHALL CONTACT THE TRAFFIC CONTROL SUPERVISOR AT (847) 705-4470 A MINIMUM OF 72 HOURS PRIOR TO THE PLACEMENT OF ANY TEMPORARY TRAFFIC CONTROL DEVICES.
12. THE CONTRACTOR SHALL CONTACT CORA MATHIS, THE AREA TRAFFIC FIELD ENGINEER, AT (815) 485-6475 TWO (2) WEEKS PRIOR TO THE PLACEMENT OF PERMANENT PAVEMENT MARKINGS.
13. ALL DAMAGE TO EXISTING PAVEMENT MARKINGS OUTSIDE THE REMOVAL LINE SHOWN ON THE PLANS SHALL BE REPLACED AT THE CONTRACTOR'S EXPENSE.
14. ALL DISTURBED AREAS SHALL BE COVERED WITH SEEDING, CLASS 2A AND EROSION CONTROL BLANKET. THE COST OF THE NITROGEN, PHOSPHORUS AND POTASSIUM FERTILIZER SHALL BE INCLUDED IN THE BID PRICE FOR SEEDING, CLASS 2A.
15. ON HIGHWAY STANDARD 420401 "BRIDGE APPROACH PAVEMENT", SUBBASE GRANULAR MATERIAL TYPE B SHALL BE USED IN LIEU OF THE TYPE A SHOWN ON THE STANDARD.

NOTE: BOXED ITEMS ARE INCIDENTAL.

FILE NAME = 60668 index.dgn
PLOT DATE = 7/7/2008



CHRISTIAN-ROGE & ASSOCIATES, INC.
ENGINEERS-PLANNERS-SURVEYORS
211 WEST WACKER DRIVE
CHICAGO, ILLINOIS 60606
PHONE: (312)372-2023 FAX: (312)372-5274

| | |
|---------------------|-----------|
| DESIGNED - S.J.P. | REVISED - |
| DRAWN - A.Y. | REVISED - |
| CHECKED - E.J.M. | REVISED - |
| DATE - JULY 7, 2008 | REVISED - |

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**INDEX OF SHEETS, LIST OF STATE STANDARDS, SCOPE OF WORK
AND GENERAL NOTES U.S. 45 / 52**

SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA.

| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEET SHEETS | SHEET NO. |
|---|------------|--------|--------------------|---------------------------|
| 330 | 17 B-1-I-1 | WILL | 29 | 2 |
| | | | | CONTRACT NO. 60668 |
| FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT | | | | |