

SUMMARY OF QUANTITIES

URBAN

CODE NO.	ITEMS	UNIT	TOTAL QUANTITY	90% FEDERAL - 10% STATE				
				I000-2A	J000-2A	Y031-1F	X271-2A	Y007
78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	2261	2261				
78008240	POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	FOOT	182	182				
78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	454	454				
78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	191	191				
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	322	322				
78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	8	8				
78200410	GUARDRAIL MARKERS, TYPE A	EACH	39	39				
78200500	BARRIER WALL MARKERS	EACH	6	6				
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	7	7				
80400100	ELECTRIC SERVICE INSTALLATION	EACH	1		1			
80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1		1			
81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	2829		2829			
81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	292		292			
81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	56		56			
81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	66		66			
81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	315		315			
81018700	CONDUIT PUSHED, 3" DIA., GALVANIZED STEEL	FOOT	1133		1133			
81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	578		578			
81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT	660		660			
81300550	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 12" X 6"	EACH	2		2			
81304600	JUNCTION BOX EMBEDDED IN STRUCTURE 18" X 12" X 6"	EACH	4		4			
81400100	HANDHOLE	EACH	18		18			
81400200	HEAVY-DUTY HANDHOLE	EACH	2		2			
81400300	DOUBLE HANDHOLE	EACH	2		2			
81701385	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE USE) 3-1/C 350MCM	FOOT	110		110			
81800320	AERIAL CABLE, 3-1/C NO. 4 WITH MESSENGER WIRE	FOOT	240		240			
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	19528		19528			
82102310	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 310 WATT	EACH	91		91			
82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	4		4			
83050810	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 15 FT. MAST ARM	EACH	86		86			
83057355	LIGHT POLE, WOOD, 60 FOOT, CLASS 4, WITH 15FT MAST ARM	EACH	4		4			
83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	830		830			
83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	84		84			
84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	4		4			
84200700	LIGHTING FOUNDATION REMOVAL	EACH	4		4			
84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	1		1			
85000400	MAINTENANCE OF TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1		1			
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1		1			
85700300	FULL-ACTUATED CONTROLLER AND TYPE V CABINET	EACH	1		1			

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57		WILL	303	9
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
990182) R-369-1B-1-BR-2	CONTRACT: 62253			

- SPECIALTY ITEM
- 50% OF THE AS-BUILT QUANTITY WILL BE CHARGED TO AQUA ILLINOIS (PRIVATE UTILITY BENEFIT). FUND CODE: Y060 (50% AQUA/50% STATE)
- † NON-PARTICIPATING ITEM
- †† NON-PARTICIPATING FOR RETROREFLECTIVE SIGN SHEETING ONLY - 100% STATE
- \* NON-PARTICIPATING ITEM - 100% MONEE FIRE PROTECTION DISTRICT. FUND CODE: Y031-3D

DESIGN FIRM REGISTRATION No. 184-000450  
**Clark Dietz** ENGINEERS  
 118 SOUTH CLINTON STREET SUITE 800  
 CHICAGO, IL 60661  
 PHONE : 312.648.9900 FAX : 312.648.0204

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 I-57 AT MANHATTAN - MONEE ROAD  
 SUMMARY OF QUANTITIES  
 6 OF 9  
 SCALE: VERT. NTS  
 HORIZ. NTS  
 DATE 8/1/2008  
 DRAWN BY KLM  
 CHECKED BY TMW

02231 0006.  
 6/10/2008

Rev.