

MODEL: GenNotesSh01 [Sheet]  
FILE NAME: c:\pwwork\pwwork\illinois.gov\_jacek.ejmont\illinois.gov\125-sh-gennote.dgn

INDEX OF SHEETS

1	COVERSHEET
2	INDEX OF SHEETS, STANDARDS, AND GENERAL NOTES
3 - 4	SUMMARY OF QUANTITIES
5	NORTH DUPAGE COUYNTY LOCATION MAP
6	NORTH KANE COUNTY LOCATION MAP
7	LAKE COUNTY COUNTY LOCATION MAP
8	MCHENRY COUNTY LOCATION MAP
9	NORTH COOK COUNTY LOCATION MAP
10	SOUTH COOK COUNTY LOCATION MAP
11	SOUTH KANE COUNTY LOCATION MAP
12	SOUTH DU PAGE COUNTY LOCATION MAP
13	WILL COUNTY LOCATION MAP
14	DETAIL OF THRIE-BEAM GUARDRAIL WITH MODIFIED OFFSET BLOCK
15	STEEL PLATE BEAM GUARDRAIL STEEL BLOCK-OUT DETAIL
16	CURB REMOVAL (PARTIAL) AND SHOULDER WIDENING FOR TRAFFIC BARRIER TERMINAL ,TYPE 1 SPECIAL
17	STEEL BRIDGE RAIL DETAIL
18	TYPICAL DETAIL TO ANCHOR STEEL PLATE BEAM GUARD RAIL ON CONCRETE (BM-02)
19	TYPICAL DETAIL FOR GUARDRAIL ANCHOR BLOCK REPAIR (BM-03)
20	TYPICAL DETAILS FOR STEEL PLATE BEAM GUARDRAIL ANCHORAGE REPAIR (BM-04)
21	DETAIL FOR CENTER LONGITUDINAL GUARDRAIL JOINT (BM-05)
22	DETAIL OF STEEL PLATE BEAM GUARDRAIL SPECIAL (BM-06)
23	DETAIL OF GUARDRAIL SUPPORT AND END ANCHORAGE (BM-07)
24 - 26	T6 TERMINAL FOR USE WITH 21" HIGH SPBGR (BM-22)
27	ENTRANCE AND EXIT RAMP CLOSURE DETAILS (TC-08)
28	TRAFFIC CONTROL DETAILS FOR FREEWAY SINGLE AND MULTI-LANE WEAVE TC-09)
29	TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS AND DRIVEWAYS (TC-10)
30	TRAFFIC CONTROL AND PROTECTION AT TURN BAYS (TC-14)
31	TRAFFIC CONTROL DETAIL FOR SHOULDER CLOSURE AND PARTIAL RAMP CLOSURES (TC-17)
32	SIGNING FOR FLAGGING OPERATIONS AT WORK ZONEOPENINGS (TC-18)

LIST OF STATE STANDARDS

630001 - 13	STEEL PLATE BEAM GUARDRAIL
630101 - 11	STRONG POST GUARDRAIL ATTACHED TO CULVERT
630301 - 09	SHOULDER WIDENING FOR TYPE 1 GUARDRAIL TERMINALS
631006 - 08	TRAFFIC BARRIER TERMINAL TYPE 1B
631011 - 10	TRAFFIC BARRIER TERMINAL TYPE 2
631026 - 06	TRAFFIC BARRIER TERMINAL TYPE 5
631031 - 18	TRAFFIC BARRIER TERMINAL TYPE 6
631046 - 04	TRAFFIC BARRIER TERMINAL TYPE 10
701006 - 05	OFF-RD OPERATIONS 2L 2W 15' TO 24" FROM PAVEMENT EDGE
701011 - 04	OFF-RD MOVING OPERATIONS 2L 2W DAY ONLY
701106 - 02	OFF-RD OPERATIONS, MULTILANE, MORE THAN 15' AWAY
701201 - 05	LANE CLOSURE, 2L 2W, DAY ONLY 45MPH OR MORE
701301 - 04	LANE CLOSURE, 2L 2W, SHORT TIME OPERATIONS
701311 - 03	LANE CLOSURE, 2L 2W, MOVING OPERATIONS DAY ONLY
701336 - 07	LANE CLOSURE, 2L 2W, WORK AREAS IN SERIES 45MPH OR MORE
701400 - 12	APPROACH TO LANE CLOSURE FREEWAY EXPRESSWAY
701401 - 13	LANE CLOSURE FREEWAY EXPRESSWAY
701411 - 09	LANE CLOSURE MULTILANE ENTRANCE OR EXIT RAMP 45MPH OR MORE
* 701421 - 08	LANE CLOSURE MULTILANE DAY OPERATIONS ONLY 45-55MPH
701426 - 09	LANE CLOSURE MULTILANE INTERMITTENT OR MOVING OPERATIONS 45MPH OR MORE
701427 - 05	LANE CLOSURE MULTILANE INTERMITTENT OR MOVING OPERATIONS 40MPH OR LESS
701428 - 01	TRAFFIC CONTROL SETUP REMOVAL FREEWAY EXPRESSWAY
701501 - 06	URBAN LANE CLOSURE, 2L 2W, UNDIVIDED
701502 - 09	URBAN LANE CLOSURE, 2L 2W WITH BIDIRECTIONAL LEFT TURN LANE
701601 - 09	URBAN LANE CLOSURE MULTILANE, 1W 2W WITH NONTRAVERSABLE MEDIAN
701606 - 10	URBAN SINGLE LANE CLOSURE MULTILANE, 2W WITH MOUNTABLE MEDIAN
701701 - 10	URBAN LANE CLOSURE MULTILANE INTERSECTION
701801 - 06	SIDEWALK, CORNER OR CROSSWALK CLOSURE
701901 - 10	TRAFFIC CONTROL DEVICES
720011 - 01	METAL POSTS FOR SIGNS MARKERS AND DELINEATORS
782006 - 01	GUARDRAIL AND BARRIER WALL REFLECTOR MOUNTING DETAILS

BLR23 - 4

701446 - 11

TRAFFIC BARRIER TERMINAL TYPE 1

TWO LANE CLOSURE FREEWAY EXPRESSWAY

REVISED SHEET 8/29/2025

GENERAL NOTES

- BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" AT (800) 892-0123 OR 811 OR "CUAN" AT (312) 744-700 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS UTILITIES. 48 HOUR NOTIFICATION IS REQUIRED.
- ALL WORK IS TO BE REPLACED IN KIND OR AS INDICATED ON THE CONTRACT QUANTITY SHEET. GUARDRAIL WORK WILL INCLUDE ALIGNMENT AS NECESSARY TO RESTORE THE RAIL TO THE ORIGINAL CONDITIONS.
- REMOVAL OF DAMAGED MATERIALS WILL INCLUDE DISMANTLING, LOADING, HAULING AND DISPOSAL. THE WORK SITE WILL BE LEFT IN A SAFE AND ORDERLY CONDITION.
- NO MATERIAL SHOULD BE LEFT ON OR NEAR THE ROADWAY DURING NON-WORKING HOURS.
- ANY NECESSARY TRAFFIC CONTROL WILL BE PROVIDED BY THE CONTRACTOR; APPROPRIATE STANDARDS ARE HEREWITH ATTACHED.
- THE LIMITS OF THE DAMAGED GUARDRAIL WILL BE MARKED WITH PAINT. THE REPLACEMENT PARTS AND THE QUANTITIES INDICATED ARE WITHIN THESE LIMITS AS MARKED.
- REMOVED GUARDRAIL THAT IS NOT REPLACED ON THE SAME DAY MUST BE DELINEATED WITH LIGHTED BARRICADES. NO LOCATIONS WILL BE LEFT WITHOUT EITHER LIGHTED BARRICADES OR RESTORED GUARDRAIL AT ANY TIME.
- GUARDRAIL MARKERS SHALL NOT BE ATTACHED TO TERMINAL SECTIONS.
- THE CONTRACTOR SHALL TELEPHONE THE IDOT BUREAU OF TRAFFIC OPERATIONS, ELECTRICAL MAINTENANCE SECTION AT 708-524-2145 TO REQUEST THE LOCATE FOR UNDERGROUND ELECTRICAL AND/OR FIBER CABLE PRIOR TO ANY DIGGING AS PER THE CONTRACT.
- REMOVAL OF EXISTING TERMINAL SECTIONS INCLUDED IN COST OF NEW TERMINAL SECTIONS
- THE CONTRACTOR SHALL SUBMIT ALL DAILY LANE, RAMP AND SHOULDER CLOSURES VIA WWW.IDOTLCS.COM AT LEAST 24 HOURS IN ADVANCE OF ALL DAILY LANE, AND RAMP AND SHOULDER CLOSURES. THE CONTRACTOR SHALL REQUEST AND GAIN THE APPROVAL FROM THE ILLINOIS DEPARTMENT OF TRANSPORTATION'S EXPRESSWAY TRAFFIC OPERATIONS ENGINEER AT (847) 705-4151 OR (847) 705-4155.
- THE CONTRACTOR SHALL CONTACT THE TRAFFIC CONTROL SUPERVISOR AT KALPANA.KANNAN-HOSADURGA@ILLINOIS.GOV A MINIMUM OF 72 HOURS IN ADVANCE OF BEGINNING WORK.

\* MOVING LANE CLOSURES NOT PERMITTED ON EXPRESSWAYS

REVISED SHEET 9/9/2025

	USER NAME = jacek.ejmont	DESIGNED -	REVISED - JE 8/29/2025	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX OF SHEETS, STANDARDS, AND GENERAL NOTES			F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -					**	2025-1083-GRR	*	32	2
	PLOT SCALE = 0.16666633' / in.	CHECKED -	REVISED -					CONTRACT NO. 62Y32				
	PLOT DATE = 8/29/2025	DATE -	REVISED -					SCALE:	SHEET OF 1 SHEETS	STA. TO STA.	ILLINOIS	FED. AID PROJECT

\*\*VARIOUS •

\*VARIOUS