

MODEL: SQQ [Sheet] - 1
FILE NAME: c:\pw_work\pwid\michael.l.crow@illinois.gov\0987717\0612324-sh-SQQ.dgn

				6-02047-0000
				NHPP FUNDING 90% FEDERAL 10% STATE
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	SN 086-0029
				0047
				RURAL
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	68	68
40800029	BITUMINOUS MATERIALS (TACK COAT)	POUND	31	31
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	10	10
50102400	CONCRETE REMOVAL	CU YD	5.1	5.1
50157300	PROTECTIVE SHIELD	SQ YD	267	267
50300225	CONCRETE STRUCTURES	CU YD	5.8	5.8
50300255	CONCRETE SUPERSTRUCTURE	CU YD	3.5	3.5
50300260	BRIDGE DECK GROOVING	SQ YD	702	702
50300300	PROTECTIVE COAT	SQ YD	767	767
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1,140	1,140
50800515	BAR SPLICERS	EACH	0	0
52000110	PREFORMED JOINT STRIP SEAL	FOOT	58	58
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1

* - INDICATES PAY ITEM REQUIRES A SPECIAL PROVISION



1 REVISED 9-5-2025

REV - MS

	USER NAME = Michael.L.Crow	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES FAI 72 (I-72)			F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -					72	(86-9HB2)BDR,BRR	SCOTT	15	3
		CHECKED -	REVISED -					CONTRACT NO. 72324				
	PLOT DATE = 6/27/2025	DATE -	REVISED -		SCALE:	SHEET 1	OF 2 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT		