


TYPICAL CROSS SECTION OF EXISTING ROADWAY
STA. 1+00 TO STA. 13+25



TYPICAL CROSS SECTION OF PROPOSED IMPROVEMENT
STA. 1+00 TO STA. 13+25

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
20100500	TREE REMOVAL, ACRES	ACRE	0.25
20200100	EARTH EXCAVATION	CU YD	75
20300100	CHANNEL EXCAVATION	CU YD	75
20400800	FURNISHED EXCAVATION	CU YD	6270
20700110	POROUS GRANULAR EMBANKMENT	TON	100
28100809	STONE DUMPED RIPRAP, CLASS A5	TON	590
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	488
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1
50200100	STRUCTURE EXCAVATION	CU YD	50
50300225	CONCRETE STRUCTURES	CU YD	34.6
50300255	CONCRETE SUPERSTRUCTURES	CU YD	81.8
50300260	BRIDGE DECK GROOVING	SQ YD	194
50300300	PROTECTIVE COAT	SQ YD	265
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1
50500505	STUD SHEAR CONNECTORS	EACH	1050
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	22,180
50900205	STEEL RAILING, TYPE S1	FOOT	129
51201600	FURNISHING STEEL PILES HP12X53	FOOT	360
51202305	DRIVING PILES	FOOT	360
51203600	TEST PILES STEEL HP12X53	EACH	1
51204650	PILE SHOES	EACH	10
51500100	NAME PLATES	EACH	1
52100520	ANCHOR BOLTS, 1"	EACH	20
54200220	PIPE CULVERTS, CLASS D, TYPE 1 15	FOOT	38
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	60
60146304	PIPE UNDERDRAINS FOR STRUCTURES, 4"	FOOT	130
67100100	MOBILIZATION	L SUM	1
72501000	TERMINAL MARKER - DIRECT APPLIED	EACH	4
X2501000	SEEDING, CLASS 2 (SPECIAL)	ACRE	0.9
X5080530	BAR TERMINATOR	EACH	380
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1

* SPECIALTY ITEM