



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

September 5, 2025

SUBJECT: FAS 962 (Country Club Road)
Section 23-00110-00-DR
Massac County
Contract No. 99745
Item 085
September 7, 2025 Letting
Addendum (A)

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

- 1. Revised the Schedule of Prices**
- 2. Revised Plan Sheets 1, 4, & 5**
- 3. Revised page 3 of the Special Provisions**

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

required soil prior to constructing the new box culvert and placement of any riprap. Suitable excavated material may be used on the roadway fill as directed by the Engineer. Unsuitable material removed from the channel shall be disposed of by the contractor.

The cost for completing the work as described above shall be included in the contract price per cubic yard of STRUCTURE EXCAVATION and no additional compensation will be allowed.

This work shall be incidental to the contract. It will cover all materials, labor, equipment, and any other items necessary to complete the work.

STONE DUMPED RIPRAP:

This item shall be in accordance with Section 281 of the "Standard Specifications for Road and Bridge Construction".

Article 281.02, Materials shall meet the requirements of Quality designation "A" and Gradation designation "RR4" as defined in Article 1005-01 of the above specifications.

Article 281.04, Delete the requirement for filter fabric and bedding stone.

Article 281.06, This work shall be measured in tons as specified in Article 311.08(b) of the Standard Specifications.

Article 281.07, Excavation required for the installation will not be paid for separately but shall be included in the contract unit price per square yard for STONE DUMPED RIPRAP, CLASS A4 of the class specified.

STEEL PLATE BEAM GUARDRAIL

This work shall consist of furnishing and installing Steel Plate Beam Guardrail according to section 630 and 631 of the Standard Specifications and the following:

The guardrail placed on Country Club Road will consist of installation on guardrail on the roadway approach and departure in both directions. It shall include all guardrail and hardware along with the applicable terminals sections that tie the railing to the bridge railing as well as the end terminal treatments.

This work as well as the additional installations shown in the plans will be paid for at the contract unit price per; Foot for STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS, ~~STEEL PLATE BEAM GUARDRAIL ATTACHED TO STRUCTURES~~, STEEL PLATE BEAM GUARDRAIL (SHORT RADIUS), and Each for TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL, TANGENT, GUARDRAIL REFLECTORS, TYPE B, and TERMINAL MARKER, DIRECT APPLIED with no additional compensation to be allowed for the above requirements.

INSERT: STRONG POST GUARDRAIL, ATTACHED TO CULVERT