



T38N



LOCATION 16: I-90/I-94 (DAN RYAN EXPRESSWAY), NB
 457' NORTH OF 67TH ST. OVERPASS IN THE LOCALS,
 RIGHT SIDE

BILL OF MATERIAL

ITEM	UNIT	QUANTITY
CONCRETE REMOVAL	Cu. Yds.	1.6
CONCRETE STRUCTURE	Cu. Yds.	1.7
TIE BARS	Each	13
SAW CUTS	Foot	19
PROTECTIVE COAT	Sq. Yds.	4.2



SECTION

**CITY OF CHICAGO
 LAKE TOWNSHIP
 COOK COUNTY**



FULL DEPTH REPAIR
 REPLACE 16' OF BARRIER WALL
 FOR MORE DETAILS, SEE SHEET #5


TRAFFIC DATA:

SPEED LIMIT: 55 MPH
 2012 ADT: 241700

Notes:

DISCONNECT AND RECONNECT EXISTING
 GUARDRAIL.

COST INCLUDED IN THE COST OF
 "CONCRETE STRUCTURE".



ELEVATION

FILE NAME =	USER NAME = SEYMORECP	DESIGNED -	REVISED -
et:\pw_work\p\pidot\seymorecp\d0348982\0189013-sh-t-plan.dgn		DRAWN -	REVISED -
Default	PLOT SCALE = 100.0000' / 1"	CHECKED -	REVISED -
	PLOT DATE = 7/11/2013	DATE -	REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

**LOCATION 16
 I-90/I-94 (DAN RYAN EXPRESSWAY)**

SCALE: SHEET OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2013-0411	VARIOUS	44	33
			CONTRACT NO. 60W86	
ILLINOIS FED. AID PROJECT				