

CONSTRUCTION CODE 0001 APPLIES TO 41ST DRIVE CONNECTOR

CONSTRUCTION CODE 0004 APPLIES TO 35TH STREET, 38TH STREET, 39TH STREET, PR 40TH AVENUE, EX 40TH AVENUE, 41ST AVENUE DRIVE, AND COALTOWN ROAD

STAGE	LOCATION	20200100	[1]	[1]	[2]	20201200	Z0054400
		EARTH EXCAVATION	EARTH EXCAVATION FOR EMBANKMENT ADJUSTED FOR SHRINKAGE (25%)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	ROCK FILL
		(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)
STAGE 1	COALTOWN ROAD STA 9+50 TO STA 16+50	1,061	796	83	713	0	0
STAGE 2	COALTOWN ROAD STA 9+50 TO STA 16+50	462	347	1,667	-1,320	0	0
	JOHN DEERE ROAD STA 265+32.49 TO STA 269+00	26	20	154	-134	0	0
STAGE 1 & 2	41 DRIVE CONNECTOR STA 520+50 TO STA 524+60	391	294	7,494	-7,200	12,654	8,482
	STA 526+15 TO STA 532+50	112	84	7,913	-7,829	20,897	14,337
	PROPOSED 40TH AVENUE STA 134+50 TO STA 134+75	532	399	1,876	-1,477	0	0
STAGE 1 & 2 SUBTOTAL		2,584	1,940	19,187	-17,247	33,551	22,819
STAGE 3A	PROPOSED 40TH AVENUE STA 131+35 TO STA 134+50	216	162	29	133	0	0
	41ST AVE DRIVE STA 193+50 TO STA 199+65.9	5,851	4,388	22	4,366	0	0
STAGE 3B	39TH STREET STA 140+50 TO STA 141+60	243	182	2	180	0	0
	PROPOSED 40TH AVENUE STA 131+35 TO STA 134+50	166	125	24	101	0	0
	41ST AVE DRIVE STA 185+50 TO STA 193+50	3,526	2,644	49	2,595	0	0
	41ST DRIVE CONNECTOR STA 532+50 TO STA 537+00	1,619	1,214	535	679	0	0
	EXISTING 40TH AVENUE STA 120+54 TO STA 124+50	1,206	905	3	902	0	0
STAGE 3 SUBTOTAL		12,827	9,620	664	8,956	0	0
STAGE 4	38TH STREET STA 149+45 TO STA 155+00	2,494	1,870	125	1,745	0	0
	41ST DRIVE CONNECTOR STA 539+00 TO STA 540+70	454	340	0	340	0	0
STAGE 4 SUBTOTAL		2,948	2,210	125	2,085	0	0
STAGE 5A	38TH STREET STA 155+00 TO STA 158+50	540	405	133	272	0	0
	41ST DRIVE CONNECTOR STA 539+00 TO STA 540+70	527	396	0	396	0	0
STAGE 5B	COALTOWN ROAD STA 16+50 TO STA 32+00	303	227	178	49	0	0
STAGE 5 SUBTOTAL		1,370	1,028	311	717	0	0
STAGE 6	COALTOWN ROAD STA 16+50 TO STA 32+00	23,173	17,380	22	17,358	0	0
	35TH STREET STA 5+50 TO STA 7+00	517	388	0	388	0	0
STAGE 6 SUBTOTAL		23,690	17,768	22	17,746	0	0
STAGE 7	COALTOWN ROAD STA 16+50 TO STA 32+00	7,413	5,560	684	4,876	0	0
	38TH STREET STA 160+61 TO STA 163+00	707	530	185	345	0	0
STAGE 7 SUBTOTAL		8,120	6,090	869	5,221	0	0
TOTAL		51,539	38,656	21,178	17,478	33,551	22,819

NOTES:

[1] PROVIDED FOR INFORMATION ONLY.

[2] 17,247 CY PAID FOR AS FURNISHED EXCAVATION AND 34,725 CY WASTE EXCAVATION (SUMMATION OF STAGES 3 - 7) INCLUDED IN COST OF EARTH EXCAVATION.

FILE NAME: c:\projects\080319108\contract\1\design\misc\sheets\026484-ant\Sched01.dgn



Ciorba Group, Inc.
CONSULTING ENGINEERS
5507 North Cumberland Avenue, Suite 402
Chicago, Illinois 60656
Tel. 773.776.4009 Fax 773.776.4014

USER NAME = espino	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 2.0000' / IN.	CHECKED -	REVISED -
PLOT DATE = 3/11/2013	DATE - 3/11/2013	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	(142-1)R & 142-1)B	ROCK ISLAND	507	35
CONTRACT NO. 64B84				
ILLINOIS FED. AID PROJECT				