

GENERAL NOTES

1. ALL ELEVATIONS REFER TO U.S.G.S. MEAN SEA LEVEL DATUM.
2. THE WORK IN THIS SECTION SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE PLANS, AS DIRECTED BY THE ENGINEER, IN ACCORDANCE WITH THE "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION" ADOPTED JANUARY 1, 2007; THE LATEST EDITION OF THE "SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS", AND THE SPECIAL PROVISIONS INCLUDED IN THE PROPOSAL FOR THIS PROJECT.
3. THE PROPOSED PROJECT IS LOCATED AT 3 SEPARATE LOCATIONS ON FAI ROUTES 57 AND 70 IN EFFINGHAM COUNTY, ILLINOIS.
4. THE WORK INCLUDED IN SECTION (25-4)BR CONSISTS OF BRIDGE REPAIR OPERATIONS AT THE 3 LOCATIONS AS SHOWN ON THE PLANS.
5. THE CONTRACTOR SHALL PROVIDE INTERNET ACCESSIBILITY TO THE HMA PLANT QUALITY CONTROL LAB SO THAT HMA PLANT REPORTS CAN BE E-MAILED TO THE DISTRICT HEADQUARTERS. THIS WORK SHALL BE INCLUDED IN THE COST OF THE HOT-MIX ASPHALT ITEMS.
6. WHERE SECTION OR SUBSECTION MONUMENTS ARE ENCOUNTERED, THE ENGINEER SHALL BE NOTIFIED BEFORE SUCH MONUMENTS ARE REMOVED. THE CONTRACTOR SHALL PROTECT AND CAREFULLY PRESERVE ALL MONUMENTS UNTIL AN AUTHORIZED SURVEYOR OR AGENT HAS WITNESSED OR OTHERWISE REFERENCED THEIR LOCATION. THE CONTRACTOR WILL BE RESPONSIBLE FOR HAVING AN AUTHORIZED SURVEYOR RE- ESTABLISH ANY SECTION OR SUBSECTION MONUMENTS DESTROYED BY HIS OPERATIONS.
7. ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE BE GIVEN TO ALL UTILITIES BEFORE DIGGING. FIELD MARKING OF FACILITIES MAY ALSO BE OBTAINED BY CALLING J.U.L.I.E. AND FOR NON-J.U.L.I.E. MEMBERS, THE UTILITY COMPANY DIRECTLY. AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS.

| | |
|------------------------|-----------------|
| *AMEREN / CIPS | GAS / ELECTRIC* |
| *ILLINOIS CONSOLIDATED | TELEPHONE |
| *CITY OF EFFINGHAM | WATER / SEWER |

(MEMBERS OF J.U.L.I.E. (800) 892-0123 ARE INDICATED BY * NON-J.U.L.I.E. MEMBERS MUST BE NOTIFIED INDIVIDUALLY.)
8. ANY FACILITIES OR APPURTENANCES WHICH ARE THE PROPERTY OF ANY PUBLIC UTILITY LOCATED WITHIN THE LIMITS OF CONSTRUCTION, SHALL BE RELOCATED OR ADJUSTED BY THEIR RESPECTIVE OWNERS. THE CONTRACTOR SHALL NOTIFY AND COOPERATE WITH THE OWNERS OF SUCH FACILITIES IN THEIR REMOVAL AND REARRANGEMENT OPERATIONS IN ORDER THAT THESE OPERATIONS AND THE CONSTRUCTION OF THIS PROJECT MAY PROGRESS IN A REASONABLE MANNER.
9. ALL CONFLICTING GROUND MOUNTED SIGNS AND SIGN SUPPORTS ARE TO BE REMOVED, COVERED OR RELOCATED AS DIRECTED BY THE ENGINEER. THIS WORK SHALL BE DONE IN ACCORDANCE WITH SECTIONS 724 OF THE STANDARD SPECIFICATIONS EXCEPT THAT IT WILL NOT BE MEASURED FOR PAYMENT BUT CONSIDERED AS INCLUDED IN THE VARIOUS ITEMS OF WORK. SIGNS SHALL BE STORED AS DIRECTED BY THE ENGINEER AND CAREFULLY PROTECTED BY THE CONTRACTOR.
10. FOR STABILIZATION, ALL TYPE III BARRICADES SHALL REQUIRE A MINIMUM OF FOUR SAND BAGS PER BARRICADE.
11. THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT PRIOR WRITTEN PERMISSION FROM THE DEPARTMENT.
12. IN ADDITION TO SURVEYS, SOME OF THE PLAN DIMENSIONS AND DETAILS RELATIVE TO THE EXISTING STRUCTURES HAVE BEEN TAKEN FROM EXISTING PLANS AND ARE SUBJECT TO NOMINAL CONSTRUCTION VARIATIONS. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY SUCH DIMENSIONS IN THE FIELD. SUCH VARIATIONS SHALL NOT BE CAUSE FOR ADDITIONAL COMPENSATION DUE TO A CHANGE IN THE SCOPE OF THE WORK. THE CONTRACTOR WILL BE PAID FOR THE QUANTITY ACTUALLY FURNISHED AT THE UNIT PRICE BID FOR THE WORK.
13. MAINTENANCE OF TRAFFIC AND STAGE CONSTRUCTION OPERATIONS FOR THIS CONSTRUCTION SECTION (SET 2 OF 2) ARE SUBJECT TO THE OVERALL SEQUENCE OF CONSTRUCTION FOR THE COMBINED SETS OF PLANS. (SEE SPECIAL PROVISIONS)

COMMITMENT - NONE

INDEX OF SHEETS

| | |
|-----------|---|
| 1660 | TITLE SHEET |
| 1661 | GENERAL NOTES, INDEX OF SHEETS AND STANDARDS |
| 1662 | SUMMARY OF QUANTITIES |
| 1663 | TYPICAL SECTIONS - EXISTING |
| 1664 | SCHEDULE OF QUANTITIES |
| 1665-1669 | HORIZONTAL CONTROLS & TIES |
| 1670-1672 | PLAN AND PROFILE |
| 1673 | GUARDRAIL DETAILS - LOCATION 5 |
| 1674-1676 | MAINTENANCE OF TRAFFIC AND STAGE CONSTRUCTION |
| 1677 | ROAD CLOSURE AND DETOUR PLANS - LOCATION 4 |
| 1678-1705 | BRIDGE REPAIR PLANS ROADWAY D SN 025-0002 |
| 1706-1740 | BRIDGE REPAIR PLANS RAMP F SN 025-0019 |
| 1741-1760 | BRIDGE REPAIR PLANS 1650th STREET SN 025-0062 |

IDOT HIGHWAY STANDARDS

| | |
|-----------|--|
| 630001-10 | STEEL PLATE BEAM GUARDRAIL |
| 630301-06 | SHOULDER WIDENING FOR TYPE 1 (SPECIAL) GUARDRAIL TERMINALS |
| 631032-08 | TRAFFIC BARRIER TERMINAL, TYPE 6A |
| 635006-03 | REFLECTOR AND TERMINAL MARKER PLACEMENT |
| 635011-02 | REFLECTOR MARKER AND MOUNTING DETAILS |
| 701001-02 | OFF-ROAD OPERATIONS, 2L, 2W, MORE THEN 15' (4.5 m) AWAY |
| 701006-04 | OFF-ROAD OPERATIONS, 2L, 5W, 15' (4.5 m) TO 24" (600 mm) FROM PAVEMENT EDGE |
| 701101-03 | OFF-ROAD OPERATIONS, MULTILINE, 15' (4.5 m) TO 24" (600 mm) FROM PAVEMENT EDGE |
| 701106-02 | OFF-ROAD OPERATIONS, MULTILINE, MORE THEN 15' (4.5 m) AWAY |
| 701201-04 | LANE CLOSURE, 2L, 2W, DAY ONLY, FOR SPEEDS > 45 MPH |
| 701301-04 | LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS |
| 701316-07 | LANE CLOSURE, 2L, 2W, BRIDGE REPAIR FOR SPEEDS > 45 MPH |
| 701400-06 | APPROACH TO LANE CLOSURE, FREEWAY/EXPRESSWAY |
| 701401-07 | LANE CLOSURE, FREEWAY/EXPRESSWAY |
| 701406-07 | LANE CLOSURE, FREEWAY/EXPRESSWAY, DAY OPERATIONS ONLY |
| 701901-02 | TRAFFIC CONTROL DEVICES |
| 000001-06 | STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS |
| 001001-02 | AREAS OF REINFORCEMENT BARS |
| 001006 | DECIMAL OF AN INCH AND OF A FOOT |