

| | | | | |
|---------------------|-----------|-----------|------------------|-----------|
| F.A.T. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 57/64 | (41-3)HBK | JEFFERSON | 518 | 063 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | | ILLINOIS | FED. AID PROJECT | |
| CONTRACT NO. 98963 | | | | |

| PIPE CULVERT & STORM SEWER REMOVAL - GRADE SEPARATION | | | | |
|---|----------------------------|-------------------------|-------------------------|-------|
| LOCATION | PIPE CULVERT REMOVAL | STORM SEWER REMOVAL 12" | STORM SEWER REMOVAL 15" | FOOT |
| | | | | FOOT |
| VETERANS MEMORIAL DRIVE | | | | |
| STA. 37+94.37 | 86.9' LT. | | | 20.0 |
| STA. 40+91.06 | 87.0' LT. | | | 31.0 |
| STA. 41+98.43 | 81.6' LT. | | | 31.0 |
| STA. 42+86.18 | 77.5' LT. | | | 31.0 |
| STA. 44+23.69 | 62.0 LT. | | | 25.0 |
| STA. 45+79.45 | 84.9' RT. | | | 30.0 |
| STA. 56+25.48 | 43.1' RT. | | | 51.0 |
| STA. 57+60.33 | 23.5' RT. | | | 30.0 |
| STA. 58+80.57 | 31.1' RT. | | | 30.0 |
| STA. 59+95.89 | 27.4 LT. | | | 8.0 |
| STA. 61+00.07 | 18.8' LT. | | | 32.0 |
| STA. 61+02.43 | 13.9' RT. | | | 32.0 |
| STA. 62+55.92 | 25.4' RT. | | | 8.0 |
| SUBTOTAL | | | | 359.0 |
| 45TH STREET | | | | |
| STA. 111+28.55 | 34.8' LT. | | | 60.0 |
| SUBTOTAL | | | | 60.0 |
| 42ND STREET | | | | |
| STA. 193+45.48 | 45' LT. TO STA. 193+67.89 | 5' LT. | | 45.0 |
| STA. 193+57.43 | 35' RT. TO STA. 193+68.28 | 5' RT. | | 41.0 |
| STA. 195+31.01 | 35' RT. TO STA. 195+32.52 | 75' RT. | | 40.0 |
| STA. 195+13.97 | 112' RT. TO STA. 195+32.46 | 75' RT. | | 41.0 |
| STA. 197+94.88 | 27' RT. TO STA. 198+15.79 | 35' RT. | | 22.0 |
| STA. 198+15.79 | 35' RT. TO STA. 198+48.14 | 63' RT. | | 42.0 |
| STA. 193+64.55 | 64' RT. TO STA. 193+57.33 | 35' RT. | | 28.0 |
| STA. 206+01.57 | 14' RT. TO STA. 206+02.49 | 14' LT. | | 39.0 |
| STA. 200+36.78 | 9' RT. TO STA. 200+40.60 | 11' RT. | | 2.0 |
| STA. 202+50.83 | 10' RT. TO STA. 202+54.83 | 10' LT. | | 4.0 |
| SUBTOTAL | | | | 4.0 |
| SUBTOTAL | | | | 261.0 |
| SUBTOTAL | | | | 39.0 |
| 42ND STREET | | | | |
| STA. 7+06.21 | 20' RT. TO STA. 7+25.27 | 19' RT. | | 20.0 |
| SUBTOTAL | | | | 20.0 |
| TOTAL | | | | 443 |
| TOTAL | | | | 261.0 |
| TOTAL | | | | 39.0 |
| USE TOTAL | | | | 443 |
| USE TOTAL | | | | 261 |
| USE TOTAL | | | | 39 |

| PLUG EXISTING STORM SEWERS SCHEDULE - GRADE SEPARATION | | | |
|--|----------------------------|----------------------------|-------|
| LOCATION | PLUG EXISTING STORM SEWERS | FILL EXISTING STORM SEWERS | FOOT |
| | | | CU YD |
| VETERANS MEMORIAL DRIVE | | | |
| STA. 48+44.39 | 62' LT TO STA. 50+79.69 | 48' LT | 1 |
| STA. 61+98.60 | 23' RT TO STA. 62+52.68 | 26' RT | 1 |
| STA. 62+52.68 | 26' RT TO STA. 62+54.10 | 15' LT | 1 |
| STA. 69+65.39 | 15' LT TO STA. 69+66.03 | 17' RT | 1 |
| STA. 72+65.32 | 15' LT TO STA. 72+65.57 | 17' RT | 1 |
| SUBTOTAL | | | 5 |
| SUBTOTAL | | | 39 |
| 42ND STREET | | | |
| STA. 198+48.47 | 24' LT TO STA. 200+43.64 | 23' RT | 1 |
| STA. 200+40.60 | 11' RT TO STA. 200+43.64 | 22' RT | 1 |
| STA. 200+40.60 | 11' RT TO STA. 201+48.84 | 4' RT. | 1 |
| STA. 201+48.84 | 4' RT. TO STA. 201+51.28 | 35' LT | 1 |
| STA. 201+48.84 | 4' RT. TO STA. 202+50.83 | 19' RT | 1 |
| STA. 202+54.83 | 4' RT. TO STA. 204+00.36 | 19' RT | 1 |
| SUBTOTAL | | | 6 |
| TOTAL | | | 11 |
| USE TOTAL | | | 11 |

** FILL EXISTING STORM SEWERS (CU YD) IS SHOWN FOR INFORMATION ONLY. THIS WORK IS NOT TO BE PAID FOR SEPARATELY BUT IS TO BE INCLUDED IN THE COST OF PLUG EXISTING STORM SEWERS. SEE SPECIAL PROVISIONS.

| CURB AND GUTTER REMOVAL SCHEDULE GRADE SEPARATION | | |
|---|-----------------------------------|--------|
| LOCATION | COMBINATION CURB & GUTTER REMOVAL | FOOT |
| | | FOOT |
| VETERANS MEMORIAL DRIVE | | |
| STA. 63+76.00 | TO STA. 76+40.34 | 2526.4 |
| SUBTOTAL | | 2527.6 |
| 42ND STREET | | |
| STA. 192+15.21 | TO STA. 199+56.00 | 2797.4 |
| STA. 201+80.00 | TO STA. 207+32.22 | 1104.6 |
| SUBTOTAL | | 3902.0 |
| 42ND STREET | | |
| STA. 113+51.19 | TO STA. 114+02.19 | 51.0 |
| SUBTOTAL | | 51.0 |
| TOTAL | | 6480.6 |
| USE TOTAL | | 6481 |

| SIDEWALK REMOVAL SCHEDULE GRADE SEPARATION | | |
|--|------------------|-------|
| LOCATION | SIDEWALK REMOVAL | |
| | SQ FT | |
| VETERANS MEMORIAL DRIVE | | |
| STA. 59+99.65 | TO STA. 60+04.61 | 201.2 |
| SUBTOTAL | | 201.2 |
| TOTAL | | 201.2 |
| USE TOTAL | | 201 |

Copyright Hanson Professional Services Inc. 2007
HANSON
 Hanson Professional Services Inc.

03/22/2007 05:35 PM
 A:\98\985\98520\98\road\sheet\c-605-sch\qgn

| | | |
|----------|-----|----------|
| LAYOUT | RLT | 02/26/04 |
| DRAWN | JED | 02/12/04 |
| REVIEWED | MTM | 03/22/07 |

| REVISIONS | |
|-----------|------|
| NAME | DATE |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
VETERANS MEMORIAL DRIVE INTERCHANGE
SECTION (41-3)HBK
 SCALE: NO SCALE DRAWN BY RLT
 DATE 3-22-07 CHECKED BY MTM