## SCHEDULE OF TRAFFIC SIGNAL REMOVAL ITEMS

пем	UNT	SHERIDAN ROAD AT LOYOLA AMENJE	SHERIDAN ROAD PEDESTRAN CROSSING AT CTA STATION		
SIGNAL HEAD, 3-SECTION*	EACH	9	9		
PEDESTRIAN SIGNAL HEAD*	EACH	6	2		
TRAFFIC SIGNAL POST*	EACH	1	О		
пантьать.	EACH	4	3		
TRAFFIC SIGNAL MAST ARM*	EACH	2	1		
TRAFFIC SIGNAL CONTROLLER*	EACH	О	1		

\* TRAFFIC CONTROL FIEWS TO BE REVIOUED AND REMAIN THE PROPERTY OF THE OTTY OF CHCAGO, CONTRACTOR SHALL DELIMER EQUIPMENT TO OTTY OF CHCAGO YARD AT 4100 S. CICERO AVE. AS DIRECTED BY THE ENGINEER

## SCHEDULE OF TRAFFIC SIGNAL ITEMS

ITEM	UNIT	QUANTITY
REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	L. SUM	1
MONUMENT FOUNDATION, TYPE A	EACH	2
FOUNDATION REMOVAL	SQ FT	364
TRENCH AND BACKFILL WITH SCREENINGS	FOOT	143
CONNECT TO EXISTING HANDHOLE VAULTS	EACH	6
CLEAN EXISTING MANHOLE/HANDHOLE (INCIDENTAL TO CONTRACT)	EACH	4
CONDUIT IN GROUND, 3" DIA., GALVANIZED STEEL	FOOT	143
ROD AND CLEAN DUCT IN EXISTING CONDUIT SYSTEM (INCIDENTAL TO CONTRACT)	FOOT	790
CONCRETE FOUNDATION FOR BASE MOUNTED "P" CABINET (PAID FOR AS CONCRETE FOUNDATION (SPECIAL))	EACH	. 1
CONCRETE FOUNDATION, 24"X9' WITH 1 1/4" A.R.	EACH	1
CONCRETE FOUNDATION, 30"X9' WITH 1 1/4" A.R.	EACH	2
CONCRETE FOUNDATION, 24" X 7' WITH 1 1/4" A.R.	EACH	2
POLE, STEEL, ANCHOR BASE, 10" D, 3 GAUGE, 34'-6"	EACH	1
POLE, STEEL, ANCHOR BASE, 11" D, 3 GAUGE, 34'-6"	EACH	2
POLE, STEEL, ANCHOR BASE, 10" D, 7 GAUGE, 34'-6"	EACH	2
ELECTRICAL CABLE IN CONDUIT, SIGNAL NO.4 2/C	FOOT	117
SIGNAL HEAD, POLYCARBONATE, LED, 3-SECTION, BRACKET MOUNTED	EACH	4
SIGNAL HEAD, POLYCARBONATE, LED, 3-SECTION, MAST ARM MOUNTED	EACH	5
PEDESTRIAN SIGNAL HEAD, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	8
MAST ARM, TRAFFIC, STEEL, MONOTUBE, 16 FOOT	EACH	1
MAST ARM, STEEL, MONOTUBE, 30 FOOT	EACH	2
ELECTRIC CABLE IN CONDUIT, #14 7/C	FOOT	615
ELECTRIC CABLE IN CONDUIT, #14 19/C	FOOT	679
CONTROLLER TRAFFIC, 12 LOAD BAY, "P" CABINET (PAID FOR CONTROLLER (SPECIAL))	EACH	1
TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1

FILE NAME =	DESIGNED - CCC	REVISED -
\onale ABC signed #1.ogn	DRAWN - TMB	REVISED -
USER NAME = tblank	CHECKED - JMM	REVISED -
PLOT DATE = 7/2/2012	DATE - 1/2/2012	REVISED -

STATI	E OI	LLINOIS
DEPARTMENT	OF	TRANSPORTATION

SIGNAL SCHEDULES		F.A.U. RTE.	SECTION	COUNTY	TOTAL	SHEET NO.		
				2865	10-B5159-00-TL	COOK	62	34
	<u>., </u>					CONTRAC	T NO.	63715
CALE:	NTS SHEET NO. 1 OF 3	SHEETS STA.	TO STA.		ILLINOIS FED.	AID PROJECT		