

STA	MAINLINE	DIRECTION	RT/LT	MUTCD CODE	DESCRIPTION	QTY
ADV	I-474	EB	Both	W9-3(0)-48	CENTER LANE CLOSED AHEAD	2
ADV	I-474	EB	Both	W16-3A(0)-3612	XX MILES	2
ADV	I-474	EB	Both	W20-1103(0)-48	ROAD CONSTRUCTION AHEAD	2
ADV	I-474	EB	Both	Work Zone Info Sign	WORK ZONE INFORMATION	2
ADV	I-74	EB	Both	W9-3(0)-48	CENTER LANE CLOSED AHEAD	2
ADV	I-74	EB	Both	W16-3A(0)-3612	XX MILES	2
ADV	I-74	EB	Both	W20-1103(0)-48	ROAD CONSTRUCTION AHEAD	2
ADV	I-74	EB	Both	Work Zone Info Sign	WORK ZONE INFORMATION	2
ADV	I-74	WB	RT	STD 701400-05	IDOT ADVANCED SIGNING STANDARD	1
459+30	I-74	WB	Both	G20-1103(0)-3660	END WORKZONE SPEED LIMIT	2
474+00	I-74	EB	Both	W9-3(0)-48	CENTER LANE CLOSED AHEAD	2
485+00	I-74	EB	Both	W9-3(0)-48	CENTER LANE CLOSED AHEAD	2
535+15	I-74	WB	RT	D9-1906(G)-4236	EXIT (ARROW) RIGHT	1
542+50	I-74	WB	RT	D4-1102(G)-3648	EXIT OPEN AHEAD	0
546+80	I-74	EB	RT	W4-1R(0)-48	MERGING TRAFFIC RIGHT SYMBOL	1
564+00	I-74	EB	Both	R2-1-3648	SPEED LIMIT XX	2
564+00	I-74	EB	Both	R2-1106-3618	\$375 FINE MINIMUM	2
564+00	I-74	EB	Both	W21-1113(0)-3612	BEGINS	2
564+00	I-74	EB	Both	W21-1115(0)-3618	WORK ZONE	2
565+00	I-74	WB	Both	R2-1-3648	SPEED LIMIT XX	2
565+00	I-74	WB	Both	R2-1106-3618	\$375 FINE MINIMUM	2
565+00	I-74	WB	Both	W21-1113(0)-3612	BEGINS	2
565+00	I-74	WB	Both	W21-1115(0)-3618	WORK ZONE	2
574+00	I-74	EB	RT	D4-1102(G)-3648	EXIT OPEN AHEAD	0
574+00	I-74	EB	RT	W13-1(0)-2424	ADVISORY SPEED (PLAQUE)	1
582+50	I-74	WB	RT	W4-1R(0)-48	MERGING TRAFFIC RIGHT SYMBOL	1
585+00	I-74	EB	RT	D4-1102(G)-3648	EXIT OPEN AHEAD	0
594+15	I-74	WB	RT	R1-2-48	YIELD	1
596+85	I-74	WB	RT	W4-1R(0)-48	MERGING TRAFFIC RIGHT SYMBOL	1
601+00	I-74	WB	Both	R2-1-3648	SPEED LIMIT XX	2
601+00	I-74	WB	Both	R2-1106-3618	\$375 FINE MINIMUM	2
601+00	I-74	WB	Both	W21-1113(0)-3612	BEGINS	2
601+00	I-74	WB	Both	W21-1115(0)-3618	WORK ZONE	2
608+00	I-74	EB	RT	W4-1R(0)-48	MERGING TRAFFIC RIGHT SYMBOL	1
611+73	I-74	EB	RT	R1-2-48	YIELD	1
618+00	I-74	EB	RT	R1-2-48	YIELD	1
624+00	I-74	WB	Both	W4-2R(0)-48	LANE ENDS RIGHT SYMBOL	2
625+00	I-74	EB	Both	G20-1103(0)-3660	END WORKZONE SPEED LIMIT	2
113+00	Ex Ramp A	WB	Both	W3-2(0)-48	YIELD AHEAD (ARROW)	2
209+50	Ex Ramp B	WB	LT	W20-7(0)-48	FLAGGER SYMBOL	1
204+50	Ex Ramp B	WB	RT	W5-4(0)-48	RAMP NARROWS	1
204+50	Ex Ramp B	WB	RT	W13-1(0)-2424	ADVISORY SPEED (PLAQUE)	1
412+50	Ex Ramp D	EB	LT	W3-2(0)-48	YIELD AHEAD (ARROW)	1
207+50	Ex Ramp E	NB	LT	W20-7(0)-48	FLAGGER SYMBOL	1
334+00	Ex Ramp F	EB	LT	W20-7(0)-48	FLAGGER SYMBOL	1
115+00	Ramp H	WB	RT	W20-7(0)-48	FLAGGER SYMBOL	1
110+00	Ramp H	WB	RT	W5-4(0)-48	RAMP NARROWS	1
110+00	Ramp H	WB	RT	W13-1(0)-2424	ADVISORY SPEED (PLAQUE)	1
105+00	Ramp H	WB	Both	W20-1103(0)-48	ROAD CONSTRUCTION AHEAD	2
ADV	I-155	NB	RT	STD 701400-05	IDOT ADVANCED SIGNING STANDARD	1
00+20	I-155	SB	RT	W5-4(0)-48	RAMP NARROWS	1
00+20	I-155	SB	RT	W13-1(0)-2424	ADVISORY SPEED (PLAQUE)	1
5+20	I-155	SB	RT	W20-7(0)-48	FLAGGER SYMBOL	1
15+00	I-155	SB	Both	W4-3L(0)-48	ADDED LANE RIGHT SYMBOL	2
23+00	I-155	NB	RT	W5-4(0)-48	RAMP NARROWS	1
23+00	I-155	NB	RT	W13-1(0)-2424	ADVISORY SPEED (PLAQUE)	1
25+00	I-155	SB	Both	G20-1103(0)-3660	END WORKZONE SPEED LIMIT	2
26+00	I-155	NB	Both	W20-1103(0)-48	ROAD CONSTRUCTION AHEAD	2

STA	MAINLINE	DIRECTION	RT/LT	MUTCD CODE	DESCRIPTION	QTY
43+00	I-155	NB	Both	R2-1-3648	SPEED LIMIT XX	1
43+00	I-155	NB	Both	R2-1106-3618	\$375 FINE MINIMUM	1
43+00	I-155	NB	Both	W21-1113(0)-3612	BEGINS	1
43+00	I-155	NB	Both	W21-1115(0)-3618	WORK ZONE	1
46+00	I-155	NB	RT	W4-3R(0)-48	ADDED LANE RIGHT SYMBOL	1
55+25	I-155	NB	Both	R2-1-3648	SPEED LIMIT XX	2
55+25	I-155	NB	Both	R2-1106-3618	\$375 FINE MINIMUM	2
55+25	I-155	NB	Both	W21-1113(0)-3612	BEGINS	2
55+25	I-155	NB	Both	W21-1115(0)-3618	WORK ZONE	2
404+00	Ex Ramp D Morton	EB	RT	W20-1905(0)-48	RAMP WORK AHEAD	1
405+00	Ex Ramp D Morton	EB	RT	W5-4(0)-48	RAMP NARROWS	1
505+50	Ex Ramp E Morton	WB	LT	W20-7(0)-48	FLAGGER SYMBOL	1
ADV	Alexander St.	EB	RT	M1-1-24	#N/A	1
ADV	Alexander St.	EB	RT	M3-4(0)-2412	#N/A	1
ADV	Alexander St.	EB	RT	W20-1103(0)-36	ROAD CONSTRUCTION AHEAD	1
ADV	Bond St.	EB	RT	W20-1103(0)-36	ROAD CONSTRUCTION AHEAD	1
ADV	Clark St.	EB	RT	W20-1103(0)-36	ROAD CONSTRUCTION AHEAD	1
22+00	Morton	NB	RT	W20-1103(0)-36	ROAD CONSTRUCTION AHEAD	1
24+00	Morton	NB	RT	W1-4bL(0)-36	2 LANES SHIFT LEFT (ARROWS)	1
26+00	Morton	NB	RT	W21-1A(0)-36	WORKERS SYMBOL	1
44+23	Morton	SB	RT	W5-4(0)-36	RAMP NARROWS	1
44+23	Morton	SB	RT	W13-1(0)-2424	ADVISORY SPEED (PLAQUE)	1
49+75	Morton	SB	RT	W13-4(0)-1818	ON RAMP	1
49+75	Morton	SB	RT	W20-1103(0)-36	ROAD CONSTRUCTION AHEAD	1
51+25	Morton	SB	RT	W21-1A(0)-36	WORKERS SYMBOL	1
55+25	Morton	SB	RT	W20-1103(0)-48	ROAD CONSTRUCTION AHEAD	1

**TEMPORARY SIGN SCHEDULE
(INCLUDED IN TRAFFIC CONTROL AND PROTECTION (SPECIAL))**

FILE NAME = D468620-sh1-s1gn01-00.dgn	DESIGNED - HTL DRAWN - KV	REVISED - REVISED -		STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	MAINTENANCE OF TRAFFIC PRE STAGE SIGN SCHEDULE	F.A.I. RTE. • 90-[14R(14HB-4,14,14HB)BR]	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
USER NAME = TERRA	CHECKED - DA/LVA	REVISED -				TAZEWELL	2433	82		
PLOT DATE = 7/16/2012	DATE - 7/20/2012	REVISED -				CONTRACT NO. 68620	ILLINOIS FED. AID PROJECT			