PAVEMENT SCHEDULE

LOCATION STATION	STATION TO	GRADING AND SHAPING SHOULDER	SUB-BASE GRANULAR MATERIAL, TYPE B 12"	AGGREGATE SHOULDERS, TYPE B	STRIP REFLECTIVE CRACK CONTROL TREATMENT	HMA SURFACE REMOVAL, 3 3/4"	PAVEMENT REMOVAL	HOT-MIX ASPHALT BASE COURSE, 10 1/4"	HOT-MIX ASPHALT SURFACE COURSE, MIX C, N90	HOT-MIX ASPHALT BINDER COURSE, N 90, IL-19.0 (2 1/4")	HOT-MIX ASPHALT BINDER COURSE, N 90, IL-19.0 (10 1/4")	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	TEMP RAMP	REMARKS
		UNIT	SQ YD	TON	FOOT	SQ YD	SQ YD	SQ YD	TONS	TONS	TONS	GAL	TON	SQ YD	
OLD US 51															
480+37	TO 485+15			17	956	1,275			108	164		229	3.8	13	
485+15	TO 486+00	0.9	44	3	170	198	28	35	19	29		50	0.8		
486+00	TO 486+90	0.9	137	3	180	120	120		20	31	73	76	1.3	13	
490+06	TO 493+37	6.6	344	12	662	662	221	276	75	113		233	3.9	27	
533+43	TO 536+50			11	614	819			69	105		147	2.5	27	
538+95	TO 546+52			26	1514	2,019			170	259		363	6.1	27	LEG "C"
551+51	TO 553+37	3.7	567	6	186		496		42	64	303	223	3.7		
IL 37															
4+67	TO 5+27	0.6	31	2	120	140	20	25	14	21		36	0.6	27	LEG "B"
19+36	TO 19+60	0.2	12	1	48	56	8	10	5	8		14	0.2	27	
												0			
9+18.4	TO 10+77.9			6	160	139			12	18		77	1.3	13	LEG "A"
SUB TOTALS										811	376				
TOTALS		13	1136	87	4610	5428	893	346	534	1187		1449	24	173	

PAVEMENT MARKING SCHEDULE

LOCATION STATION	STATION TO	THERMOPLASTIC PAVEMENT MARKINGS - LINE 24"	PAINT PAVEMENT MARKING - LINE 4"					REMARKS
		FOOT	FOOT					
			LT EOP SOLID	C/L SKIP DASH	C/L SKIP & SOLID	C/L DOUBLE SOLID	RT EOP SOLID	
			(WHITE)	(YELLOW)	(YELLOW)	(YELLOW)	(WHITE)	
OLD US 51								
480+37	TO 482+00		163		204		163	
482+00	TO 485+15		315	79			315	
485+15	TO 486+00		85	21			85	
486+00	TO 486+90		90	23			90	
490+06	TO 493+37		331	83			331	
533+43	TO 536+50		307			614	307	
538+95	TO 546+52		600			1,280	757	LEG "C"
540+70		12						
551+51	TO 553+37		186		233		186	
IL 37								
4+67	TO 5+27		60			120	60	LEG "B"
19+36	TO 19+60		24			48	24	
9+18.4	TO 10+77.9		160			319		LEG "A"
			2321	205	436	2381	2318	
TOTALS		12	7661					

FILE NAME = c:\pw_work\pwidot\greenleosm\d0312786\s-tb-typ_sch_ties.dgn	USER NAME = greenleosm	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
$MODEL$NAME$	PLOT DATE = 7/17/2012	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULES

SCALE: | SHEET OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR	09 BIT RES AND PATCH 2013-3	PULASKI	10	5

CONTRACT NO. 78329

ILLINOIS FED. AID PROJECT