CONTRACT NO. 98948

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	✳	WILLIAMSON	55	41

STA. _____ TO STA. _____
FED. ROAD DIST. NO. ___ | ILLINOIS FED. AID PROJECT

✳ [X1-(4,4-1,5,6,6-2)] R-1

TO JOHNSTON CITY
SEE SHEET 42
FOR ADDITIONAL
SIGNING

TO JOHNSTON CITY
SEE SHEET 42
FOR ADDITIONAL
SIGNING

NOT TO SCALE
N

37

Marion

VETERANS
ADMINISTRATION
HOSPITAL

MARION
MEMORIAL
HOSPITAL

PROPOSED SIGN KEY

3 — PROPOSED SIGN
A — EXISTING SIGN

PLACE PROPOSED SIGN WITHIN 200' OF THE EXISTING SIGN IN
RURAL AREAS. FOR PROPOSED SIGNS IN CITY LIMITS, THE
SIGNS SHALL BE PLACED SO THEY DO NOT INTERFERE WITH
EXISTING SIGNS AND AS DIRECTED BY THE ENGINEER. SIGNS
SHALL NOT BE PLACED ON EXISTING POSTS WITH EXISTING SIGNS.

EXISTING SIGN KEY

A   STATE ROUTE SIGN
B   MILEAGE SIGN
C   SPEED LIMIT SIGN
D   DIRECTIONAL STATE ROUTE SIGN
E   CROSS ROAD SIGN
F   I-57 DIRECTIONAL SIGN
G   NO PARKING SIGN
H   SOUTHERN BRANCH - LINCOLN HERITAGE TRAIL SIGN

NOTES:

1. THE CONTRACTOR HAS THE OPTION OF USING METAL POSTS
    INSTEAD OF WOOD.

2. ALL SIGNS SHALL BE BLACK ON ORANGE. THE POSTS SHALL
    BE PLACED 12 FEET FROM THE EDGE OF PAVEMENT AS
    DIRECTED BY THE ENGINEER.

3. ALL SIGN HARDWARE REQUIRED TO INSTALL THE ALTERNATE
    ROUTE SIGNING SHALL BE INCLUDED IN COST OF
    SIGN PANEL TYPE 1.

4. SIGNS SHALL BE REMOVED ON COMPLETION OF THE
    CONTRACT AT THE DIRECTION OF THE ENGINEER. THIS
    WORK SHALL BE COMPLETED ACCORDING TO SECTION 724
    OF THE STANDARD SPECIFICATIONS. THIS WORK WILL
    NOT BE PAID FOR. THE SIGNS AND POSTS SHALL BECOME
    THE PROPERTY OF IDOT. △

5. ALTERNATE A = ILL. RTE. 37

6. THE RELOCATING, MAINTENANCE OR REPLACEMENT OF SIGNS
    SHALL BE PAID FOR IN ACCORDANCE WITH ARTICLE 109.04.

7. EXACT SIGN PLACEMENT WILL BE DETERMINED BY THE ENGINEER.

8. THE DISTRICT 9 OPERATIONS ENGINEER SHALL BE CONTACTED
    10 DAYS PRIOR TO THE ERECTION OF SIGNS.

△ REV, 9-5-06

ALTERNATE ROUTE SIGNING – ALTERNATE A
IL 37 – MARION