


ROUTE NO.	SECTION	COUNTY		TOTAL SHEETS	SHEET
F.A.S. 888	00-00065 -00-BR	GALL	ATIN	22	14
FED. ROAD DIST. NO.		ILLINGIS	FED. ALD PROJECT-		

CONTRACT NO. 99232






NOTCH BEAM DETAIL AT EXPANSION END




EXPANSION ABUTMENT DETAIL

€ Brg. -

© 50°F



EXPANSION END ELEVATION (At Abutments)



Note: Space reinforcement bars to miss dowel rod holes.

1'4" x 1'-6" Dowel Rods

After beams are in place drill 134'% holes in cap and grout dowel rods in cap. Do not grout slotted hole at expansion end of beams.

Slotted hole shall be covered before concrete for expansion joint is placed.



BARS E & EI

BILL OF MATERIAL

BAR	NO.	SIZE	LENGTH	SHAPE
a(E)	6	#5	29'-8"	
Reinf. Bai	s, Epoxy	Coated	Pound	185
	Expansion	Foot	60	
Concrete Superstructure			Cu. Yd.	1.6

grouted and cured.

A Division of Hampton, Lenzini and Renwick, Inc. Cīvīi & Structural Engineers 801S. Durkin Drive Springfield, Illinois 62704 217-546-3400

See Sheet 15 for Neoprene Expansion Joint details.

Notes: Joint openings shall be adjusted according to Article 503.10(c) of the Standard Specifications when the deck is poured at an ambient temperature other than 50° F.

Concrete Superstructures shall be poured after shear keys are

Account Number 12-38-0003-1 Date: 05/26/05

P.O. Box 1036 DuQuoin, Illinois 62832 618-790-4637 SIGNED: T.P.L. CHECKED: S.W.M. DRAWN: D.B. SUPERSTRUCTURE DETAILS SECTION 00-00065-00-BR F.A.S. 888 / C.H. II GALLATIN COUNTY

STR. NO. 030-3116 / STATION 10+00