

TREE REMOVAL (6 TO 15 UNITS DIAMETER)		
STATION	OFFSET	UNITS
11+27	15L	8
10+13	13L	8 10
10+27	17L	7
10+50	20L	6
10+74	17L	7
11+81	1R	10
11+99	64L	8
12+00	73L	12
12+01	69L	9
12+14	93L	6
12+28	6L	6
12+35	3R	10
13+58	100L	12
13+54	104L	12
13+56	107L	12
13+54	107L	12
14+47	15R	6
15+12	9R	7
15+38	11R	7
15+54	14R	8
15+80	12R	7
26+57	24L	9
26+61	27L	7
26+73	22L	11
26+74	18L	10
26+86	16L	9
26+86	20L	7
26+94	40L	7
27+05	29L	6
27+23	25L	9
27+32	21L	8
27+04	17L	7
27+04	13L	9
27+10	11L	13
27+46	7R	6
27+71	7L	9
27+60	13R	7
26+66	39L	12
28+20	15L	9
MORRIS POND		81
TOTAL:		426

TREE REMOVAL (OVER 15 UNITS DIAMETER)		
STATION	OFFSET	UNITS
13+73	14L	25
24+56	71L	37
30+52	13R	18
31+21	13R	18
MORRIS POND		105
TOTAL:		203

TREE REMOVAL, ACRES			
STATION		OFFSET	QUANTITY (ACRES)
FROM	TO		
15+50	21+00		2.1
21+00	24+48		0.7
25+33	26+50		0.2
TOTAL:			3.0

REMOVING CATCH BASIN			
LOCATION STATION	OFFSET	QUANTITY (FOOT)	QUANTITY (EACH)
14+10	135' LT		1
TOTAL:			1

REMOVE EXISTING FLARED END SECTION			
LOCATION STATION	OFFSET	QUANTITY (FOOT)	QUANTITY (EACH)
13+60	86' LT		1
13+60	50' LT		1
TOTAL:			2

PAVEMENT REMOVAL			
LOCATION STATION	OFFSET	QUANTITY (SFT)	QUANTITY (SYD)
11+50 - 13+50	0'-70' LT	3,393	377
TOTAL:			377

STORM SEWER REMOVAL, 12"			
LOCATION STATION	OFFSET	QUANTITY (FOOT)	QUANTITY (EACH)
13+66	50' LT	33.0	
TOTAL:			33.0

RUSTIC FENCE REMOVAL			
LOCATION STATION	OFFSET	QUANTITY (FOOT)	QUANTITY (EACH)
14+37	88' LT	72	
TOTAL:			72

SIDEWALK REMOVAL				
LOCATION STATION-STATION	LENGTH	WIDTH	AREA	QUANTITY (SQ.FT)
GRACE STREET				
201+43 TO 202+43/L	100	5	500	500
201+43 TO 202+43/L	35	5	175	175
FINLEY ROAD POND	21	5	105	105
TOTAL:				780

COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.12 REMOVAL		
LOCATION STATION-STATION	LENGTH	QUANTITY (FOOT)
GRACE STREET		
201+90 TO 202+20/L	30	30
201+90 TO 202+20/R	30	30
FINLEY ROAD POND	30	30
TOTAL:		90