


# SUMMARY OF QUANTITIES

CONF NO.	ITEM	UNIT	TOTAL QUANTITY	90% FED/ 10% STATE	90% FED/ 10% STATE	90% FED/ 10% STATE								
				URBAN	MAINLINE ROADWAY 0004	STRUCTURE SN057-0249 0011	STRUCTURE SN057-0250 0011							
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	2,394	2,394										
44004250	PAVED SHOULDER REMOVAL	SQ YD	207	207										
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	2,422	2,422										
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	112	112										
48203100	HOT-MIX ASPHALT SHOULDERS	TON	1,245	1,245										
48300300	PORTLAND CEMENT CONCRETE SHOULDERS 8"	SQ YD	3,688	3,688										
48301000	PROTECTIVE COAT	SQ YD	3,688	3,688										
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	2		1	1								
50104400	CONCRETE HEADWALL REMOVAL	EACH	3	3										
50105220	PIPE CULVERT REMOVAL	FOOT	102	102										
50157300	PROTECTIVE SHIELD	SQ YD	554		210	344								
50200100	STRUCTURE EXCAVATION	CU YD	2,268		687	1,581								
50300225	CONCRETE STRUCTURES	CU YD	960.0		293.4	666.6								
50300255	CONCRETE SUPERSTRUCTURE	CU YD	1,040.3		462.9	577.4								
50300260	BRIDGE DECK GROOVING	SQ YD	2,738		1,204	1,534								
50300280	CONCRETE ENCASEMENT	CU YD	21.7		7.0	14.7								
50300300	PROTECTIVE COAT	SQ YD	3,392		1,466	1,926								
50500505	STUD SHEAR CONNECTORS	EACH	11,025		5,400	5,625								
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	365,980		159,370	206,610								
50800515	BAR SPLICERS	EACH	2,731		1,183	1,548								
51100100	SLOPE WALL 4 INCH	SQ YD	1,728		809	919								
51201600	FURNISHING STEEL PILES HP12X53	FOOT	2,640			2,640								
51201610	FURNISHING STEEL PILES HP12X63	FOOT	3,076		3,076									
51202305	DRIVING PILES	FOOT	5,716		3,076	2,640								
51203600	TEST PILE STEEL HP12X53	EACH	4			4								
51203610	TEST PILE STEEL HP12X63	EACH	4		4									
51204650	PILE SHOES	EACH	23			23								
51500100	NAME PLATES	EACH	2		1	1								
52000110	PREFORMED JOINT STRIP SEAL	FOOT	184			184								
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	12			12								
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	6			6								

**LEGEND:**

\* SPECIALTY ITEMS

**SHEET NO. 2 OF 5**

FILE NAME =	USER NAME = keysrb	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ci:\pwwork\p\idot\keysrb\d0101450\0570520-shs-500.DGN		DRAWN -	REVISED -			55	(57-7HB-2 & 57-7HB-1)BR	MCLEAN	153	4
 Johnson, Depp & Outsenberry CONSULTING ENGINEERS Springfield, Illinois	PLOT SCALE = 20.0000 / IN.	CHECKED -	REVISED -		SCALE:	SHEET NO. OF SHEETS STA. TO STA.		FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT		
	PLOT DATE = 8/17/2010	DATE -	REVISED -					CONTRACT NO. 70520		